



Contents

	Page
Taxonomic studies on the genus <i>Glyphodes</i> Guenee (Lepidoptera: Crambidae: Spilomelinae) from Karnataka, India <i>P. Maheswara Reddy and M. Shankara Murthy</i>	241
Influence of spinosad on the reproductive potential of <i>Tribolium castaneum</i> (Herbst), (Coleoptera: Tenebrionidae) infesting wheat <i>Umme Habiba, Wahedul Islam and Selina Parween</i>	249
Relative abundance and foraging activity of hymenopteran pollinators in cucurbitaceous vegetables <i>Erra Harisha and S. Shanas</i>	259
On a new species of <i>Neoceratobaeus</i> Rajmohana (Hymenoptera: Scelionidae) from India <i>P. Sunita and K. Rajmohana</i>	269
Occurrence of multiple nest entrance in the stingless bee <i>Tetragonula travancorica</i> (Hymenoptera: Meliponini) <i>P. Faseeh and S. Shanas</i>	275
SHORT COMMUNICATION	
Influence of wind direction on parasitization behaviour of <i>Trichogramma chilonis</i> Ishii (Hymenoptera: Trichogrammatidae) in brinjal ecosystem <i>P. Dominic Manoj, G. Ravi and M.I. Manivannan</i>	283

Evaluation of pongamia oil soap against leaf hopper, <i>Amrasca biguttula biguttula</i> (Ishida) infesting okra <i>Anu Thomas and K. M. Sreekumar</i>	287
Effect of carbofuran on quantitative and qualitative alterations in haemolymph of larva of <i>Oryctes rhinoceros</i> L. (Coleoptera: Scarabaeidae) <i>V.S. Salini</i>	293
Bioefficacy of horticultural mineral oil against spider mite, <i>Tetranychus truncatus</i> Ehara (Prostigmata: Tetranychidae) on okra <i>Kavya Yadav, Haseena Bhaskar and Madhu Subramanian</i>	301
First report of <i>Aeolesthes holosericea</i> (Fabricius, 1787) (Cerambycidae: Lamiinae) from Goa, India <i>Parshuram S. Naik and S. V. More</i>	307
First report of incidence of eriophyid mite <i>Aceria</i> sp. on <i>Amaranthus</i> <i>K. M. Sreekumar, N. Srinivasa and R. Sivamoorthy</i>	309
First report of <i>Rinamba opacicollis</i> Cameron (Hymenoptera: Braconidae, Doryctinae) in India as parasitoid of coffee stem borer, <i>Xylotrechus quadripes</i> (Chevrolat) (Coleoptera: Cerambycidae) <i>A. Roobakkumar, H.G. Seetharama, P. Krishna Reddy, M.S. Uma and A. P. Ranjith</i>	311
Scorpion Hemocyte- Plasmocyte <i>U. H. Shah</i>	315



Taxonomic studies on the genus *Glyphodes* Guenee (Lepidoptera: Crambidae: Spilomelinae) from Karnataka, India

P. Maheswara Reddy^{*1} and M. Shankara Murthy²

¹Department of Entomology, University of Agricultural Sciences, College of Agriculture, Raichur 584-104, Karnataka, India; ²Department of Entomology, University of Agricultural Sciences, College of Agriculture, Bheemarayanagudi, 585-287, Karnataka, India.

Email: pasammaheswarareddy@gmail.com; smurthyent@gmail.com

ABSTRACT: The specimens collected and reared to an adult stage on their respective hosts utilized to characterize the species of the genus *Glyphodes* based on morphological and genital characters of adults, revealed three species of the genus *Glyphodes* and were documented from Karnataka viz., *Glyphodes caesalis* Walker, *Glyphodes pulverulentalis* Hampson and *Glyphodes vertumnalis* Guenee on jack-fruit, mulberry and jasmine, respectively. These three species differ morphologically in having entire body green colour in *G. vertumnalis*, abdomen with oblique lateral stripes in *G. pulverulentalis* wherein, *G. caesalis* having sub-marginal black edged patch on costa with four spots. In genitalia, uncus greatly curved and beak shaped in *G. vertumnalis*, uncus slim and slightly curved in *G. caesalis*, whereas in *G. pulverulentalis* uncus long, narrow and slightly curved with short setae at apex. © 2019 Association for Advancement of Entomology

KEY WORDS: Taxonomy, three species, *Glyphodes*, Genitalia

INTRODUCTION

The genus *Glyphodes* was established by Guenee in 1854. This genus is more varied, omnipresent and comprises of 187 species throughout the world. It is one of the most economically important genera comprising fruit borers, shoot borers, leaf webbers, leaf rollers etc. Twenty-five species have been recorded in the Southeast Asia and seventeen species in Australia (Robinson *et al.*, 1994; Shaffer *et al.*, 1996). In India, so far 22 species of the genus *Glyphodes* have been reported (Nuss *et al.*, 2003-2019). In Tamil Nadu, three species namely *G. bivitalis*, *G. caesalis* and *G. canthusalis* were

recorded by Fletcher (1914) and Nair (1970). Recently, Rathikannu and Chitra (2017) reported 6 species of *Glyphodes* viz., *G. bivitalis*, *G. caesalis*, *G. canthusalis*, *G. onychinalis*, *G. pulverulentalis* and *G. stolalis* from Tamil Nadu by relying on light trap collection. They have provided taxonomic description of genitalia with line diagram and a key. Above studies indicate that in India, the taxonomic studies on the genus *Glyphodes* were carried out by the researchers predominantly based on light trap collections and none of them made any efforts to associate *Glyphodes* species with their host plants. Hence, the description of a species reared from actual hosts

* Author for correspondence

is the need of the hour for accurate identification and authentication of its host. In this context, in the present investigation, an attempt was made to study the host-based taxonomy of the genus *Glyphodes*, which were collected and reared on their actual hosts. In the current paper, synonyms and taxonomic descriptions for the species of *Glyphodes* are provided with photographic illustrations of genitalia, wing venation and adult habitus. Further, an illustrated key is provided for easy identification of the species.

MATERIALS AND METHODS

To study the adult morphological and genital characters, the specimens already collected (Karnataka) and reared from their host plants at the Department of Agricultural Entomology, College of Agriculture, Bheemarayanagudi, University of Agricultural Sciences, Raichur 584-104, Karnataka, India were utilized. The morphological as well as genital characters of the adult Spilomelinae were studied following Hampson (1896), Clark (1941), Robinson (1976), Thomas (2007) and Nagaraj (2014) with the necessary modifications. Before dissection of genitalia, adult specimens were photographed. Adult structures such as forewing and hindwing, palpi and genitalia were photographed using Trinocular microscope with auto-montage (Leica M 205C).

RESULTS

Genus *Glyphodes* Guenee, 1854; type species: *Glyphodes stolalis* Guenee, 1854

= *Caloptychia* Hubner, 1825; type species: *Phalaena chrysialis* Stoll, 1790

= *Calliptychia* Agassiz, 1847; type species: *Phalaena luciferalis* Snellen, 1780

= *Morocosma* Lederer, 1863; type species: *Phalaena margaritaria* Clerck, 1764

Diagnosis: Labial palpi inverted, the 2nd joint broadly scaled in front, the 3rd porrect and lying along the hair on the 2nd joint; maxillary palpi triangularly scaled; frons rounded; tibiae with inner spur twice the length of the outer spur; tuft of hairs

in forewing of the male; costa much arched towards apex.

Wing venation similar in almost all the *Glyphodes* species, but the external markings on wings of each species differs. So, wing venation of each species not discussed here, instead general venation for all the species is given below.

Wing venation: Fore wing with vein R₅ marginally approaching to R₃₊₄; M₁ arises close towards vein R₅; M₃, M₂ arising from angle of cell; Cu_{1a} from below the angle of cell, Cu_{1b} before angle of cell; hind wing with vein Rs stalked with Sc+R₁; M₂ and M₃ closely approximated for short distance; Cu_{1b} before angle of cell.

***Glyphodes caesalis* walker, 1859;** type locality: Sri Lanka (Fig. 1 A-H)

= *Glyphodes assimilis* Rothschild, 1915; type locality: Indonesia, Papua

Description: Head brown; labial palpi white; abdomen dark brown with white at side; forewing yellowish brown; an oblique ante medial fuscous line; a large fuscous edged iridescent white patch in and below end of cell; fuscous disco-cellular edged iridescent scales below lower angle of cell; hindwing ground colour, iridescent white with a broad marginal band with fuscous line on its inner edge; fringe yellowish mixed with brown.

Male genitalia: Uncus long, slim, curved, dentate and hooked at apex with hairs; valva broad with hairs; costa sclerotized; harpe thorn-shaped and straight; sacculus half the length of valva, inner surface granulated and thick; saccus triangular and slender, pointed at apex; aedeagus short and stout with cornuti inside vesica at apex.

Female genitalia: Ovipositor slit cut open; anal papillae thick; both the apophyses short, posterior apophysis half the length of anterior apophysis; sub-genital plate small; ductus bursae fairly long and stout; corpus bursae spherical with a scar like signum on the anterior apex.

Materials examined: India: Karnataka: Bellary, 1♂, 07.iii.2017, reared on jackfruit, S. Murthy;




Figure 1. Genital and morphological characters of adult *Glyphodes caesalis* Walker
 (A. male; B. female; male genitalia, C. ventral view; D. dorsal view; E. aedeagus; F. female genitalia; G. sub-marginal black edged patch on outer margin with four spots; H. wing venation)




Figure 2. Genital and morphological characters of adult *Glyphodes pulverulentalis* Hampson

(A. male; B. female; male genitalia, C. ventral view; D. dorsal view; E. aedeagus; F. female genitalia; G. abdomen with oblique lateral stripes; H. wing venation)




Figure 3. Genital and morphological characters of adult *Glyphodes vertumnalis* Guenee
 (A. male; B. female; male genitalia, C. ventral view; D. dorsal view; E. aedeagus; F. female genitalia;
 G. male hind tibia with tuft of hairs on outer extreme region; H. wing venation)

Bellary, 1♂, 1♀, 06.iii.2017, reared on jackfruit, S. Murthy; Bellary, 1 ♂, 2♂, 15. Vi. 2012, reared on jack fruit, S. Murthy; Bellary, 2♂, 1♀, 17.vi. 2012, reared on jack fruit, S. Murthy.

Remarks: It feeds on jack fruit as a fruit borer. Externally, this can be easily discriminated from other species by the presence of a large sub-triangular medial black edged patch with black below it on inner margin, a post medial band formed of two irregular black edged patches with their inner and outer edged indented and sub-marginal black edged patch on costa with four spots on black suffusion extending from it to inner margin.

***Glyphodes pulverulentalis* Hampson 1896;** type locality: India (Fig. 2 A-H)

Description: General body thickly irrorated, striated with black; abdomen with oblique lateral stripes; anal tuft black with brown middle; forewing with all the markings obscured by the spots and striae, the antemedial, medial and post-medial bands broader and less irregular, the 2nd vein without disco-cellular spot on it, the 3rd with series of pale specks on its outer edge from vein 4 to inner margin; hindwing thickly striated, oblique black edged brown post-medial and sub-marginal bands almost meeting at a point near anal angle; cilia of both wings fuscous, with fulvous and brown lines at base.

Male genitalia: Uncus long and narrow, anterior tip enlarged and pointed, beak-shaped dorsally with short setae; tegumen longer than wide, sclerotized and arched; vinculum long, sclerotized; saccus long, U-shaped; valva long, membranous, apex broadly rounded; costa weakly sclerotized, dorsally fringed with long hairs; juxta narrow, sclerotized, arrow-like; phallus almost straight, vesica with long sclerotized bar with lateral spine-like projection; curved sclerotized hook-like cornutus.

Female genitalia: Ovipositor slit swollen; anal papillae thick; both the apophyses short, thin and tapering, posterior apophysis half the extent of anterior apophysis; ductus bursae fairly short and thick; corpus bursae spherical with a scar like signum.

Materials examined: India: Karnataka: Bellary, 2♂, 10.x.2017, reared on mulberry, Manjunath; Bellary, 1♂, 1♀, 06.x.2016, reared on mulberry, Manjunath; Bellary, 1♂, 01.x.2017, reared on mulberry, Manjunath; Bellary, 1♂, 2.x.2017, reared on mulberry; Manjunath.

Remarks: This is one of the leaf-webber species which sustains on mulberry. Morphologically, this can be easily differentiated from other species of *Glyphodes* by the presence of oblique lateral stripes on the abdomen.

***Glyphodes vertumnalis* Guenee, 1854;** type locality: India (Fig. 3 A-H)

= *Enchocnemi diafuscitibia* Warren, 1896; type locality: Indonesia, Maluku, Tanimbar Islands

= *Margaronia herbidalis* Walker, 1866; type locality: Indonesia, Maluku, Seram

= *Margaronia melanuralis* Walker, 1866; type locality: Indonesia, Flores

= *Margaronia morvusalis* Walker, 1859; type locality: Malaysia, Borneo, Sarawak

= *Margaronia phryneusalis* Walker, 1859; type locality: North India

= *Margaronia proximalis* Walker, 1866; type locality: Indonesia, Maluku, Makian; Sulawesi

= *Pachyarches tibialis* Moore, 1877; type locality: India, South Andamans

Description: Body green, neither of the wings fulvous; marginal specks often obsolescent; cilia fulvous; abdomen small and profuse; male having black anal tuft of hairs; female devoid of anal tuft of hairs on hind tibiae; male with black tuft of hairs on hind tibiae at outer margin and extremity; hindwing of male with the inward area compactly clothed below with clumps of yellowish hair.

Male genitalia: Uncus broad and greatly curved, bending forward giving a beak like appearance; gnathos equal to uncus and broad; base of the gnathos and uncus darken laterally; vinculum wide and V-shaped; coremata with long thick as well as

finehair; valvae small, broad, fan-like having chitinous hook-like clasper in the costal base; phallus equally long,

Female Genitalia: Ovipositor slit swollen, wide dorsally and tapered ventrally; anal papillae thick; apophyses short; anterior apophysis twice the length of posterior apophysis; sub-genital plate small, ductus bursae fairly long and thick; corpus bursae spherical with two triangular signa one on each side near the apex.

Materials examined: India: Karnataka: Gulbarga, Raddewadigi, 1♀, 05.ii.2015, reared on jasmine, Nagaharish; Gulbarga, Hattekuni, 1♀, 12.viii.2015, reared on jasmine, Nagaharish; Yadgir, Bgudi, 4♂, 20.iv.2013, at light, S. Murthy; Gulbarga, Raddewadigi, 1♂, 15.x.2015, reared on jasmne, Nagaharish; Yadgir, B gudi, 5♂, 1♀, 03.xii.2012, jasmine, S. Murthy; Yadgir, B gudi, 1♂, 4.ix.2012, at light, S. Murthy; Yadgir, B gudi, 1♂, 16.vii.2012, jasmine, S. Murthy; Yadgir, B gudi, 1♂, 18.vii.2012, jasmine, S. Murthy.

Remarks: *Glyphodes vertumnalis* Guenee intently looks like *G. marginata* Hampson. Both are recognized by wing character. In *G. marginata* Hampson, wings are fulvous; however, in *G. vertumnalis* Guenee wings are not fulvous.

An illustrated key to *Glyphodes* species

1. Moth green coloured, male hind tibia enclosed with tuft of hairs on outer extreme margin, male genitalia with hook like clasper at base of costa, bursa copulatrix with two triangular signum near the apex.....*Glyphodes vertumnalis* Guenee (Fig. 3. A, B, C, D, E, F & G)
- Moth straw-yellow coloured, male hind tibia without tuft of hairs on the outer extreme margin, male genitalia without clasper at base of costa, bursa copulatrix without two triangular signum near the apex.....2
2. Abdomen marked with lateral oblique stripes; both apophysis small, phallus slim and long; ductus bursae thin and narrow.....

.....*Glyphodes pulverulentalis* Hampson (Fig. 2. C, D, E, F & G)

- Abdomen marked without lateral oblique stripes; anterior apophysis larger than posterior apophysis, phallus stout and short, ductus bursae thick and wide ...*Glyphodes caesalis* walker (Fig. 1. C, E, F & G)

In the present investigation, three species of the genus *Glyphodes* were identified with *G. caesalis* on jack fruit, *G. pulverulentalis* on mulberry and *G. vertumnalis* on jasmine. The taxonomic descriptions for these species were provided with photographic illustrations of genitalia, wing venation and adult habitus. An illustrated key was also provided for the same for easy identification of the species. Further, current taxonomic status of each species was given.

ACKNOWLEDGMENTS

Authors are grateful to Dr. C. A. Viraktamath, Department of Entomology, University of Agricultural Sciences, Bengaluru, India, and Dr. A. Prabhuraj, Professor and Head, Department of Entomology, University of Agricultural Sciences, College of Agriculture, Raichur, India, for their constant encouragement, constructive suggestions and motivation to carry out research work on Pyraloidea. We thank Alma Solis (USA) and Bernard Landry (Switzerland) for providing literature.

REFERENCES

- Clark G.J.F. (1941) The preparation of slides of the genitalia of Lepidoptera. Bulletin of Brooklyn Entomological Society 36.
- Fletcher T.B. (1914) Some South Indian Insects. Indian Agricultural Research Institute, New Delhi, India. 565 pp.
- Guenee M.A. (1854) Historie Naturelle des Insectes, Species General des Lepidopteres. Paris, 446 pp.
- Hampson G.F. (1896) The fauna of British India including Ceylon and Burma. Moths-Taylor and Francis Limited. 594 pp.
- Nagaraj S.K. (2014) Faunistic studies on Pyraloidea fauna associated with cereals in Hyderabad-Karnataka

- region. M. Sc. Thesis, University of Agricultural Sciences, Raichur.
- Nair M.R.G.K. (1970) Insects and Mites of Crops in India. New Jack Printing Works Private Limited, Bombay. 404 pp.
- Nuss M., Landry B., Mally R., Vegliante F., Tranker A., Bauer F., Hayden J., Segerer R., Schouten R., Li H., Trofimova T., Solis M.A., Prins J.D. and Speidel W. (2003–2019) Global information system on Pyraloidea. - www.pyraloidea.org
- Rathikannu S. and Chitra N. (2017) Genitalia study on the genus *Glyphodes* (Crambidae: Spilomelinae) in Tamil Nadu, India. Entomon 42 (2): 145–152.
- Robinson G.S. (1976) The preparation of slides of Lepidoptera genitalia with special reference to the microlepidoptera. Entomological Gazette 27: 127–132.
- Robinson G.S., Tuck K.R. and Shaffer M. (1994) A field Guide to the smaller Moths of South-east Asia. In: *Pyralidae* IV (Eds. Robinson G.S., Tuck K.R. and Shaffer M.), Malaysian Nature Society, Malaysia, Kuala Lumpur, pp 146–154.
- Shaffer M., Nielsen E.S. and Horak M. (1996) Checklist of the Lepidoptera of Australia. In: *Pyralidae* IV (Eds. Nielsen, E.S., Edwards, E.D. and Rangsi, T.V.), Monographs on Australian Lepidoptera, Canberra. pp 67–199.
- Thomas E.W. (2007) Preparing wing slides for microlepidoptera. Entomological Society of Washington. pp 30–31.

(Received September 24, 2019; revised ms accepted December 11, 2019; published December 31, 2019)



Influence of spinosad on the reproductive potential of *Tribolium castaneum* (Herbst), (Coleoptera: Tenebrionidae) infesting wheat

Umme Habiba¹, Wahedul Islam^{1*} and Selina Parween²

¹Institute of Biological Sciences, University of Rajshahi*, ²Department of Zoology, University of Rajshahi, Bangladesh. Email: mwislam18@gmail.com

ABSTRACT: Spinosad of different concentrations were screened against *Tribolium castaneum* (Herbst) reared on four local wheat varieties to observe the effects on reproductive potentials for two successive generations. The lowest number of eggs laid was 119 (23.80 ± 0.97) observed in Shatabdi-21 (S-21) in 45 d in F_1 and 15 (3.00 ± 0.71) in 15 d in F_2 generation when treated at $0.12 \mu\text{l/g}$ of spinosad. Spinosad at all concentration totally inhibited egg laying or oviposition rate on day 45 in all wheat varieties except P-24 variety in F_1 generation. The lowest fertility was found in Shatabdi-21 variety as 12.61 percent in F_1 and 6.67 percent in F_2 generation at $0.12 \mu\text{l/g}$. The latent effect of spinosad on number of eggs, larva, pupa and adult obtained in Shatabdi-21 as 2.00 ± 0.32 , 0.80 ± 0.37 , 0.40 ± 0.40 and 0.20 ± 0.20 at $0.12 \mu\text{l/g}$ of spinosad in F_2 generation. There was no significant difference between the number of males and females in F_2 generation wheat varieties. Spinosad ultimately reduced the fecundity, fertility and decreased the egg to adult survivability in four wheat varieties compared to control and F_1 and F_2 generations. Results of the research revealed that comparatively higher concentrations of spinosad that used in this study would potentially control development and reproductive potentiality of *T. castaneum* in wheat varieties.

© 2019 Association for Advancement of Entomology

INTRODUCTION

In a recent post-harvest compendium *T. castaneum* is reported as most common secondary pest of all plant commodities in store throughout the world (Babarinde and Adeyemo, 2010; Stejskal *et al.*, 2014). This external feeder pest makes serious damage on flour and over whelms cereal particularly at larval and adult stages (Baldwin and Fasulo, 2004) making it unfit for human intake. This insect causes substantial loss in storage because of its high reproductive potential (Campbell and Runnion, 2003). Diet type and initial population density may also have an

immediate or indirect impact on the reproduction, development rate, number of progeny and body weight of *T. castaneum* (Longstaff, 1995; Assie *et al.*, 2008). Shukla and Upadhyay (2011) noticed that the progeny production rate of *T. castaneum* was very excessive and the fourth instar larvae were enormously energetic in rainy season causing very excessive infestation where in adults could live for 2 years or greater in the course of duration the female producing nearly 1000 eggs.

Spinosad is an insecticide product from Dow Agro Sciences (Indianapolis, Indiana, USA) based on

* Author for correspondence

chemical compounds of a soil bacterium *Saccharopolyspora* was discovered in 1985 (Mertz and Yao, 1990). Hertlein *et al.* (2011) stated that spinosad has an aggregation of high potency, minimum mammalian toxicity, and secure environmental profile which is unique among existing products recently used for stored-grain protection. The mode of action of spinosad is characterized by involving the disruption of nicotinic acetylcholine receptors and γ -amino butyric acid (GABA)-gated ion channels of insect nervous systems (Salgado and Sparks, 2005; Kirst, 2010; Sparks *et al.*, 2012). Spinosad must be sprayed directly into the eggs, but larvae and adults can be efficaciously dosed through contact but it is most effective when ingested (Cleveland *et al.*, 2001). Spinosad is more toxic through ingestion than via contact (Athanasios and Kavallieratos, 2014).

Wheat is the major and second staple food worldwide and Bangladesh respectively. Different wheat varieties were developed in different countries, among which the factors like pest resistant and insecticide susceptible varieties gaining importance from the point of view of reducing infection stress during post-harvest storage. In this research four local varieties of wheat were used to screen out the variety that is susceptible to spinosad treatment without leaving any hazardous effect on human health. The objective of this experiment was to evaluate the effect of different concentrations of spinosad on the reproductive potentials of *T. castaneum* for two successive generations as a result of contact action to eggs and contact and gustatory effects on the adults of *T. castaneum* in four wheat varieties local of Bangladesh.

MATERIALS AND METHODS

Culturing of *T. castaneum*: *T. castaneum* beetles were obtained from the stock culture maintained in the control temperature (CT) room, at Entomology and Insect Biotechnology Laboratory, Institute of Biological Sciences, University of Rajshahi, Bangladesh. The standard food medium, mixture of whole wheat flour with powdered Brewer's Yeast (19:1) (Park and Frank, 1948; Park, 1962) was used as a food medium throughout the mass

culture of *T. castaneum*. Both flour and yeast were previously passed through a 250 μ m sieve sterilized at 60°C for six hours in an oven, and kept at least for 15 days before use, to equilibrate the moisture content with the environment (Khan, 1981; Mondal, 1984).

Mass cultures were maintained in plastic containers (2.5 liters) in a Control Temperature (CT) room at 30 \pm 1°C and 70 \pm 5% RH providing 250g of wheat flour /container. About 500 adults of *T. castaneum* were introduced into each container. The cultures were checked at regular intervals and eggs and larvae were separated to avoid cannibalism. A crumpled filter paper was placed inside each container for easy movement of the beetles. Mouth of the container was covered with muslin cloth using a rubber band, to prevent the possible contamination and escape of insects (Mondal and Parween, 1997). A series of stock culture were maintained for the constant supply of these insects to conduct different experiments.

Preparation of spinosad concentrations:

Spinosad is light grey to white in colour with slight odour stale water. About 500ml of spinosad (PRN-MAPP-12054, cafno 20012-019, Lot No-3068404) was obtained from Dow Agro Sciences, UK. Concentration of spinosad was 120g a.i./l.

Spinosad measuring 0.72 μ l was pipetted in a glass vial and added 6ml distilled water properly by using 2ml syringe. The vial was shaken vigorously for thorough mixing of spinosad and water serving as stock having 0.12 μ l spinosad/ml of other desired concentrations of spinosad (0.06 and 0.03 μ l/g) were prepared by serial dilution by taking 1 ml of solution and adding 2 ml distilled water in each step.

Wheat varieties: Infestation free four wheat varieties viz., BARI-26, BARI-28, Prodip-24 and Shatabdi-21 (B-26, B-28, P-24 and S-21) were used for the experiment. The grains were washed with water and dried at room temperature before adjusting their moisture content to 13.5 by adding tap water, cleaned by sieving through 500 micrometer aperture sieve and sterilized in an oven at 60°C for 8 h. After sterilization wheat grains were

kept in separate plastic containers according to variety. Grains were partially broken down by the hand blender before further use.

Bioassay: The efficacy of spinosad against reproductive potentiality of *T. castaneum* was investigated by dietary exposure termed Treated Food Method (TEM) (Talukder and Howse, 1994). Newly emerged 50 pupae from culture were sexed by the electric microscopic examination of the exo-genital process. In female the structure of exo-genital lobes are larger than male. The genital papillae of females are pointy but male's genital papillae are stubby, conjoined. Female papillae resemble fingers like 2 combined thumbs (Halstead 1963). After adult emergence, 20 male and females were paired up to 15 days and collected about 350 numbers of freshly eggs with the help of microscope. Two grams of each wheat variety was soaked with different concentrations of spinosad as treated wheat and 2gms of each wheat variety was soaked with distilled water as for control or untreated wheat. About 20 eggs were placed on each petri-dish and provided with 2gms treated wheat and untreated wheat of each variety which was changed after every three days. The larvae were checked regularly until they emerged as pupae. Pupae from each treated concentration were paired by microscopic examination of the exo-genital process. After 48 h emerged adults were paired and 5 pairs of beetles from each concentration were placed in separate petri-dishes and provided with 2gms of treated wheat of each variety of different concentrations for egg collection.

Eggs from each pair were collected after three days up to a 45 day. Total number of eggs laid by each pair up to 45 day was recorded and daily egg production/female was determined. Fertility of the eggs was assessed by the how many larvae were recovered from the total number of eggs up to 45 days of 5 pairs adults into 100 was recorded. The ultimate effects of the spinosad were assessed by recording the total number of larvae produced, recoveries of total pupae and adults up to 45 d. About fifty pupae were sexed and the males and females were kept separately again.

After emergence, adults were paired again (5 pairs) and kept separately. Similarly, the total number of eggs laid by each pair up to 15 days, fertility of these eggs, the total number of larvae produced, and recoveries of pupae and adults were recorded. The second generation (larvae to adults) was developed on untreated wheat. A similar set of experiment was conducted with same number of beetles in untreated wheat, as the control batch. All the experiments were conducted at CT room ($30\pm 1^\circ\text{C}$) and 75% RH and replicated thrice. Data obtained from the experiments were analyzed using the Analysis of variance (Factorial) using SPSS version 20. Means were compared by Tukey's test, accepting significant differences at $P < 0.05$. Sex ratios were determined by χ^2 test ($P > 0.05$).

RESULTS AND DISCUSSION

i) Effect on fecundity in two successive generations

The total number of egg laid by *T. castaneum* ranged from 656 to 1125 in control and 119 to 761 in treatments in F_1 and 163 to 384 in control and 15 to 145 in treatments in F_2 generation. The lowest number of eggs laid was 119 (23.80 ± 0.97) observed in S-21 up to 45 days in F_1 and 15 (3.00 ± 0.71) up to 15 days in F_2 generation at $0.12\mu\text{l/g}$ and the highest number of egg was found in P-24 as 761 (152.20 ± 2.60) in F_1 and 145 (29.00 ± 1.30) in F_2 generation at $0.03\mu\text{l/g}$ concentration (Tables 1 and 2).

ii) Effect on fertility of the eggs in two successive generations

Spinosad at all concentrations reduced fertility of the laid eggs in a concentration- dependent manner in F_1 and F_2 generations in all wheat varieties (Figure 1). The percentage of fertility of eggs ranged from 74.70 to 89.67 percent in untreated wheat and 12.61 to 64.91 percent in treatments in F_1 generation. The lowest fertility was noted in S-21 variety as 12.61 percent at $0.12\mu\text{l/g}$ in F_1 generation. In F_2 generation, the percentage of fertility ranged from 69.94 to 85.16 percent in untreated wheat and 6.67 to 45.52 percent in treatments. The same trend was also observed in F_2 generation where the lowest fertility was recorded in S-21 variety as 6.67 percent.

iii) Latent effect of spinosad on the life stages produced in second generations

The latent effect of different concentrations of spinosad at different life stages and sex ratio of *T. castaneum* deviated from 1:1 in F_2 generation; the effects were concentration-dependent and in all wheat varieties (Table 2). The mean number of eggs production ranged from 32.60 ± 1.47 to 76.80 ± 1.39 in control and 3.00 ± 0.71 to 29.00 ± 1.30 in treatments. Out of four wheat varieties, the lowest number of eggs was produced in S-21 as 3.00 ± 0.71 at $0.12 \mu\text{l/g}$ of spinosad compared with control in F_2 generation (Table 2).

Larval mortality was found to be very high especially in spinosad at $0.12 \mu\text{l/g}$ concentration. Few larvae became black and shriveled, failed to shed the old cuticle and died while hatching after 2-3 days. Larval survival ranged from 22.80 ± 1.02 to 65.40 ± 0.86 nos in control and 0.20 ± 0.20 to 13.20 ± 0.86 nos in treatments. The lowest number of larva was recorded in S-21 as 0.20 ± 0.20 at $0.12 \mu\text{l/g}$ compared with the control and rest of other concentrations (Table 2). The mean number of pupal survival ranged from 20.80 ± 1.02 to 50.20 ± 1.80 nos in control and 0.00 ± 0.00 to 9.00 ± 0.711 nos in treatments. The lowest number of pupa was recorded in S-21 as 0.00 ± 0.00 at $0.12 \mu\text{l/g}$ compared with the control and other concentrations (Table 2).

The mean number of adult survival ranged from 17.80 ± 0.86 to 41.60 ± 1.50 nos in control and 0.00 ± 0.00 to 5.60 ± 0.40 nos in treatments. The lowest number of adult was observed in S-21 as 0.00 ± 0.00 at $0.12 \mu\text{l/g}$ of spinosad compared with the control and other concentrations. Few adults became black and shriveled (Table 2). The sex ratios for the treatment variables did not differ significantly from each other in any generation as judged by χ^2 test ($P > 0.05$) (Table 3).

Results of the present experiments have demonstrated that spinosad affected egg to adult survivability and reproductive potentiality of *T. castaneum* in F_1 (45 d) and F_2 (15 d) generations. There was significant decrease in egg number of *T. castaneum* laid on different wheat varieties. The

lowest number of eggs laid (119) in 45 d was observed in S-21 in F_1 generation; and that was 15 laid in 15 d in F_2 generation; at highest concentration $0.12 \mu\text{l/g}$. Egg laying was decreased in all wheat varieties and in F_1 generation females laid small number of eggs after 33 d; and at highest concentration was totally failed in the later part of oviposition period.

Spinosad at $0.12 \mu\text{l/g}$ concentration totally inhibited egg laying on day 45 in F_1 and day 15 in F_2 generation in all wheat varieties. Absence of adequate published literature on the spinosad toxicity on the fecundity and oviposition rate of stored product insects, make the present result quite difficult to compare. Similarly fertility rate lowest in S-21 variety as 12.61 percent in F_1 and 6.67 percent in F_2 generation at $0.12 \mu\text{l/g}$ concentration. Accordingly, lowest number of larva, pupa and adult was recorded in S-21 at $0.12 \mu\text{l/g}$ of spinosad in F_2 generation.

Bajracharya *et al.* (2013) reported that spinosad caused high mortality and complete progeny suppression of *Rhizopertha dominica* at five storage periods (2, 84, 168, 252, and 336 d) which was in agreement with Bonjour *et al.* (2006) who demonstrated that stored wheat treated with 1 ppm of spinosad completely controlled *R. dominica* adults and progeny production for all the post treatment storage periods (28, 84, 182, 252, 336, and 672 d). Subramanyam *et al.* (2012) reported that complete suppression in *R. dominica* (0.0 ± 0.0) and near complete suppression of adult progeny in *T. castaneum* (1.2 ± 1.0 and 0.6 ± 0.4) achieved on spinosad-treated wheat (spinosad I and spinosad II) after 42 days. The author additionally reported that no *Plodia interpunctella* adults have been found on liquid spinosad treated wheat after 42 days. These findings are consistent with Huang *et al.* (2004) who stated that spinosad was highly toxic against *P. interpunctella* inhibiting larval survivability and adult emergence on wheat and maize. Adult mortality of *Cryptolestes ferrugineus*, *R. dominica*, *Oryzaephilus surinamensis*, *S. oryzae*, and *S. zeamais* was found as $>98\%$ at 1 and 2 mg of spinosad/kg on corn after 12 days. Spinosad absolutely suppressed egg-to-larval




Fig..1 Effect of spinosad on the fertility in F₁ (A) and F₂ (B) generations of *T. castaneum* in wheat varieties.

survival at ≥ 0.5 mg/kg after 21 days and egg-to-adult emergence of *P. interpunctella* after 49 days, whereas 16 percent adults of *T. castaneum* survived at 1 mg of spinosad/kg of flour after 12 days. Spinosad at 1 or 2 mg/kg provided complete or close to entire suppression of progeny production and kernel damage of all species after 49 days (Huang and Subramanyam, 2007). The present

findings are more or less consistent with above results. There was no significant deviation was found in sex ratios at any concentrations of spinosad, wheat varieties and F generations.

Spinosad (Tracer®) showed powerful toxicity against the adults of *R. dominica* and *S. oryzae* and maximum mortality occurred at 250 and 80 ppm

Table 1. Latent effects of spinosad on the life stages of F₁ generation of *T. castaneum* in different wheat varieties (N=5 pairs).

Wheat varieties	Concentrations (µl/g)	Total no. and Mean ± SE							
		Eggs		Larvae		Pupae		Adults	
B-26	Control	1075	215.00±1.30a	964	192.80±1.93a	839	167.80±3.32a	655	131.00±3.32a
	0.03	579	115.80±1.69b	359	71.80±2.31b	314	62.80±2.24b	205	41.00±1.18b
	0.06	352	70.40±1.17c	176	35.20±2.31c	111	22.20±1.83c	65	13.00±1.10c
	0.12	265	53.00±1.22d	101	20.20±2.15d	62	12.40±1.44d	43	8.60±1.17d
B-28	Control	761	152.20±2.01a	593	118.60±1.81a	424	84.80±3.57a	328	65.60±2.38a
	0.03	380	76.00±1.41b	23	146.20±2.35b	14	929.80±2.84b	76	15.20±1.83b
	0.06	174	34.80±2.18c	58	11.60±1.33c	39	7.80±1.16c	17	3.40±0.68c
	0.12	130	26.00±0.89d	26	5.20±0.58d	14	2.80±0.37d	3	0.60±0.24d
P-24	Control	1125	225.00±2.21a	990	198.00±1.76a	735	147.00±3.74a	553	110.60±3.59a
	0.03	761	152.20±2.60b	494	98.80±4.67b	337	67.40±6.19b	220	44.00±6.96b
	0.06	405	81.00±0.45c	219	43.80±1.39c	141	28.20±2.11c	80	16.00±1.87c
	0.12	300	60.00±1.58d	120	24.00±1.30d	69	13.80±0.73d	52	10.40±0.81d
S-21	Control	656	131.20±3.92a	490	98.00±1.30a	368	73.60±3.39a	271	54.20±3.22a
	0.03	331	66.20±2.15b	165	33.00±1.70b	98	19.60±1.72b	44	8.80±1.07b
	0.06	185	37.00±2.10c	49	9.80±0.37c	25	5.00±0.55c	12	2.40±0.60c
	0.12	119	23.80±0.97d	15	3.00±0.32d	10	2.00±0.32d	2	0.40±0.24d
Source	DF	F	Sig.*	F	Sig.*	F	Sig.*	F	Sig.*
Varieties	3	164.58***	0.00	187.22***	0.00	146.68***	0.00	65.72***	0.00
Concentrations	3	1278.25***	0.00	1790.61***	0.00	2120.40***	0.00	1117.38***	0.00
Varieties *									
Concentrations	9	50.95***	0.00	96.15***	0.00	72.95***	0.00	39.84***	0.00

In a column means with same letter do not significantly differed from each other within varieties at 0.05% level (Tukey's test).
 Note: *Significant value, *** 0.001 = P < 0.001.

Table 2. Latent effects of spinosad on the life stages of F₂ generation of *T. castaneum* in different wheat varieties (N=5 pairs).

Wheat varieties	Total no. and Mean±SE									
	Concentrations (µl/g)		Eggs		Larvae		Pupae		Adults	
B-26	Control		343 68.60±0.93a		257 51.40±1.63a		207 41.40±0.81a		175 35.00±1.00a	
	0.03		123 24.60±2.01b		54 10.80±0.80b		35 7.00±0.55b		21 4.20±0.37b	
	0.06		70 14.00±1.22c		27 5.40±0.40c		13 2.60±0.24c		6 1.20±0.37c	
	0.12		28 5.60±0.51d		4 0.80±0.20d		3 0.60±0.24d		2 0.40±0.24c	
B-28	Control		211 42.20±1.77a		151 30.20±1.43a		138 27.60±1.17a		109 21.80±2.44a	
	0.03		123 24.60±2.24b		52 10.40±1.17b		30 6.00±0.55b		18 3.60±0.51b	
	0.06		38 7.60±0.74c		6 1.20±0.20c		5 1.00±0.32c		1 0.20±0.20c	
	0.12		20 4.00±0.83d		2 0.40±1.75d		0 0.00±0.00d		0 0.00±0.00c	
P-24	Control		384 76.80±1.39a		327 65.40±0.86a		251 50.20±1.80a		208 41.60±1.50a	
	0.03		145 29.00±1.30b		66 13.20±0.86b		45 9.00±0.71b		28 5.60±0.40b	
	0.06		88 17.60±0.81c		29 5.80±0.66c		16 3.20±0.37c		8 1.60±0.24c	
	0.12		40 8.00±0.84d		7 1.40±0.40d		3 0.60±0.24d		2 0.40±0.24c	
S-21	Control		163 32.60±1.47a		114 22.80±1.02a		104 20.80±1.02a		89 17.80±0.86a	
	0.03		100 20.00±0.95b		36 7.20±0.86b		18 3.60±0.40b		12 2.40±0.24b	
	0.06		285.60±0.40c		30.60±0.24c		10.20±0.45c		00.00±0.00c	
	0.12		15 3.00±0.71d		1 0.20±0.20d		0 0.00±0.00d		0 0.00±0.00c	
Source		DF	F	Sig.*	F	Sig.*	F	Sig.*	F	Sig.*
Varieties		3	164.58***	0.00	187.22***	0.00	146.68***	0.00	65.72***	0.00
Concentrations		3	1278.25***	0.00	1790.61***	0.00	2120.40***	0.00	1117.38***	0.00
Varieties *										
Concentrations		9	50.95***	0.00	96.15***	0.00	72.95***	0.00	39.84***	0.00

In a column means with same letter do not significantly differed from each other within varieties at 0.05% level (Tukey's test). Note: *Significant value, *** 0.001 = P < 0.001.

Table 3. Effect of spinosad on the sex ratio of the 2nd generation of *T. castaneum* in different wheat varieties (N=5 pairs).

Wheat varieties	Concentrations (µl/g)	Male No. (%)	Female No. (%)	Sex ratio (Male: Female)	÷ ² value
B-26	Control	91(43.96)	116(56.04)	1:1.27	1.81 ^{NS}
	0.03	14(40.00)	21(60.00)	1:1.50	1.76 ^{NS}
	0.06	9(69.23)	4(30.77)	1:0.44	3.61 ^{NS}
	0.12	3(100.00)	0(0.0)	0:0.00	0.00 ^{NS}
B-28	Control	79(57.25)	59(42.75)	1:0.75	2.42 ^{NS}
	0.03	14(46.67)	16(53.33)	1:1.14	2.11 ^{NS}
	0.06	4(80.00)	1(20.00)	1:0.25	0.00 ^{NS}
	0.12	0(0.0)	0(0.0)	0:0.00	0.00 ^{NS}
P-24	Control	116(46.22)	135(53.78)	1:1.16	3.72 ^{NS}
	0.03	25(55.56)	20(44.44)	1:0.80	1.80 ^{NS}
	0.06	10(62.50)	6(37.50)	1:0.60	2.84 ^{NS}
	0.12	2(66.67)	1(33.33)	1:0.50	0.00 ^{NS}
S-21	Control	53(50.96)	51(49.04)	1:0.96	1.45 ^{NS}
	0.03	9(50.00)	9 (50.00)	1:1.00	2.20 ^{NS}
	0.06	1(100.00)	0(0.0)	1:0.00	0.00 ^{NS}
	0.12	0(0.0)	0(0.0)	0:0.00	0.00 ^{NS}

Note: NS= Not significant at 5% level.

spinosad after 20 days exposure for *R. dominica* and *S. oryzae*. These results inspired the usage of Tracer® as an safe agent for insect pests' management (Sadeghi and Ebadollahi, 2015). Huang and Subramanyam (2007) reported that progeny production was 28.0±4.2 in control treatment after 49 days and decreased by 91 percent at 0.5 mg/kg and >96 percent at 1 and 2 mg/kg for *T. castaneum*. These consequences certify our results that spinosad is powerful in suppressing progeny production and there is an inverse relationship between progeny production and spinosad concentrations.

The present result revealed that higher concentrations of spinosad were highly effective against progeny production of *T. castaneum* in all wheat varieties in both generations. Among the wheat varieties used S-21 was found to give best result. So, it is revealed that spinosad inhibits the potentiality of *T. castaneum* at 0.12µl/g, and the

latent effect transmitted to the next generation. It ultimately reduced the fecundity, fertility and decreased the egg to adult survivability in four wheat varieties in F₂ generations. So, it can be said that effect of spinosad at higher concentrations could effectively control development and reproductive potentiality of *T. castaneum* in stored wheat.

REFERENCES

- Assie L. K., Brostaux Y. and Haubruge E. (2008) Density-dependent reproductive success in *Tribolium castaneum* (Herbst) (Coleoptera: Tenebrionidae). Journal of Stored Product Research 44: 285-289.
- Athanassiou C.G. and Kavallieratos N. G. (2014) Evaluation of spinetoram and spinosad for control of *Prostephanus truncatus*, *Rhyzopertha dominica*, *Sitophilus oryzae*, and *Tribolium confusum* on stored grains under laboratory tests. Journal of Pest Sciences 87: 469-483.

- Babarinde S.A. and Adeyemo Y.A. (2010) Toxic and repellent properties of *Xylopiiaethiopica* (Dunal) A. Richard on *Tribolium castaneum* Herbst infesting stored millets, *Pennisetum glaucum* (L.) R. Br. Archives of Phytopathology and Plant Protection 43: 810-816.
- Bajracharya N.S., Opit G.P., Talley J. and Jones C.L. (2013) Efficacies of Spinosad and a Combination of Chlorpyrifos-Methyl and Deltamethrin against Phosphine-Resistant *Rhyzopertha dominica* (Coleoptera: Bostrichidae) and *Tribolium castaneum* (Coleoptera: Tenebrionidae) on Wheat. Journal of Economic Entomology 106: 2208-2215.
- Baldwin R. and Fasulo T.R. (2004) Red and confused flour beetles-*Tribolium* sp. <http://creatures.ifas.ufl.edu/urban/beetles/red-flour-beetle.html>.
- Bonjour E.L., Phillips T.W. and Pitts J.T. (2006) Spinosad provides long-term protection for stored wheat. In: Lorini I, Bacaltchuk B, Beckel H, Deckers D, Sundfeld E, dos Santos J P, Biagi J D, Celaro J C, Faroni L R D A, Bortolini de O F L, Sartori M R, Elias M C, Guedes R N C, da Fonseca R G and Scussel V M (Eds.), Proceedings of the 9th International Working Conference for Stored-Product Protection, 15-18 October 2006. ABRAPOS, Campinas, São Paulo, Brazil. pp. 1189-1193.
- Campbell J.F. and Runnion C. (2003) Patch Exploitation by female Red flour beetles, *Tribolium castaneum*. Journal of Insect Science 3: 20.
- Cleveland C. B., Mayes M.A. and Cryer S. A. (2001) An ecological risk assessment for spinosad use on cotton. Pest Management Science 58: 70-84.
- Halstead D.G.H. (1963) External sex differences in stored-products Coleoptera. Bulletin Entomological Research 54: 119-134.
- Hertlein M.B., Thompson G.D., Subramanyam B. and Athanassiou C.G. (2011) Spinosad: A new natural product for stored grain protection. Journal of Stored Product Research 47: 131-146.
- Huang F. and Subramanyam B. (2007) Effectiveness of spinosad against seven major stored-grain insects on corn. Insect Science 14: 225-230. Journal of Compilation © Institute of Zoology, Chinese Academy of Sciences.
- Huang F., Subramanyam B. and Toews M.D. (2004) Susceptibility of laboratory and field strains of four stored-product insect species to spinosad. Journal of Economic Entomology 97: 2154-2159.
- Khan A.R. (1981) The combined action of organophosphorus insecticides and microsporidians on *Tribolium castaneum*. Unpublished Ph D Thesis, University of Newcastle upon Tyne, UK. 162 pp.
- Kirst H. A. (2010) The spinosyn family of insecticides: realizing the potential of natural products research. Journal of Antibiotics 63: 101-111.
- Longstaff B. (1995) An experimental study of the influence of food quality and population density on the demographic performance of *Tribolium castaneum* (Herbst). Journal of Stored Product Research 31: 123-129.
- Mertz F.P. and Yao R.C. (1990) *Saccharopolyspora spinosa* sp. nov. isolated from soil collected in a sugar mill rum still. International Journal of Systematic Bacteriology 40: 34-39.
- Mondal K.A.M.S.H. (1984) A method of determining the larval instars of *Tribolium castaneum* Herbst (Coleoptera: Tenebrionidae). Laboratory Practice 33: 120-121.
- Mondal K.A.M.S.H. and Parween S. (1997) Laboratory culturing of flour beetles, *Tribolium* species. Tribolium Information Bulletin 37: 153-162.
- Park T. and Frank M. B. (1948) The fecundity and development of the flour beetles, *Tribolium confusum* and *Tribolium castaneum* at three constant temperatures. Ecology 29: 368-375.
- Park T. (1962). Beetles competition and population Science 138: 1369-1375.
- Sadeghi R. and Ebadollahi A. (2015) Susceptibility of *Rhyzopertha dominica* (F.) (Coleoptera: Bostrichidae) and *Sitophilus oryzae* (L.) (Coleoptera: Curculionidae) to Spinosad (Tracer®) as a eco-friendly Biopesticide. Ecologia Balkanica 7: 39-44.
- Salgado V. L. and Sparks T. C. (2005) The spinosyns: chemistry, biochemistry, mode of action and resistance. In: Gilbert L. I., Iatrou K. and Gill S. (Eds.), Comparative Insect Molecular Science 6: 137-173.
- Shukla G. S. and Upadhyay V. B. (2011) Economic Zoology. Rastogi. Publs. 487pp.
- Sparks T. C., Dripps J. E., Watson G. B. and Paroonagian D. (2012) Resistance and cross-resistance to the spinosyns –A review and analysis. Pesticidal Biochemistry Physiology 102: 1-10.

- Stejskal V., Aulicky R. and Kucerova Z. (2014) Pest control strategies and damage potentials of seed-infesting pests in the Czech stores-A review. *Plant Protection Science* 50: 165-173.
- Subramanyam B., Hartzer M. and Boina D. R. (2012) Performance of pre-commercial release formulations of spinosad against five storedproduct insect species on four stored commodities. *Journal of Pest Science* 85: 331-339.
- Talukder F. A. and Howse P. E. (1994) Efficacy of pithraj (*Aphanamixis polystachya*) seed extracts against stored-product pests. *Proceedings of 6th International Working Conference on stored-product Protection* 2: 848-852, Canberra, Australia.

(Received November 20, 2019; revised ms accepted December 15, 2019; published December 31, 2019)



Relative abundance and foraging activity of hymenopteran pollinators in cucurbitaceous vegetables

Erra Harisha¹ and S. Shanas^{*2}

¹Department of Agricultural Entomology, College of Agriculture, Vellayani, Thiruvananthapuram 695522, Kerala, India; ²AICRP on Honey bees & Pollinators, RARS (SZ), College of Agriculture, Vellayani, Thiruvananthapuram, 695522, Kerala, India. Email: harishaerra13@gmail.com

ABSTRACT: A study was conducted to investigate the diurnal activity patterns of hymenopteran pollinators in culinary melon and the dynamics of hymenopteran pollinators of five selected cucurbitaceous vegetables viz., culinary melon, bitter gourd, pumpkin and ridge gourd in 34 locations of Kerala from 06:00 h to 18:00 h with a cone type hand net. The study revealed that *Apis cerana indica* was dominant in culinary melon, pumpkin and ridge gourd and *Tetragonula travancorica* was dominant in bitter gourd and ash gourd, *A. cerana indica*, *T. travancorica* and *Halictus* sp. recorded highest foraging speed during 10:00 h to 11:00 h; *Ceratina hieroglyphica* and *Lasioglossum* sp. recorded highest foraging speed during 09:00-10:00 h; *T. travancorica*, *C. hieroglyphica* and *Lasioglossum* sp. recorded maximum foraging rate during 10:00 h to 11:00 h; *A. cerana indica* and *Halictus* sp. recorded highest foraging rate during 11:00-12:00 h and 09:00-10:00 h.

© 2019 Association for Advancement of Entomology

KEY WORDS: Pollinators, composition, relative abundance, diurnal activity, cucurbitaceous, foraging speed, foraging rate

INTRODUCTION

Insect pollinators play an important role in effecting optimum pollination of several crops and contribute to the raise of their productivity and quality. Their essentiality is more significant in crops like cucurbitaceous vegetables. Among the vegetable crops, cucurbits are cultivated extensively in India. The cucurbitaceous family comprises of cucumber, pumpkin, chow-chow, bitter gourd, bottle gourd, ridge gourd, ash gourd, watermelon, muskmelon, etc. Globally, the family cucurbitaceae comprises of 118 genera and 825 species. At present in India, cucurbits are cultivated in an area of 555,000 ha with a productivity of 9,912,000 MT and in Kerala

cucurbits are cultivated in an area of 2,970 ha with a productivity of 41,610 MT (NHB, 2018). FAO estimates show that, in India about 6% of the total vegetables produced are from eight species of cucurbitaceous vegetables. In India, studies have been conducted on some of the important cucurbit crops to record the insect visitors and to understand the pollinators diurnal activity.

Cucurbits being monoecious, bearing male and female flowers separately on the same plant, depends mainly on insects for pollination and also, their pollen grains being large and sticky, cannot be blown away by the wind. Hence, pollination by insects is essential to bear improved quality of fruits

* Author for correspondence

and seeds (Free, 1970; Mc Gregor, 1976). In cucurbitaceous vegetables, among all the pollinating insects, the honeybees are known to be the most efficient. For maximizing the yield of cross pollinated crops, utilization of pollinators especially honeybees are considered as one of the cheapest and eco-friendly approach (Free, 1970).

Grewal and Sidhu (1978) recorded that in Punjab, the most frequent visitors of bittergourd flowers were *Apis florea* F. and various species of Anthophoridae and Halictidae with 28, 10 and 5.2 per-cent, respectively. In Vellayani, Kerala, on sponge gourd the most abundant pollinator was *Tetragonula iridipennis* Smith (Mohan, 2000). Pateel and Sattagi (2007) observed that in Karnataka, *A. florea*, *Apis cerana* F. and *Apis dorsata* F. were the most abundant insect pollinators visiting cucumber in Rabi season.

In Kannur, Kerala on ash gourd flowers, *T. iridipennis* was the most frequent pollinator followed by *Halictus timidus* Smith, *A. cerana* F., *Ceratina hieroglyphica* Smith, and *Halictus taprobanae* Cameron (Leena and Nasser, 2015). Lalita and Yogesh (2015) observed that in Hisar (Haryana), on pumpkin flowers, *A. dorsata* was the most efficient pollinator followed by *Apis mellifera* F., *A. cerana* and *A. florea*.

Hence, keeping in view of the pollination requirements of cucurbits, bee conservation requires rapid and effective tools for identification and delineation of species. For this purpose, composition, relative abundance and diurnal activity of hymenopteran pollinators is to be studied.

MATERIALS AND METHODS

The study was conducted during the year 2018 - 2019 on five selected cucurbitaceous vegetables viz., culinary melon (*Cucumis melo* var. *acidulus*), bitter gourd (*Momordica charantia* L.), ash gourd (*Benincasa hispida* Thunb. and Cogn.), pumpkin (*Cucurbita moschata* L.) and ridge gourd (*Luffa acutangula* (Roxb.) L.). surveyed once in 34 locations in Thiruvananthapuram and four other districts of Kerala viz., Kollam, Pathanamthitta, Alappuzha and Kasaragod in the months of September, October, November and December during the year 2018 and in January, February and March during the year 2019 from 06:00 h to 18:00 h of the day with a cone type hand net during the blooming period. The four southern districts were selected based on the mandate of the RARS whereas the Kasaragod district was included to represent north Kerala. The selected number of locations covered in each district is mentioned in the table 1.

Table 1. Localities of sample collection

District	Localities covered	Number of locations
Thiruvananthapuram	Vellayani, Karamana, Kulathoor, Karyavattom, Karode, Venkulam, Balaramapuram, Vellarada, Pangode, Parassala, Idinjar, Pallichal, Mukkola, Oorutukaala, Azhicode, Melvettoor, Kalliyoor, Muttakkad, Venganoor, Vizhinjam, Athiyanoor, Pothencode, Puliyancode, Vattiyoorkavu, Perumkadavila	25
Kollam	Edamon, Kottarakkara, Karunagappally	3
Kasaragod	Padannakkad, Nileshwar	2
Alappuzha	Moncompu, Kavalam	2
Pathanamthitta	Padam, Thiruvalla	2
	Total	34

The composition and relative abundance of the different hymenopteran pollinators visiting flowers of five selected cucurbitaceous vegetables from the randomly marked one square meter area were recorded from 06:00 h to 18:00 h of the day at an hourly interval for 5 minutes during flowering period and expressed as mean number of pollinators / m² / 5 min. Diurnal activity observations were recorded from the flowers of one selected cucurbit viz., culinary melon in College of Agriculture, Vellayani during October to December. Foraging speed (time spent by the bee per flower) from landing till takeoff was recorded by using a stop watch and was expressed in seconds per flower, foraging rate (number of flowers visited by bee per minute) of bees were recorded. These observations were recorded from 06:00 h to 18:00 h at an hourly interval for 5 minutes during flowering period.

RESULTS AND DISCUSSION

A total of twenty-nine species of hymenopteran pollinators were recorded from five cucurbitaceous vegetables (Table 2).

The results on relative abundance (RA) and diurnal activity are presented in tables 3 to 7 and figures 1 to 4. The study on composition and relative abundance of hymenopteran pollinators from Thiruvananthapuram and four other districts of Kerala revealed that, *A. cerana indica* was the dominant pollinator in culinary melon (42.51%), pumpkin (38.76%) and ridgegourd (35.16%) whereas, *T. travancorica* was the dominant pollinator in bittergourd (31.86%) and ashgourd (33.50%). During two seasons, the foraging speed of *A. cerana indica*, *T. travancorica* and *Halictus* sp. was found to be highest during 10:00-11:00 h. The foraging speed of *Ceratina hieroglyphica* and *Lasioglossum* sp. was found to be highest during 09:00-10:00 h. The foraging rate of *T. travancorica*, *C. hieroglyphica* and *Lasioglossum* sp. was found to be highest during 10:00-11:00 h. The foraging rate of *A. cerana indica* and *Halictus* sp. was found to be highest during 11:00-12:00 h and 09:00-10:00 h respectively.

Study of hymenopteran pollinators composition and relative abundance in cucurbits

A. cerana indica was the most frequent pollinator followed by *T. travancorica*. Jangaiah (2007) reported that in Kerala, on culinary melon flowers, *A. cerana indica* was the most dominant and frequent floral visitor. *T. travancorica* (31.86 per cent) was recorded as the dominant pollinator on bitter gourd flowers followed by *A. cerana indica* (29.90 per cent) and *Ceratina* sp. (11.76 per cent). Subhakar *et al.* (2011) reported that, in Tirupathi on bitter gourd flowers, *T. iridipennis* (86.31 per cent) was the most frequent visitor. The abundance of bees depends on so many factors such as anthesis, weather parameters, competing flora, nectar concentration and its volume (Free, 1970). At peak flowering, the availability of flowers is more than commencement and cessation of flowering, and maximum number of insects would visit the crop during this period to increase the pollination process. Therefore, the flower number clearly influences the pollinator abundance, and in turn, the level of pollination.

A. cerana indica (38.76 per cent) was the frequent floral visitor followed by *T. travancorica* (24.03 per cent). Hemanthkumar (2006) and Mohapatra and Sontakke (2012) observed that on pumpkin flowers *A. cerana* was the most frequent and dominant pollinator followed by *A. dorsata*. *A. cerana indica* (35.16 per cent) was observed as the most frequent floral visitor on ridge gourd followed by *Xylocopa verticalis* (18.68 per cent). Kuberappa *et al.* (2008) and Lakshmi (2013) also reported that on ridge gourd flowers *A. cerana* was the most frequent and dominant pollinator. *T. travancorica* (33.50 per cent) was the most dominant pollinator on ash gourd followed by *A. cerana indica* (26.73 per cent). Leena and Nasser (2015) reported that, on ash gourd flowers, *T. iridipennis* was the most frequent pollinator followed by *H. timidus*, *A. cerana*, *C. hieroglyphica* and *H. taprobanae* in Kannur (Kerala).

Table 2. List of hymenopteran pollinators in cucurbitaceous vegetables

Common name	Scientific name	Family	Vegetable
Indian bee	<i>Apis cerana indica</i> F.	Apidae	Culinary melon, Bitter gourd, Pumpkin, Ash gourd, Ridge gourd
Rock bee	<i>Apis dorsata</i> F.		Culinary melon, Bitter gourd, Pumpkin, Ash gourd, Ridge gourd
Little bee	<i>Apis florea</i> F.		Culinary melon
Stingless bee	<i>Tetragonula travancorica</i> Shanas and Faseeh		Culinary melon, Bitter gourd, Pumpkin, Ash gourd
	<i>Tetragonula</i> sp. nov.1		Pumpkin
Small carpenter bee	<i>Ceratina hieroglyphica</i> Smith, <i>Ceratina simillima</i> Smith, <i>Ceratina binghami</i> Cockerell, <i>Ceratina unimaculata javanica</i> van der Vecht		Culinary melon, Bitter gourd, Pumpkin, Ash gourd, Ridge gourd
Blue- banded bee	<i>Amegilla zonata</i> L.		Culinary melon, Ridge gourd
Carpenter bee	<i>Xylocopa verticalis</i> Smith		Culinary melon, Ridge gourd
Sweat bee	<i>Lasioglossum</i> sp.	Halictidae	Culinary melon, Bitter gourd, Pumpkin, Ash gourd
	<i>Halictus</i> sp. 1, <i>Halictus</i> sp. 2, <i>Halictus</i> sp. 3		Culinary melon, Bitter gourd, Pumpkin, Ash gourd, Ridge gourd
Alkali bee	<i>Nomia eliotti</i> Smith, <i>Nomia westwoodi</i> Gribodo <i>Nomia curvipes</i> F., <i>Nomia</i> sp.		Culinary melon, Ashgourd
Leaf- cutter bee	<i>Megachile lanata</i> F., <i>Megachile disjuncta</i> F.	Megachilidae	Bitter gourd, Ash gourd
Paper wasp	<i>Ropalidia brevita</i> Das & Gupta	Vespidae	Culinary melon, Ridge gourd
Potter wasp	<i>Eumenes</i> sp.		Ridge gourd
	<i>Anterhynchium abdominale abdominale</i> Illiger		Culinary melon
Mud dauber	<i>Sceliphron madraspatanum</i> F.	Sphecidae	Culinary melon
Blue mud dauber	<i>Chalybion bengalense</i> Dahlbom		
Scoliid wasp	<i>Phalerimeris phalerata phalerata</i> de Saussure	Scoliidae	Ash gourd
	<i>Campsomeriella annulata annulata</i> F.		
Mole cricket hunters	<i>Larra maura</i> F.	Crabronidae	Culinary melon

Table 3. Composition and relative abundance of different hymenopteran pollinators in culinary melon

Pollinator	Trivandrum	Kollam	Pathanam-thitta	Alappu-zha	Kasara-god	Total	% RA
<i>Apis cerana indica</i>	167	21	13	4	8	213	42.51
<i>Tetragonula travancorica</i>	77	5	6	-	5	93	18.56
<i>Ceratina</i> Sp.	46	6	5	-	-	57	11.38
<i>Apis dorsata</i>	44	2	4	-	1	51	10.18
<i>Lasioglossum</i> sp.	10	4	5	-	4	23	4.59
<i>Nomia</i> sp.	12	-	-	5	2	19	3.79
<i>Halictus</i> sp.	5	3	3	3	-	14	2.79
<i>Apis florea</i>	7	1	2	-	-	10	1.96
<i>Xylocopa verticalis</i>	6	-	-	-	3	9	1.80
<i>Amegilla zonata</i>	5	-	-	2	-	7	1.40
Wasps	3	-	1	1	-	5	1.00
Total	382	42	39	15	23	501	42.51

No. of locations – 29

Total no. of pollinators collected - 501

% RA - mean number of pollinators/m²/5 min

Table 4. Composition and relative abundance of different hymenopteran pollinators in bittergourd

Pollinator	Trivandrum	Kollam	Pathanam-thitta	Alappu-zha	Kasara-god	Total	% RA
<i>Tetragonula travancorica</i>	34	7	8	6	10	65	31.86
<i>Apis cerana indica</i>	39	6	7	4	5	61	29.90
<i>Ceratina</i> sp.	19	-	2	3	-	24	11.76
<i>Megachile</i> sp.	5	4	4	-	2	15	7.35
<i>Lasioglossum</i> sp.	8	2	-	1	3	14	6.86
<i>Apis dorsata</i>	7	2	-	3	1	13	6.37
<i>Halictus</i> sp.	6	3	1	2	-	12	5.88
Total	118	24	22	19	21	204	

No. of locations – 27

Total no. of pollinators collected - 204

% RA - mean number of pollinators/m²/5 min

Foraging Behavior of Bees

On culinary melon flowers, *A. cerana indica*, *T. travancorica* and *Halictus* sp. recorded maximum

foraging speed during 10:00 h to 11:00 h. *C. hieroglyphica* and *Lasioglossum* sp. recorded highest foraging speed during 09:00 to 10:00 h. *T. travancorica*, *C. hieroglyphica* and *Lasioglossum*

Table 5. Composition and relative abundance of different hymenopteran pollinators in Pumpkin

Pollinator	Trivandrum	Kollam	Pathanam-thitta	Alappu-zha	Kasara-god	Total	% RA
<i>Apis cerana indica</i>	28	7	6	5	4	50	38.76
<i>Tetragonula travancorica</i>	15	4	4	3	5	31	24.03
<i>Ceratina</i> sp.	8	3	-	-	3	14	10.85
<i>Apis dorsata</i>	7	-	1	3	2	13	10.08
<i>Lasioglossum</i> sp.	2	5	2	1	1	11	8.53
<i>Halictus</i> sp.	5	1	2	2	-	10	7.75
Total	65	20	15	14	15	129	

No. of locations – 19

Total no. of pollinators collected – 129

% RA - mean number of pollinators/m²/5 min

Table 6. Composition and relative abundance of different hymenopteran pollinators in ash gourd

Pollinator	Trivandrum	Kollam	Pathanam-thitta	Alappu-zha	Kasara-god	Total	% RA
<i>Tetragonula travancorica</i>	43	6	7	4	6	66	33.50
<i>Apis cerana indica</i>	39	4	5	2	4	54	27.41
<i>Ceratina</i> sp.	10	-	4	-	3	17	8.62
<i>Halictus</i> sp.	8	3	-	5	-	16	8.12
<i>Nomia</i> sp.	7	2	2	-	2	13	6.59
Wasps	-	5	2	4	-	11	5.58
<i>Lasioglossum</i> sp.	6	-	2	-	1	9	4.56
<i>Apis dorsata</i>	6	1	-	-	-	7	3.55
<i>Megachile</i> sp.	4	-	-	-	-	4	2.03
Total	123	21	22	15	16	197	

No. of locations – 24

Total no. of pollinators collected – 197

% RA - mean number of pollinators/m²/5 min

sp. recorded the highest foraging rate during 10:00 h to 11:00 h. While *A. cerana indica* and *Halictus* sp. were observed to have maximum foraging rate during 11:00 to 12:00 h and 09:00 to 10:00 h. Rapp (1981) reported that, on cucumber flowers, honey bees started foraging at 06:00 h and their activity was maximum from 09:00 to 12:00 h and was found decreasing in the afternoon hours. The peak

foraging activity during morning hours can be correlated with the abundant availability of pollen and nectar during this period.

In the present study the maximum time was spent by *T. travancorica* (11.23 sec and 11.46 sec) for pollen collection, followed by *Lasioglossum* sp. (11.06 sec and 11.30 sec), *A. cerana indica* (10.61




Fig. 1. Foraging speed (seconds) of hymenopteran pollinators during season I (October to November)




Fig. 2. Foraging speed (seconds) of hymenopteran pollinators during season II (November to December)

sec and 10.63 sec), *Halictus* sp. (10.26 sec and 10.40 sec) and *C. hieroglyphica* (9.02 sec and 9.11 sec) during two seasons. Prakash (2002) reported that in cucumber, among the honey bees, maximum time was spent for pollen collection, by

A. florea (13.49 sec), followed by *T. iridipennis* (11.44 sec), *A. cerana* (9.65 sec), *A. mellifera* (8.74 sec) and the least in *A. dorsata* (7.22 sec). The difference in the foraging speed of bee species, may be due to different climatic conditions, type of




Fig. 3. Foraging rate of hymenopterans during season I (October to November)




Fig. 4. Foraging rate of hymenopterans during season II (November to December)

crop, geographic location and species specific differences and variation in the availability of foraging source.

In culinary melon flowers, the mean foraging rate was found highest in *A. cerana indica* (10.60 &

10.88 flowers/min) followed by *T. travancorica* (9.16 and 9.23 flowers/min), *C. hieroglyphica* (5.01 and 5.10 flowers/min), *Lasioglossum sp.* (4.83 and 4.85 flowers/min) and *Halictus sp.* (4.03 and 4.13 flowers/min) during the two seasons. In Hisar, the data on the foraging activity of insect visitors in

Table 7. Composition and relative abundance of different hymenopteran pollinators in ridge gourd

Pollinator	Trivandrum	Kollam	Pathanam-thitta	Alappu-zha	Kasara-god	Total	% RA
<i>Apis cerana indica</i>	11	6	5	4	6	32	35.16
<i>Xylocopa verticalis</i>	5	5	-	6	1	17	18.68
Wasps	5	-	4	3	2	14	15.38
<i>Apis dorsata</i>	3	4	1	-	4	12	13.19
<i>Lasioglossum</i> sp.	3	-	-	2	4	9	9.89
<i>Amegilla zonata</i>	1	3	3	-	-	7	7.69
Total	28	18	13	15	17	91	

No. of locations – 13

Total no. of pollinators collected – 91

% RA - mean number of pollinators/m²/5 min

cucumber hybrids, viz., Evergreen, NBH-Manu, Damini and Rani showed that the mean foraging rate irrespective of different day hours was highest in *A. dorsata* (8.63 flowers/min.) followed by *C. sexmaculata* (5.03 flowers/min.), and it was lowest in *Halictus* sp. (4.38 flowers/min.) (Hanh *et al.*, 2014). Fluctuation in visits of insect pollinators on culinary melon flowers reveals that the visits were low at the time of commencement and cessation of flowering but these remained high during mid flowering period. This difference might be due to variation in the floral density during the span of blooming and changes in climatic conditions.

ACKNOWLEDGEMENT

We express our gratitude to the Kerala Agricultural University for funding the study.

REFERENCES

- Balina P. K., Sharma S. K. and Rana M. K. (2012) Diversity, abundance and pollination efficiency of native bee pollinators of bittergourd (*Momordica charantia* L.) in India. *Journal of Apicultural Research* 51(3): 227-231.
- Free J. B. (1970) *Insect Pollination of Crops*. Academic press, London and New York. 544 pp.
- Grewal G. S. and Sidhu A. S. (1979) Insect pollination of some cucurbits in Punjab. *Indian Journal of Agricultural Science* 48: 78-83.
- Hanh T. T. M., Sharma S. K. and Rana M. K. (2014) Pollination efficiency of native bee pollinators of cucumber (*Cucumis sativus* L.) in India. *Journal of Apiculture* 29(3): 199-205.
- Hemanthkumar M. S. (2006) Pollination potentiality of Indian honeybee (*Apis cerana indica* F.) in pumpkin (*Cucurbita moschata* Duch ex Poir). M. Sc. (Ag), Thesis, University of Agricultural Sciences, Bengaluru, Karnataka. 92 p.
- Jangaiah V. (2007) Insect community analysis in cucurbitaceous vegetables and impact of insecticides on insect pollinators. M.Sc. (Ag) thesis, Kerala Agricultural University, Thrissur, Kerala. 112 p.
- Kuberappa G. C., Ramesh R. G. and Vishwas A. B. (2008) Pollinator's fauna with special reference to the role of honeybees in ridgegourd, *Luffa acutangula* L. In: *Bioresource Conservation and Management*. New Delhi (IN): Today and Tomorrow Printers and Publishers. pp. 163-174.
- Lakshmi K. S. (2013) Studies on pollinator's diversity, abundance and foraging activity with special reference to role of honeybees in the productivity of ridgegourd (*Luffa acutangula* L.) Ph.D. thesis, University of Agricultural Sciences, GKVK, Bangalore, Karnataka. 244 p.
- Lalita P. and Yogesh K. (2015) Pollination efficiency of major insect pollinators of pumpkin, *Cucurbita moschata* (Duch. ex Lam) crop in different varieties. *Journal of Applied and Natural Science* 9 (3): 1603–1607.

- Leena P. T. and Naseer M. (2015) Effect of insect pollination on fruit production on cucurbit crop ashgourd. *International Journal of Tropical Agriculture* 33(2): 831-835.
- Mc Gregor S. E. (1976) Insect pollination of cultivated crop plants (Agriculture hand book No.496), Agricultural Research Service. U.S. Dept. Agric. pp. 411.
- Mohan R. (2000) Bio-ecology and management of stingless bees (Apidae: Meliponinae). M.Sc. (Ag) thesis, Kerala Agricultural University, Thrissur, Kerala. 68 p.
- Mohapatra L. N. and Sontakke (2012) Foraging behaviour and diurnal abundance of Indian hive bee *Apis cerana indica* Fab. in Pumpkin. *Journal of Plant Protection and Environment* 9(2): 80-82.
- NHB (2018) National Horticulture Board. Area and Production of Horticultural Crops- All India: 2016-17 to 2017-18 (3rd Advance Est.) [on-line]. Available: http://nhb.gov.in/statistics/State_Level/-2017-18.
- Pateel M.C. and Sattagi H.N. (2007) Abundance of different Insect pollinators visiting cucumber (*Cucumis sativus* L.) in Rabi season. *Karnataka Journal of Agricultural Sciences* 20(4): 853-854.
- Prakash K. B. (2002) Pollination potentiality of Indian honey bee viz., *Apis cerana* on the production of cucumber (*Cucumis sativus* Linn.) S. W.: Cucurbitaceae). M. Sc. (Ag) thesis, University of Agricultural Sciences, Bangalore, Karnataka. 87 p.
- Rapp R. (1981) The effect of pollination by honey bees (*Apis mellifera* L.) on cucumber cv. Delila seed production. M.Sc.(Ag) thesis, Hebrew Univeristy of Jerusalem, Rehovot, Israel. 110 p.
- Subhakar G., Sreedevi K., Manjula K. and Reddy N.P.E. (2011) Pollinator diversity and abundance in bittergourd, *Momordica charantia* Linn. *Pest Management in Horticultural. Ecosystems* 17(1): 23-27.

(Received August 07, 2019; revised ms accepted December 14, 2019; published December 31, 2019)



On a new species of *Neoceratobaeus* Rajmohana (Hymenoptera: Scelionidae) from India

P. Sunita and K. Rajmohana*

Zoological Survey of India, Kolkata, West Bengal 700053, India. Email: mohana.skumar@gmail.com

ABSTRACT: *Neoceratobaeus* Rajmohana (Hymenoptera: Scelionidae) was described from India as a monotypic genus. The present paper describes and illustrates the second species *N. dwitiyus* sp. nov. from West Bengal, India. Morphological affinities with the known species are discussed.

© 2019 Association for Advancement of Entomology

KEYWORDS: *Neoceratobaeus*, new species, Baeini, egg parasitoid

INTRODUCTION

Neoceratobaeus Rajmohana 2014, (Hymenoptera: Scelionidae) with type species *Neoceratobaeus gibbus* Rajmohana, 2014, has been a monotypic genus, described from India. With 7 segmented antenna ending in a large unsegmented clava in females, forewing rather spoon shaped distally and T1 having a large, backward directed and laterally compressed horn, the genus is easily diagnosed. It belongs to subfamily Scelioninae and tribe Baeini. Members of the tribe Baeini are unique among Scelionidae since they attack spider eggs (Austin *et al.*, 2004; Carey *et al.* 2006). Majority of the Baeini species fall under 4 genera with 433 species known globally. *Ceratobaeus* Ashmead (165 species), *Idris* Förster (160 species), *Odontacolus* Kieffer (55 species), and *Baeus* Haliday (53 species). In India Baeini comprises 47 species under five genera - *Baeus* Haliday (1 species), *Ceratobaeus* Ashmead (12 species), *Idris* Förster (31 species), *Neoceratobaeus* Rajmohana (1 species) and *Odontacolus* Kieffer (2 species) (Johnson 1992, Johnson *et al.* 2018). In this paper

Neoceratobaeus dwitiyus sp. nov. collected from West Bengal, India, the second species of the genus is described and illustrated. Morphological affinities with *N. gibbus* are discussed.

MATERIALS AND METHODS

Specimens were collected using yellow pan traps, set in a vegetable garden. 30 traps were kept for 10 hours. The collected specimens were preserved in 70% ethanol and later mounted on point-card tips. Descriptions and images were prepared using Leica M205-A stereomicroscope, with 1X objective and Leica DFC-500 digital camera and processed with LAS version 3.6 extended focus software. Morphological terminology follows Masner (1976), Austin and Field (1997) and Mikó *et al.* (2007, 2010).

Abbreviations used in the description are as follows: F1 to F4- Funicular Segments; L- Length; W- Width; H- Height; IOS- Inter Occipital Space; HW- Head Width, HH- Head Height; stgv- Stigmal vein; mv- Marginal vein; pmv- Post marginal vein; T1-T7- Metasomal tergites 1 to 7.

* Author for correspondence

Both the holotype and paratype of *N. dwitiyus* sp. nov. are deposited in the National Zoological Collection, Zoological Survey of India, Kolkata.

***Neoceratobaeus dwitiyus* sp. nov. Holotype Female (Figs. 1-6)**

urn:lsid:zoobank.org:act:C43ADC42-B34D-42C4-B2CB-D2FBF2E86286

DESCRIPTION

Holotype Female. Length = 1.02 mm. Head and mesosoma black, metasoma yellow, contrasting in colour with rest of body, horn on T1 concolorous with metasoma, blackish brown only towards tip and; legs pale; eyes silvery; mandibles as well as base of antennal clava yellowish brown; wings clear and hyaline; veins brown (Figs 1, 2).

Head : (L: W): 35: 6 transverse dorsally, slightly wider than mesosoma; in anterior view subtriangular; vertex straight, upper frons, frons, vertex and occiput with coarse granulations; with fine and dense setigerous punctate; frons entirely, face and gena entirely sculptured except for a large smooth and glabrous speculum (Fig 4), on antennal scrobe, extending upto three fourth eye level on frons medially; cheeks with fine radiating striae, lacking granulations in between striae, and gradually merging with granulations near lower margin of eyes, pilosity scanty; IOS : HW to HH = 22 : 35 : 14 (in front view); eyes densely pubescent; mandibles with three pointed and equal teeth; central keel distinct, complete and expending till anterior ocelli; lateral ocelli contiguous with orbital margin; hyper-occipital carina complete; occipital carina distinct, striate-scribulate; temples coarsely granulate, without any striae; antennae with 7 segments, 4 funicular segments; clava large (Figs. 3, 6), segmentation indistinct; length and width of F1 a little less than that of pedicel, F1 longest, > 2x length of F2; F3 and F4 much transverse; clava large, 4 segmented, segmentation indistinct. L: W ratio of antennal segments being 17: 3; 7: 2; 1: 2; 1:2; 1:2; 1:2; 1:1; 14:8.

Mesosoma : (L : W = 31 : 33); narrower than head dorsally (Fig. 1); surface with granulations as on vertex; mesoscutum with dense pubescence; notauli distinct as a short strip, but visible only till

0.2 of mesoscutum, trans scutellar sulcus not crenulated; mesoscutellum moderately convex (Fig. 1), surface with granulations as on mesoscutum, pilosity scattered; posterior margin of mesoscutellum feebly excavate, a row stiff setae present on posterior border; metascutellum with an arched row of horizontal foveolae; propodeum feebly hairy, drawn into pointed spines at lower corners; propodeal lamellae and flanges on either sides of metasomal horn developed into spines laterally; pronotum laterally striate longitudinally and with rough rugosity, mesopleural carina distinct (Figs. 5), bordered, though not continuous, with longitudinal striae; acetabular carina, flanked by irregular punctate and irregular longitudinal elements; lower, stem of forewing emarginated inwards, fitting to curvature of metasomal horn when at rest; L : W = 61 : 17; pmv longer than stgv; (mv : stgv : pmv = 2: 7 : 8), pmv with 5-6 large setae; marginal fringe short; hindwing wider than usual, width of hindwing: forewing = 14 : 23; basal vein absent (Fig. 2).

Metasoma : (L : W = 58 : 34); T3 is widest among all the tergites ; all tergites transverse, T2 onwards with fine pubescence laterally; metasomal horn in dorsal view extending backwards, upto anterior half of T2, horn dorsally with closely placed concentric striae; median suture between T1 and T2 distended downwards; T1 longest among tergites; proportions of width to length of T1 to T7 medially being 23: 14; 31: 8; 34: 11; 27: 6; 22: 2; 14: 1; 8: 8 T1 and T2 with similar sculpture, weak and wavy longitudinal striae, T3 onwards with dense and fine irregular reticulate sculpture; anterior margin of T3 with a narrow smooth band; posterior margins of T3-T6 with a narrow smooth band; T7 entirely sculptured, with sparse long hairs (Fig. 1); ovipositor extended.

Male: Unknown.

Etymology: The species is named '*dwitiyus*', this being the second species under the genus ('Dwitiya' in Sanskrit = second)

Material examined: Holotype. Female (20678/H3). India: West Bengal: Sagar Island, Phulbari (N21° 51' 43.94", E088° 07' 46.32"); Coll: Sunita; 21.iii.2018; yellow pan trap.



Fig. 1



Fig. 2



Fig. 3




Fig. 4





Fig. 5



Fig. 6

Figs. 1-6. *Neoceratobaeus dwitius* sp. nov. Holotype, female

1) Dorsal view; 2) Lateral view; 3) Wings; 4) Head front view (Speculum indicated); 5) Head with Mesopleuron; 6) Head with antenna

**Fig. 7****Fig. 8**

Figs. 7-8. Female *Neoceratobaeus gibbus* Rajmohana
7) Head frontal view (Speculum indicated); 8) Forewing

Paratype: 1 female (20679/H3). India: West Bengal: Sagar Island: Gangasagar Island, Bharat Seva Ashram Campus (N21° 38' 22.05", E088° 04' 48.32"); Coll: Sunita; 23.iii.2018; yellow pan trap.

Diagnosis:

Neoceratobaeus dwitiyus sp. nov. is very similar to *N. gibbus*, but the former can be identified by the smooth, shiny and glabrous speculum on antennal scrobe, which is very conspicuous. In *N. gibbus*, speculum is not smooth (Fig. 7), instead with impressions or traces of coriaceous sculpture. In *N. dwitiyus*, forewing is comparatively longer, 3.5X as long as wide, with distal margin slantingly convex. In *N. gibbus*, forewing is wider, only 2.5X as long as wide, with a more rounded distal margin (Fig. 8). Both the species differ largely in the shape and size of the forewing (Figs. 3, 8).

Comments:

Genus *Neoceratobaeus* has been known by females only. The metasomal horn on T1, serve as a recess for the internally retracted ovipositor and the horn length is correlated to ovipositor length (Austin *et al.*, 2004). The prominent metasomal horn of *N. dwitiyus* gives a clue of the length of the ovipositor and also that the eggs of the host

spider would have a thick sac. Since only one specimen each was trapped, in both the collecting events, this indicates the rarity of the species.

ACKNOWLEDGEMENT

The authors are grateful to the Director, Zoological Survey of India, for encouragement and providing facilities to accomplish this work.

REFERENCES

- Austin A.D. and Field S.A. (1997) The ovipositor system of scelionid and platygastid wasps (Hymenoptera: Platygastroidea): comparative morphology and phylogenetic implications. *Invertebrate Taxonomy* 11: 1-87.
- Austin A.D., Johnson N.F. and Downton M. (2004) Systematics, Evolution and Biology of Scelionid and Platygastid Wasps. *Annual Review of Entomology* 50: 553-582.
- Carey D., Murphy N. P. and Austin A. D. (2006) Molecular phylogenetics and the evolution of wing reduction in the Baeini (Hymenoptera: Scelionidae): Parasitoids of spider eggs. *Invertebrate Systematics* 20(4).
- Johnson N.F. (1992) Catalogue of world Proctotrupoidea excluding Platygastidae. *Memoirs of the American Entomological Institute* 51: 1-825.
- Johnson N.F., Chen H. and Huber B.A. (2018) New species of *Idris* Förster (Hymenoptera,

- Platygastroidea) from southeast Asia, parasitoids of the eggs of pholcid spiders (Araneae, Pholcidae). ZooKeys 811: 65–80.
- HOL (2018) Hymenoptera Online (HOL). <https://hol.osu.edu/> [Accessed 3 Sept 2019]
- Masner L. (1976) Revisionary notes and keys to world genera of Scelionidae (Hymenoptera: Proctotrupoidea). Memoirs of the Entomological Society of Canada 97: 1-87.
- Mikó I., Vilhelmsen L., Johnson N.F., Masner L and Péntzes Z. (2007) Skeletomusculature of Scelionidae (Hymenoptera: Platygastroidea): head and mesosoma. Zootaxa 1571: 1-78.
- Mikó, I., Masner L. and Deans A.R. (2010) World revision of *Xenomerus* Walker (Hymenoptera: Platygastroidea, Platygastriidae). Zootaxa, 2708: 1-73.
- Rajmohana K. (2014) A systematic inventory of Scelioninae and Teleasinae (Hymenoptera: Platygastriidae) in the rice ecosystems of North central Kerala. Memoirs of the Zoological Survey of India, Vol: 22. 72 pp.

(Received October 11, 2019; revised ms accepted December 11, 2019; published December 31, 2019)



Occurrence of multiple nest entrance in the stingless bee *Tetragonula travancorica* (Hymenoptera: Meliponini)

P. Faseeh^{*1} and S. Shanas²

¹Department of Entomology, College of Agriculture, Kerala Agricultural University, Vellayani, Thiruvananthapuram-695522, Kerala, India;

²Regional Agricultural Research Station (Southern Zone), Kerala Agricultural University, Vellayani, Thiruvananthapuram 695522, Kerala, India. Email: usmanfaseeh37@gmail.com

ABSTRACT: Multiple nest entrance occurs in the stingless bee *Tetragonula travancorica* Shanas & Faseeh at a low frequency (2.3%). Different types of multiple nest entrances are described and its significance discussed. © 2019 Association for Advancement of Entomology

KEY WORDS: stingless bee, nest architecture, Kerala, India.

INTRODUCTION

The stingless bees (Hymenoptera, Apidae, Meliponini) are the most diverse eusocial bees in the tropical regions of the world. They are 60 times more speciose than the *Apis* bees. Nesting habits and nest architecture vary greatly not only among genera but also among species within this genus. The nesting habitats of stingless bees vary widely from cracks and crevices, walls, tree hollows, the base of trees, bird nests, underground structures, limestones etc. According to Roubik (2006) the nest entrance is normally associated with physio-chemical regulation, maintenance of microclimate inside the nest, foraging activity and defence of a colony and it is the check point at which the individual stingless bees entering the nest are recognized. He also mentioned the possibility of occurrence of innovations in the nest architecture within a taxon.

Attributes of nest structure and nesting habits can be used as a tool for ecological, phylogenetic and

taxonomical studies (Rasmussen and Camerago, 2008; Lima *et al.*, 2013). Kelly *et al.* (2014) observed that the nest entrance of stingless bees differs with genus. Most of the studies were concentrated on ecology, biology, morphology and pollination of these bees (Vijayakumar 2014). They use the waxy secretion from their dorsal body along with resins collected from plants for construction of nests (Virkar, 2014). Only limited information is available on the nesting behaviour of stingless bees in India (Roopa *et al.*, 2015; Patel and Pastagia, 2016).

Shanas and Faseeh (2019) described three new species of stingless bees from south India and provided keys to the species of *Tetragonula* of the Indian subcontinent. They also established that, *T. iridipennis* (Smith, 1854) does not occur in India and *Tetragonula iridipennis*, mentioned in publications from south India most probably refers to *T. travancorica* Shanas & Faseeh. Multiple nest entrance in *Tetragonula travancorica* from Kerala is described and its significance discussed here.

* Author for correspondence

MATERIALS AND METHODS

The study was conducted during 2017-2018 in Kerala, India. Stingless bees were collected from different geographical regions in the state. The colonies were located at Manakkadavu, Kannur District (12°13'12.21"N 75°30'07.29"E, altitude 223 m), Peechi, Thrissur District (10°30'56.06"N 76°21'31''.35"E, altitude 115 m), Vellayani, Thiruvananthapuram District (8°25'40.85"N 76°59'05.68"E, altitude 29 m), Kadannamanna, Malappuram District (11°01'53.58"N 76°10'07.90"E, altitude 55 m), Ambanad, Kollam District (9°00'50.99"N 77°05'21.88"E, altitude 362 m), Thenmala, Kollam District (8°57'45.58"N 77°03'53.38"E, altitude 153 m). A total of 207 colonies were located during the study. The colonies with more than one entrance were recorded with the number of guard bees, shape of entrance mouth, length and width of entrance mouth, number of entrance tubes, length of each entrance tube, number of active entrances, height from the ground level and nest habitat. Each nest entrance was photographed with a 55mm macro lens mounted

on a Nikon D80 camera. Latitude, longitude, and altitude of each colony were noted with the help of Google earth pro app.

Transparent bottles of 15-20 cm height were kept covering the mouth of the entrance and gently tapped around the nearby areas of nest which resulted in bees getting trapped inside the bottle. An average of 20 stingless bees was collected from each colony and no colonies were harmed during the entire collection. Collected bees were killed using ethyl acetate and preserved in 70% ethyl alcohol, few of which were pinned, dried and stored in insect boxes for further studies.

RESULTS AND DISCUSSION

The samples were collected from various locations in Kerala (comprising all geographical regions such as coastal areas, planes, and hills). Out of the 207 colonies, six colonies had multiple nest entrance openings, of which four were from the hill tracts and two were from the plains. The shape of entrance tubes identified were either round, oval or slit. Three of the nest entrances were oval and

Table 1. Nest entrance characters of colonies with more than one entrance

Character	Location*					
	M	P	V	T	A	K
No of entrance tubes	2	2	2	2	2	5
No of active entrance tubes	2	1	1	2	2	5
Shape of entrance	Round	Oval	Oval	Round	Slit	Round
No of guard bees	5+5	5	6	4+4	7+7	4+1+1+1+1
Length of entrance mouth (cm)	1.2	1.2	2.1	1	2.5	
Length of each entrance tube (cm)		2.1	7.6	5.4	7	04.3
						3.8
						2.3
						5.4
						5.4
Height from ground level (cm)	34	67	28.7	25.4	138	7.8
Nest habitat	Stone wall	Stone wall	Stone wall	Stone wall	Building wall	Stone wall

*(M-Manakkadavu, P-Peechi, V-Vellayani, T-Thenmala, A-Ambanad, K-Kadannamanna)



Fig. 1 Vellayani



Fig. 2 Thenmala



Fig. 3 Manakadavu

Plate 1. Multiple entrances recorded in *Tetragonula travancorica*



Fig. 4 Kadannamanna



Fig. 5 Peechi



Fig. 6 Ambanad

Plate 1. Multiple entrances recorded in *Tetragonula travancorica*




Fig.7 Arrows indicate the openings in the entrance tube at Thachampara, Palakkad (Host: Fig tree)

two of them were round and one was slit in shape. It was also observed that the shape of entrance mouth was similar for all entrance tubes of the same colony.

The number of guard bees varied between colonies, however, the number of guard bees were same in each active entrance tube of the same colony, except in the case of a single colony where in, out of five active entrance tubes, one entrance tube had 4 guard bees and the remaining entrance tubes were guarded by a single bee (Fig. 4).

The number of entrance tubes was two for colonies identified from Vellayani (Fig. 1), Thenmala (Fig. 2), Manakkadavu (Fig. 3), Peechi (Fig. 5), and Ambanad (Fig. 6) whereas five entrance tubes were found in a single colony from Kadannamanna (Fig. 4). The number of active entrances differed in each colony. Colonies from Thenmala, Ambanad and Manakkadavu had two active entrances, whereas colonies from Vellayani and Peechi were with only one entrance tube which was active and the other one was closed entirely or joined with the active entrance tube mouth (Vellayani). A colony from Kadannamanna had five entrance tubes (Fig.4) and all of them were active.

The length and width of entrance mouth were almost same for different entrance tubes in a single colony. Length of entrance mouth varied from 1.0 to 2.5 cm and width varied from 0.2 to 1.2 cm in different locations. The height of colony from ground level varied in different locations. All colonies were located at a height of less than 50 cm, except the ones in Ambanad (138 cm) and Peechi (67 cm). Five colonies were found associated with foundations of buildings made of stones, and one colony was observed inside the wall of a building.

All the five colonies were having the entrance tubes one above the other presenting an overall look of vertical arrangement of entrance tubes. In one colony, the five entrances were arranged in a different manner: two pairs of entrance tubes arranged vertically (one below to the other) and the fifth, in line with the upper entrance tubes (three tubes were in one line and two tubes were in another line) (Fig.4).

In addition to these six colonies with multiple entrances, one more colony was identified from Thachampara (Palakkad dist) with multiple nest entrance openings. Three to four small openings were observed in the entrance tube, in addition to

opening on the apex. Except for the apex, all openings were non-functional and without any guard bees. The main entrance was guarded by 4-5 bees and the colony was located 186cm above the ground level on a fig tree (Fig.7).

Wille and Michener (1973) reported two species of stingless bees *Tetragonisca angustula* and *Trigona fulviventrtris*, those rarely form nests with two or three entrances. Roubik (2006) stated the existence of multiple entrances in some genera such as *Lepidotrigona*, *Scaptotrigona*, *Plebia*, *Tetragona*, and *Hypotrigona* and these multiple entrances cannot be considered as a consistent character in these genera. Benziger and Benziger (2010) observed two exceptional nests of minute stingless bees, *Lisotrigona cacciae* and *L. furva* having two nest entrances for a single colony. The nest entrances of *Pariotrigona klossi* obtained from calcareous rocks were having several tubelets (highest reported were with 300 tubelets) arranged on interconnected clumps (Benziger, 2011). Such clumps were observed only in one of the five colonies (colony which had five entrance tubes originating from a clump) in the current study. The nests with two entrances had no clumps, however, each tube was very closely constructed or merged partially at the base. This may enhance the stability of the nest entrances as the number of entrance tubes increases. Divya *et al.* (2016) observed two nests of *Tetragonula iridipennis*, each with two entrances, from Poojappura and Tholicode in Kerala. Jose (2015) observed two separate entrance funnels in a *T. iridipennis* nest.

This behaviour of constructing multiple entrances can be considered as a defensive strategy of the stingless bees or to avoid the huge foraging traffic in the strong colonies. The building of a large, single entrance may result in variation in the microclimate of the bee nest, which may adversely affect the colony. This could be a plausible for the construction of multiple entrance holes instead of one big entrance. It is also difficult to manage the intruders as the size of the nest entrance increases and at the same time, an efficient distribution of guard bees can be done by dividing the nest entrance, and thus fortify the defence. All the nests mentioned in the

current study were obtained inside stone walls of the foundations of buildings and all of them were free from harsh weather and other disturbances. Benziger *et al.* (2011) stated, in order to construct complex nest entrances they need to be protected well and the nests of *Pariotrigona klossi* obtained from crevices of limestones were protected by overhanging rocks.

Multiple exit holes and platforms were observed in *Tetragona clavipes* and the species also varied with broad and lamellate nest entrances (Roubik, 1979). Roubik (2006) reported construction of tubercles or hollow tubes around the nest entrance of *Lestrimelitta* and occurrence of dual entrances in colonies of *Meliponula ferrugenia* and *Lepidotrigona ventralis*. Jose (2015) reported two openings in a single entrance tube of an artificial hive in *T. iridipennis*, in which both the openings were guarded by bees. In the current study, we observed single entrance tube with multiple openings in a natural habitat (in feral colonies) however, none of them were functional except the opening at the apex of the tube (Fig.7).

The shape of nest entrance of *T. iridipennis* varied from slit-like, circular, oval, funnel-shaped and feral colonies are dominant with slit and circular nest entrance apex (Pavithra *et al.*, 2013; Jose, 2015). The shape of entrance apex was similar with in a colony while it varied between colonies such as slit-like, oval or circular. The reported nest entrance length in *T. iridipennis* varies from 6 to 18 mm (Roopa *et al.*, 2015), 10.6 to 102.6 mm (Jose, 2015) and 5 to 90mm (Ramya *et al.*, 2015). *Tetragonula* colonies without an entrance tube were also reported from Kerala (Jose, 2015). The length of the entrance tube varied from 2.1 cm to 7.6 cm and among them, one colony was without a nest entrance tube and was with a slit-like opening. In addition to environmental cues, the pheromone-regulated nest mate interaction also acts as a stimulus for nest building, when these stimuli become more complex and vigorous, it changes the nest building behaviour and results in the formation of novel building action (Pavithra *et al.*, 2013).

The behaviour of *Tetragonula travancorica* in constructing nests with multiple entrance is

prevalent in different regions of Kerala, however, its frequency is low (2.3%). The factors behind this behaviour or instinct are not known. The knowledge on nesting and nesting site can be a useful tool for designing stingless beehives and their conservation for honey as well as pollination purpose.

REFERENCES

- Banziger H. and Banziger S. (2010) Mammals, birds, and reptiles as hosts of *Lisotrigona* bees, the tear drinkers with the broadest host range (Hymenoptera, Apidae). *Mitteilungen der Schweizerischen Entomologischen Gesellschaft* 83:271–282.
- Banziger H., Pumikong S. and Srimuang K. (2011) The remarkable nest entrance of tear drinking *Pariotrigonaklossi* and other stingless bees nesting in limestone cavities (Hymenoptera: Apidae). *Journal of Kansas Entomological Society* 84(1): 22-35.
- Divya K.K., Amritha V.S. and Devanesan S. (2016) Nest architecture of stingless bees. *Advances in Life Sciences* 5(6): 2035-2038.
- Jose S. K. (2015) An investigation of systematic biology and behavior of stingless bees of Kerala and improved techniques for meliponiculture. Ph. D. (Thesis), Department of Zoology, C. M. S. College, Mahatma Gandhi University. pp. 40-61.
- Kelly N., Farisya M.S.N., Kumara T.K. and Marcela P. (2014) Species diversity and external nest characteristics of stingless bees in Meliponiculture. *Pertanika Journal of Tropical Agricultural Sciences* 37 (3): 293 - 298.
- Lima F.V.O., Silvestre R. and Balestieri J.B.P. (2013) Nest entrance types of stingless bees (Hymenoptera: Apidae) in a tropical dry forest of mid-western Brazil. *Sociobiology* 60(4): 421-428.
- Pavithra P.N., Shankar, M.R. and Jayaprakash (2013) Nesting pattern preferences of stingless bee, *Trigona iridipennis* Smith (Hymenoptera: Apidae) in Jnana Bharathi Campus, Karnataka, India. *International Research Journal of Biological Science* 2(2): 44-50.
- Patel H.K. and Pastagia J.J. (2016) Habitat, nesting behavior, and colony organization of stingless bees *Tetragonula laeviceps* Smith. *Asian Journal of Biological Science* 11(1): 186-189.
- Ramya L., Suma K.P. and Kuberappa G.C. (2015) Nesting behavior of stingless bee, *Tetragonula iridipennis* Smith. *Trends in Biosciences Journal* 8(9): 2460-2462.
- Rasmussen C. and Camargo J.M.F. (2008) A molecular phylogeny and the evolution of nest architecture and behavior in *Trigona* s.s. (Hymenoptera: Apidae: Meliponini). *Apidologie* 9: 102-118.
- Roopa A.N., Eswarappa G., Sanganna M. Sajjanar and Gowda G. (2015) Study on nesting characteristics and biology of stingless bee (*Trigona iridipennis* Smith.). 2015. *IOSR Journal of Agriculture and Veterinary Science (IOSR-JAVS) e-ISSN: 2319-2380, p-ISSN: 2319-2372*. 8(10):34-36.
- Roubik D.W. (2006) Stingless bee nesting biology. *Apidologie* 37(2): 124-143.
- Roubik D.W. (1979) Nest and colony characteristics of stingless bees from French Guiana (Hymenopter: Apidae). *Journal of Kansas Entomological Society* 52(3): 443-470.
- Shanas S. and P. Faseeh (2019) A new subgenus and three new species of stingless bees (Hymenoptera: Apidae: Apinae: Meliponini) from India. *Entomon* 44(1) 33- 48.
- Vijayakumar K. (2014) Nest and colony characters of *Trigona (Lepidotrigona) ventralis* var. *arcifera* Cockerell from North East India. *Asian Journal of Conservation Biology* 3 (1): 90–93.
- Virkar P.S., Shrotriya S. and Uniyal V.P. (2014) Building walkways: observation on nest duplication of *Trigona iridipennis* Smith (1854). *Ambient Science* 1(1): 38-40.
- Wille A. and Michener C. D. (1973) The nest architecture of stingless bees with special reference to those of Costa Rica. *Revista de Biología Tropical* 21(1): 1-178.



Influence of wind direction on parasitization behaviour of *Trichogramma chilonis* Ishii (Hymenoptera: Trichogrammatidae) in brinjal ecosystem

P. Dominic Manoj^{1*}, G. Ravi² and M.I. Manivannan³

¹ Department of Agricultural Entomology, Agricultural College and Research Institute, Tamil Nadu Agricultural University, Killikulam, Vallanadu, Tamil Nadu, Thoothukudi, India;

² Department of Plant Protection, Anbil Dharmalingam Agricultural College and Research Institute, Tamil Nadu Agricultural University, Tiruchirappalli, Tamil Nadu, India;

³ Department of Horticulture, Agricultural College and Research Institute, Tamil Nadu Agricultural University, Killikulam, Vallanadu, Tamil Nadu, Thoothukudi, India.

Email: babydominic5@gmail.com

ABSTRACT: Investigations were carried out to assess the impact of wind direction on parasitization behaviour of *Trichogramma chilonis* Ishii on brinjal shoot and fruit borer *Leucinodes orbonalis* Guenee indicated maximum number of parasitization in windward direction. Findings indicate importance of air stream in the parasitization behaviour of *T. chilonis* in field condition.

© 2019 Association for Advancement of Entomology

KEY WORDS: Biocontrol, *Leucinodes orbonalis*, *Trichogramma* parasitoid, wind

Trichogrammatids are the most widely used egg parasitoids against lepidopterous pests on a wide range of agricultural and forest crops across the world for more than 70 years (Li, 1994) as inundative releases. More than 25 species reported in India, *Trichogramma chilonis* Ishii occurs widely all over the country throughout the year. Farmers in Tamil Nadu are known to use *Trichogramma* egg parasitoid for shoot and fruit borer *Leucinodes orbonalis* management. It is well known that movement activity of *Trichogramma* species may depend on environmental conditions, primarily temperature (Fournier and Boivin, 2000), host density, release rates (Singh and Jalali, 1992), host plant density, wing size (Kolliker- Ott *et al.*, 2004) and sex (Canto-Silva *et al.*, 2006). This study was

conducted to understand the orientation behaviour of *T. chilonis* influenced by wind direction to decide on parasitoid release points in an inundative release during wind influence situation for the management of brinjal shoot and fruit borer (BSFB) in brinjal ecosystem.

Orientation behaviour of *T. chilonis* in brinjal field

1. Sentinel Egg Card Technique

A field trial conducted *kharif* 2017 in Agricultural College and Research Institute, Killikulam in Thoothukudi district using brinjal variety KKM 1. The experiment was conducted in supervisory trial. The experiment was organized on brinjal crop in vegetative stage 25 DAT having shoot damage

* Author for correspondence

caused by *L. orbonalis* to the extent of more than 10 per cent. *T. chilonis* orientation behaviour study conducted adopting sentinel egg card technique (Niranjana, 2015). *Corcyra* egg card having approximately 0.0625 cc parasitized eggs fixed in centre surrounded by each 0.0125 cc unparasitized *Corcyra* egg placed in 60 cm and 120 cm distance in all four directions constituted an experimental unit. Five such units were arranged randomly in half acre of the cropped area. A minimum of more than five meter distance was maintained between the experimental units. After three days of parasitoid release, the baited cards were brought to the laboratory and the parasitized eggs (blackened eggs) were counted. Data was compared based on the number of parasitized eggs in each bait cards. Weather data *viz.*, wind direction and wind speed corresponding to the experimental period recorded in Meteorological unit of Agricultural College and Research Institute, Killikulam was used for further interpretation. Experiment was repeated eight times and the data were compared observation week wise with wind direction that prevailed.

2. On field host *L. orbonalis* egg in brinjal crop

To understand the parasitization behaviour of *T. chilonis* on the field host *L. orbonalis* eggs *insitu* in field condition, the parasitoid was released at the rate of 1cc per hectare in brinjal crop in the vegetative stage having a shoot damage caused by *L. orbonalis*. The extent of damage observed was more than 20 per cent. The *L. orbonalis* eggs (10 eggs) were located by using hand lens and tagged with bright colour tags before the parasitoid release for easy identification. *Corcyra* egg card having approximately 0.0625 cc parasitized eggs were placed in the prefixed parasitoid release spots. After three days of parasitoid release, the parasitized eggs were counted and brought to the laboratory for further observation. Data was compared based on the number of parasitized eggs in each direction and the parasitoid emergence, the species identity of *T. chilonis* was established based on the taxonomic features (Niranjana, 2015). Experiment was repeated six times. Weather data *viz.* wind direction and wind speed corresponding to the experimental period recorded in Meteorological unit

of Agricultural College and Research Institute, Killikulam was used for further interpretation. Experiment was replicated five and repeated seven times and data along with direction prevailed during the parasitoid release period was tabulated observation wise.

Orientation behaviour of *T. chilonis* under field condition (Sentinel Egg Card Technique)

The result of the field experiment conducted using sentinel egg card technique is furnished in Table 1. During first observation conducted during 39th std. week, the mean level of parasitization ranged from 20 per card in South direction and 47 in North direction, during this period wind ward direction was in South. During 45th std. week (Observation II), a maximum parasitization was recorded in North direction (20.20 eggs/ card) and a minimum parasitization was observed in East direction (9.20 eggs/ card) and during this period wind ward direction was in South. During observation III (46th std. week) the mean level of parasitization ranged from 7.80 per card in South direction and 35.80 eggs per card in West direction and during this period the wind ward direction was in East. In the observation conducted during 48th std. week, the wind ward direction was remained same, a maximum level of parasitization was recorded in West direction (33.00 eggs/ card) and a minimum level of parasitization was observed in South direction (15.80 eggs/ card). During the subsequent observation V (6th std. week), the mean level of parasitization ranged from 6.80 eggs per card in North direction and 18.80 eggs per card in South direction. During this period the wind ward direction was in North. During 6th observation (8th std. week), a maximum parasitization was recorded in East direction (19.60 eggs/ card) and a minimum parasitization was observed in South direction (9.60 egg/ card) and during this period the wind ward direction was in West. During observation VII (10th std. week), the peak level of parasitization was recorded in East direction (15.40 eggs/ card) and minimum level of parasitization was observed in South direction (8.00 eggs/ card). In the final observation repeated during 13th std. week, a maximum level of parasitization was recorded in

North direction (10.80 eggs/ card) and a minimum level of parasitization was recorded in West direction (8.00 eggs/ card), during this period the wind ward direction was in South.

Orientation behaviour of *T. chilonis* on *L. orbonalis* eggs in-suit under field condition

Based on the above result of the preliminary studies conducted on the orientation behaviour of *T. chilonis*, involving laboratory host egg (*Corcyra* egg) a subsequent experiment was conducted to

assess the orientation behaviour of *T. chilonis* on the *L. orbonalis* in field condition. Result is presented in Table 2.

During the first observation (18th std. week), the mean level of parasitization recorded ranged from 1.60 eggs in South direction and 3.60 eggs in East direction, during this period wind ward direction was West. During observation II made in 19th std. week, maximum level of parasitization was recorded in West direction (2.20 eggs) and a minimum level of parasitization was observed West direction (0.60

Table 1. Extend of parasitization of *T. chilonis* in brinjal field influence by wind direction (Sentinel Egg Card Technique)

Direction	Number of parasitized eggs/ card							
	Observation I	Observation II	Observation III	Observation IV	Observation V	Observation VI	Observation VII	Observation VIII
	(39 th std. week)	(45 th std. week)	(46 th std. week)	(48 th std. week)	(6 th std. week)	(8 th std. week)	(10 th std. week)	(13 th std. week)
East	22.00	09.20	15.40	19.80	12.20	19.60	15.40	07.80
West	23.00	16.60	35.80	33.00	10.20	17.20	10.60	08.00
North	47.00	20.20	16.00	20.00	06.80	15.60	10.00	10.80
South	20.00	10.40	07.80	15.80	18.80	09.60	08.00	08.40
Wind direction	North	North	West	West	South	East	East	North

Table 2. Extend of parasitization by *T. chilonis* on *L. orbonalis* egg in brinjal field influence by wind direction

Direction	Number of parasitized eggs					
	Observation I	Observation II	Observation III	Observation IV	Observation V	Observation VI
	(18 th std. week)	(19 th std. week)	(20 th std. week)	(21 th std. week)	(23 th std. week)	(24 th std. week)
East	3.60	2.20	1.40	2.60	1.80	0.40
West	2.00	0.60	3.20	3.00	0.80	1.40
North	3.00	1.80	5.40	4.20	5.60	2.20
South	1.60	2.00	4.00	3.00	4.60	2.20
Direction	East	East	North	North	North	North

egg). During this period wind ward direction was west. During 3rd observation period *i.e.* on 20th std. week ththth, the mean number of parasitization recorded ranged from 1.40 eggs in East direction and 5.40 eggs in North direction, during this period the wind ward direction was South. During the subsequent week (21th std. week), the wind direction remained same and maximum parasitization was recorded in North direction (5.60 eggs) and a minimum parasitization was observed in East direction (2.60 eggs). During subsequent observations the wind direction remained the same at North to South direction, a maximum level of parasitization (5.60 eggs) was observed in North direction in observation V and 2.20 eggs observed in observation VI. In East direction during this period of observation a minimum parasitized egg were recorded.

In the observation made on the orientation behaviour of *Trichogramma* under field condition, it is interesting to note that the wind direction has an influence on orientation behaviour of *T. chilonis*. The change in wind direction has resulted in shifting the parasitoid orientation on the host egg towards the wind stream. The consistency of observation indicates existence of positive correlation between parasitization and wind stream direction under field condition was recorded both in the sentinel egg card technique and *L. orbonalis* eggs. The kairomone fumes carried by the air current may attribute such variations in the orientation behaviour. This is the first such research report for the dispersal behaviour

of *T. chilonis* under field condition on both the *C. cephalonica* and *L. orbonalis* eggs under field condition.

REFERENCES

- Canto-Silva C.R., Kolberg R., Romanowski H.P. and Redaelli L. (2006) Dispersal of the egg parasitoid *Gryon gallardoi* (Brethes) (Hymenoptera: Scelionidae) in tobacco crops. *Brazilian Journal of Biology* 66: 9-17. <http://dx.doi.org/10.1590/S1519-69842006000100003>
- Fournier F. and Boivin G. (2000) Comparative dispersal of *Trichogramma evanescens* and *Trichogramma pretiosum* (Hymenoptera: Trichogrammatidae) in relation to environmental conditions. *Environmental Entomology* 29: 55-63. <https://doi.org/10.1603/0046-225X-29.1.55>
- Kolliker-Ott U.M., Bigler F. and Hoffmann A.A. (2004) Field dispersal and host location of *Trichogramma brassicae* is influenced by wing size but not wing shape. *Biological Control* 31: 1-10. <https://doi.org/10.1016/j.biocontrol.2004.04.018>
- Li L.Y. (1994) Worldwide use of *Trichogramma* for biological control of different crops: A survey, In: Wajnberg, E, Hassan, S. A. (Eds.). *Biological control with egg parasitoids*. CAB International; Wallingford, U. K.
- Niranjana V. (2015) Bio-control based management of brinjal shoot and fruit borer, *Leucinodes orbonalis* Guenee. Unpublished Ph.D. (Ag.) Thesis, Tamil Nadu Agricultural University, Coimbatore, India.



Evaluation of pongamia oil soap against leaf hopper, *Amrasca biguttula biguttula* (Ishida) infesting okra

Anu Thomas* and K. M. Sreekumar

Department of Agricultural Entomology, College of Agriculture, Padannakad, 671314, Kerala, India. Email: anu32794@gmail.com; sreekumar.km@kau.in

ABSTRACT: Field studies on evaluation of pongamia and neem oil soap at various concentrations against okra leaf hopper, *Amrasca biguttula biguttula* (Ishida) was carried out during the year 2018-19. Treatments i.e. T₁: Pongamia oil soap 0.6%; T₂: Pongamia oil soap 1%; T₃: Pongamia oil soap 2%; T₄: Neem oil soap 0.6%; T₅: Soap solution 0.5%; T₆: Quinalphos 25 EC @ 0.05%; T₇: Standard check applied once at vegetative stage and twice during reproductive stage. Quinalphos 25 EC @ 0.05 % was effective followed by pongamia oil soap 2 per cent, pongamia oil soap 1 per cent, neem oil soap 0.6 per cent and pongamia oil soap 0.6 per cent. The effectiveness of the soap reduced after seven days of treatment. © 2019 Association for Advancement of Entomology

KEY WORDS: Pongamia, neem oil soap, leaf hopper

Okra, *Abelmoschus esculentus* (L). Moench also known as lady's finger native to West Africa is a warm season vegetable crop cultivated for its tender and delicious fruits which remains productive even in the long summers of South East. India stands first in okra production with 62 per cent share of world production. With a production of 6094.94 MT during 2017-18, okra is cultivated in 509.02 ha of area with a productivity of 11.97MT/ha (Anon., 2018). One of the major constraints for okra production is heavy infestations of several insect pests which exert both quantitative and qualitative loss. Insect pests caused 48.97 per cent loss to the tune of 77.78 q/ha (Kanwar and Ameta, 2007). Early stages of crop is infested by sucking pests like leafhoppers, aphids and whiteflies that cause huge economic loss due to sucking of the cell sap and making the plant weak. Krishnaiah (1980) reported that leafhoppers alone can cause a yield loss of 54.04 per cent in okra.

Okra being harvested at frequent intervals, application of synthetic insecticides may lead to toxic residues in fruits causing health hazards. Non judicious use of synthetic pesticides over the last four to five decades have resulted in many negative consequences like resurgence and resistance of pests and pesticide residues in farm products (Kabir *et al.*, 1994; Mahapatro, 1999). Hence, to control these pests and to reduce such risks, alternative environmentally safe methods like bio pesticides, botanicals etc., are to be adopted (Khade *et al.*, 2014).

Pongamia pinnata (L.) is a multipurpose tree species of pea family Fabaceae which is widely distributed in India, China, Bangladesh and Australia. It is commonly called as Indian Beech Tree or Karanj. Karanj oil is thick yellowish red/brown non edible oil, extracted from seed. It is used for the treatment of rheumatism and skin diseases, in soap

* Author for correspondence

industry, as a fuel, lubricant and pesticide. The secondary metabolites like flavanoids, chalcones, steroids and terpenoids in pongamia oil serve as natural pest repellents (Pavela, 2009). It has insecticidal (antifeedent) properties similar to neem oil and act against a number of insect pests. Tripathi *et al.* (2012) stated that pongamia oil is safe to humans and other mammals. Hence an experiment was carried out to evaluate the efficacy of botanical product “pongamia oil soap” at various concentrations against leaf hopper infesting okra..

Pongamia oil soap was prepared according to the technology used for the preparation of Ready To Use neem oil garlic soap, the first botanical of KAU, approved by Kerala Agricultural University (Varma, 2018).

A field study was carried out in the Instructional farm, College of Agriculture, Padannakkad during 2018 – 19. Seeds of okra (Variety: Arka Anamika) were sown at a spacing of 60 x 45 cm² during October to January under randomized block design (RBD). There were seven treatments (Table 1). Spraying of pongamia oil soap solution was done at 30 days after sowing (DAS) during vegetative phase and during the reproductive stage at 55 and 80 DAS using 16 L Knapsack sprayer. Spraying was carried out during evening hours and precautions were taken to avoid drift. Four plants out of eight were randomly selected and tagged in each plot for recording the observations. Population density of leaf hopper was recorded by counting the number of nymphs and adults from five leaves (one top, two middle and two lower) of selected four plants on one day prior to and 1, 3, 5, 7 and 14 days after spraying of various treatments. Data on the population density of sucking pests were analyzed after square root transformation. The data were analysed using analysis of variance (ANOVA). Web Agri Stat Package (WASP) was used to compare the significance of each treatment.

The results revealed that a day after the first application, the plot treated with quinalphos 25 EC at 0.05 per cent (standard check) recorded the least count of 1.75 leaf hoppers/5 leaves, followed by pongamia oil soap 2 per cent (2.81 leaf hoppers/5 leaves) and pongamia oil soap 1 per cent (3.75 leaf

hoppers/5 leaves) which were on par with the standard check. All the treatments stood significantly superior over the control (5.38 leaf hoppers/5 leaves) whereas soap solution 0.5 per cent (5.19 leaf hoppers/5 leaves) was on par with control. It was further observed that after three days of application, among the botanicals, pongamia oil soap 2 per cent showed lowest population of 1.19 leaf hoppers/5 leaves which was at par with standard check (1.00 leaf hoppers/5 leaves). It was followed by pongamia oil soap 1 per cent, neem oil soap 0.6 per cent and pongamia oil soap 0.6 per cent (2.81, 3.00 and 3.69 leaf hoppers/ 5 leaves) respectively which was at par with each other. Soap solution 0.5 per cent and control showed highest population count of 5.31 and 5.56 leaf hoppers/5 leaves which was at par with each other. Five days after first application lowest hopper population was observed in standard check (0.31 leaf hoppers/ 5 leaves) which was immediately followed by pongamia oil soap 2 per cent (0.81 leaf hoppers/5 leaves). A gradual decrease in the population was observed in all the treatments except control and soap solution 0.5 per cent on the seventh day after first application with minimum population recorded in standard check (0.13 leaf hoppers/ 5 leaves) which was on par with pongamia oil soap 2 per cent (0.44 leaf hoppers/ 5 leaves). Pongamia oil soap 1 per cent was at par with neem oil soap 0.6 per cent with a population count of 1.00 and 1.25 leaf hoppers/5 leaves respectively. A gradual increase in leaf hopper population in all the treatments on fourteenth day after first application and among the botanicals pongamia oil soap 2 per cent recorded the lowest leaf hopper population of 0.75 leaf hoppers/5 leaves which was at par with standard check 0.31 leaf hoppers/5 leaves. Soap solution 0.5 per cent and control showed the highest population count of 7.44 and 7.50 leaf hoppers/5 leaves which was at par with each other (Table 1).

Precount of leaf hopper population prior to second application was at a range of 5.37 - 8 leaf hoppers/ 5 leaves /plant. A day after the second application, a reduction in the leaf hopper population was observed in all the treatments except in soap solution 0.5 per cent (8.06 leaf hoppers/ 5 leaves) and control (8.1 leaf hoppers/ 5 leaves) which were on

par with each other. Quinalphos 0.05 per cent (standard check) recorded the least count of 3.13 leaf hoppers/ 5 leaves, followed by pongamia oil soap 2 per cent (4.63 leaf hoppers/5 leaves). Pongamia oil soap 1 per cent (5.81 leaf hoppers/ 5 leaves), neem oil soap 0.6 per cent (6.06 leaf hoppers/ 5 leaves) and pongamia oil soap 0.6 per cent (6.19 leaf hoppers/ 5 leaves) were found on par with each other.

A similar trend was observed at three days after second application with lowest population recorded in standard check (1.00 leaf hoppers/ 5 leaves) followed by pongamia oil soap 2 per cent (2.50 leaf hoppers/ 5 leaves). Pongamia oil soap 1 per cent, neem oil soap 0.6 per cent and pongamia oil soap 0.6 per cent (3.88, 4.25 and 4.50 leaf hoppers/ 5 leaves) respectively were found on par with each other. Standard check showed the lowest hopper population of 0.19 leaf hoppers/5 leaves followed by pongamia oil soap 2 per cent (0.94 leaf hoppers/ 5 leaves) at five days after second application while Soap solution 0.5 per cent and control showed the maximum leaf hopper population with 9.00 and 9.31 leaf hoppers/5 leaves. Observations at seventh day after second application during rabi season revealed standard check as the best treatment with 0.00 leaf hopper population as significantly superior treatment followed by pongamia oil soap 2 per cent (0.56 leaf hoppers/ 5 leaves) and pongamia oil soap 1 per cent (1.69 leaf hoppers/ 5 leaves). However all the treatments were significantly superior to control and soap solution 0.5 per cent. A gradual increase in leaf hopper population was observed in all the treatments at 14 days after application with standard check showing the lowest population count of 0.56 leaf hoppers/ 5 leaves, while among the botanicals pongamia oil soap 2 per cent recorded the lowest leaf hopper population of 1.06 leaf hoppers/5 leaves. Neem oil soap 0.6 per cent (3.94 leaf hoppers/5 leaves) and pongamia oil soap 0.6 per cent (4.06 leaf hoppers/5 leaves) were on par with each other.

Precount of leaf hopper population prior to third application was at a range of 7.93 – 11.25 leaf hoppers/5 leaves /plant. A day after the third application pongamia oil soap 2 per cent showed

least population of 5.50 leaf hoppers/5 leaves among the botanicals which was on par with standard check (11.94 leaf hoppers/5 leaves). Pongamia oil soap 1 per cent (7.00 leaf hoppers/5 leaves) was the next best treatment followed by neem oil soap 0.6 per cent (7.75 leaf hoppers/5 leaves) which was on par with pongamia oil soap 0.6 per cent (8.31 leaf hoppers/5 leaves). Soap solution 0.5 per cent (11.19 leaf hoppers/5 leaves) was at par with control. Third day count of leaf hopper population recorded the lowest population of 2.00 leaf hoppers/ 5 leaves in standard check followed by pongamia oil soap 2 per cent, pongamia oil soap 1 per cent, neem oil soap 0.6 per cent and pongamia oil soap 0.6 per cent with 3.38, 4.44, 5.00 and 5.44 leaf hoppers/ 5 leaves respectively. A similar trend was observed at five days and seven days after third application were standard check showed the lowest hopper population of 1.19 and 0.81 leaf hoppers/ 5 leaves followed by pongamia oil soap 2 per cent (2.38 and 2.13 leaf hoppers/ 5 leaves). While the population was 12.50 and 13.00 leaf hoppers/5 leaves at seven days after third application in soap solution 0.5 per cent and control respectively which were on par with each other. A gradual increase in leaf hopper population in all the treatments at 14 days after application was observed while among the botanicals pongamia oil soap 2 per cent recorded the lowest leaf hopper population of 2.81 leaf hoppers/ 5 leaves after the standard check 1.25 leaf hoppers/ 5 leaves which was followed by pongamia oil soap 1 per cent, neem oil soap 0.6 per cent which was on par with pongamia oil soap 0.6 per cent with 4.19, 4.75 and 5.06 leaf hoppers/ 5 leaves respectively. Soap solution 0.5 per cent and control showed the highest count of 13.19 and 14.06 leaf hoppers/ 5 leaves respectively (Table 1).

From the data observed during the rabi season it is evident that all the treatments except soap solution 0.5 per cent was effective in reducing the leaf hopper population significantly as compared to that of control. In general the efficacy of pongamia oil soap at 0.6, 1 and 2 per cent and neem oil soap 0.6 per cent were significantly superior over control, however the standard check (Quinalphos 25 EC @ 0.05 per cent) was superior to pongamia and

Table 1. Average population density of leaf hoppers during rabi season from October 2018 to January 2019

Treat- ments	Number of leaf hoppers/5 leaves																	
	First application						Second application						Third application					
	1 DBA	1 DAA	3 DAA	5 DAA	7 DAA	14 DAA	1 DBA	1 DAA	3 DAA	5 DAA	7 DAA	14 DAA	1 DBA	1 DAA	3 DAA	5 DAA	7 DAA	14 DAA
Ponga- mia oil soap 0.6%	4.94 (2.21)	4.31 (2.07) ^{ab}	3.69 (2.02) ^{ab}	2.50 (1.56) ^b	2.38 (1.68) ^b	3.31 (1.94) ^b	7.75 (2.87) ^a	6.19 (2.48) ^b	4.50 (2.23) ^b	3.06 (1.88) ^b	3.38 (1.96) ^b	4.06 (2.01) ^b	10.37 (3.21) ^{ab}	8.31 (2.88) ^b	5.44 (2.33) ^b	4.94 (2.22) ^b	4.44 (2.10) ^b	5.06 (2.24) ^b
Ponga- mia oil soap 1%	4.44 (2.07)	3.75 (1.90) ^{abc}	2.81 (1.81) ^b	1.63 (1.27) ^c	1.00 (1.22) ^c	1.56 (1.42) ^c	7.06 (2.73) ^{ab}	5.81 (2.40) ^b	3.88 (2.08) ^b	1.88 (1.53) ^c	1.69 (1.46) ^c	2.06 (1.43) ^c	10 (3.16) ^b	7.00 (2.63) ^b	4.44 (2.09) ^{bc}	3.63 (1.90) ^c	3.19 (1.78) ^c	4.19 (2.04) ^c
Ponga- mia oil soap 2%	5.06 (2.22)	2.81 (1.58) ^{bc}	1.19 (1.25) ^c	0.81 (0.89) ^d	0.44 (0.96) ^d	0.75 (1.11) ^d	6.31 (2.60) ^{bc}	4.63 (2.15) ^c	2.50 (1.72) ^c	0.94 (1.18) ^d	0.56 (1.02) ^d	1.06 (1.02) ^d	8.75 (2.95) ^c	5.50 (2.34) ^c	3.38 (1.82) ^c	2.38 (1.52) ^d	2.13 (1.45) ^d	2.81 (1.67) ^d
Neem oil soap 0.6%	4.13 (2.01)	4.06 (2.00) ^{ab}	3.00 (1.86) ^b	2.06 (1.43) ^{bc}	1.25 (1.31) ^c	1.69 (1.46) ^c	7.18 (2.77) ^{ab}	6.06 (2.45) ^b	4.25 (2.17) ^b	2.94 (1.85) ^b	2.81 (1.81) ^b	3.94 (1.97) ^b	10.25 (3.20) ^{ab}	7.75 (2.78) ^b	5.0 (2.23) ^b	4.44 (2.10) ^{bc}	4.00 (1.99) ^b	4.75 (2.17) ^b
Soap solution 0.5%	4.25 (1.97)	5.19 (2.25) ^a	5.31 (2.40) ^a	6.00 (2.43) ^a	6.63 (2.65) ^a	7.44 (2.81) ^a	7.87 (2.89) ^a	8.06 (2.83) ^a	8.44 (2.98) ^a	9.00 (3.08) ^a	9.63 (3.18) ^a	10.25 (3.19) ^a	11 (3.31) ^a	11.19 (3.34) ^a	11.63 (3.40) ^a	12.06 (3.47) ^a	12.50 (3.53) ^a	13.19 (3.63) ^a
Quinalph os 25 EC 0.05%	4.00 (1.97)	1.75 (1.27) ^c	1.00 (1.17) ^c	0.31 (0.55) ^e	0.13 (0.78) ^d	0.31 (0.88) ^d	5.37 (2.41) ^c	3.13 (1.76) ^d	1.00 (1.19) ^d	0.19 (0.82) ^e	0.0 (0.70) ^e	0.56 (0.72) ^e	7.93 (2.81) ^c	4.69 (2.14) ^c	2.0 (1.38) ^d	1.19 (1.08) ^e	0.81 (0.89) ^e	1.25 (1.11) ^e
Control	4.69 (2.10)	5.38 (2.25) ^a	5.56 (2.41) ^a	6.25 (2.49) ^a	6.81 (2.70) ^a	7.50 (2.82) ^a	8 (2.91) ^a	8.1 (2.92) ^a	8.38 (2.97) ^a	9.31 (3.13) ^a	10.0 (3.23) ^a	11.0 (3.31) ^a	11.25 (3.35) ^a	11.94 (3.45) ^a	12.19 (3.48) ^a	12.75 (3.56) ^a	13.0 (3.60) ^a	14.06 (3.74) ^a
C.D (0.05)	NS	0.62	0.49	0.28	0.25	0.25	0.24	0.17	0.24	0.19	0.23	0.22	0.15	0.25	0.29	0.20	0.14	0.13

Figure in parenthesis denotes square root transformed value. Means followed by similar letters are not significantly different; DBA- Day before application; DAA- Days after application; NS- Non significant.

neem oil soap. Similar findings were reported by Kumar (2013), where he stated that imidacloprid followed by triazophos, quinalphos and neem based insecticides were effective in reducing jassid population as compared to that of control.

After three sprays, pongamia oil soap 2 per cent was effective in reducing the leaf hopper population followed by pongamia oil soap 1 per cent, neem oil soap 0.6 per cent and pongamia oil soap 0.6 per cent. Efficacy of pongamia oil soap was reduced with the reduction in concentration. Even though pongamia oil soap 0.6 per cent and neem oil soap 0.6 per cent showed similar results, better efficacy was showed by neem oil soap 0.6 per cent in reducing leaf hopper population. Similar results were observed by Anitha (2007) who reported that among the botanicals and myco pathogens, neem oil 2 per cent recorded least leafhopper population (2.90 leafhoppers/3 leaves) followed by pongamia oil 2 per cent (3.44 leafhoppers/3 leaves) on okra. Superiority of neem based insecticides have been reported by Mandal *et al.* (2006) and Sinha and Sharma (2007). Higher efficacy of pongamia oil soap 2 per cent against leaf hopper as observed in this study is in line with Sardana and Krishnakumar (1989), who stated that maximum reduction in hopper population to the extent of 17.51 leafhoppers per plant was recorded in case of karanj oil (2 per cent) as compared to neem oil (0.5 per cent) and garlic oil (0.5 to 1%).

ACKNOWLEDGMENT

We thank Kerala Agricultural University for providing financial support.

REFERENCES

- Anonymous (2018) *Horticultural Statistics at a Glance 2018*. Ministry of Agriculture & Farmers' Welfare, Govt. of India. 490 p.
- Anitha K.R. (2007) Seasonal incidence and management of sucking pests of okra. M.Sc.(Ag) thesis, University Of Agricultural Sciences, Dharwad. 90 p.
- Kabir K.H., Roul P.M.A., Islam H.N., and Malakar P.K. (1994) Efficacy of different insecticides in controlling brinjal shoot and fruit borer, *Leucinodes orbonalis* Guen. Journal of Zoology of Rajshahi University, 13: 1-8.
- Kanwar N. and Ameta O.P. (2007) Assessment of losses caused by insect pests of okra. Pestology 31(6): 45-47.
- Khade K.N., Undirwade D.B., Tembhurne R.D. and Lande G.K. (2014) Biorational management of sucking pests of cowpea *Vigna sinensis* L. Trends in Bioscience 7(20): 3212-3217.
- Krishnaiah, K. (1980) Methodology for assessing crop losses due to pests of vegetables. Methodology for assessing crop losses due to pests of vegetables. pp.259-267.
- Kumar D. (2013) Management of major insect pests of okra (*Abelmoschus esculentus* (L.) Moench.) in agro-climatic condition of Ranchi. M.Sc. (Ag) thesis, Birsa Agricultural University, Ranchi. 130 p.
- Mahapatro G.K. (1999) Pesticides: boon or bane? Discussing its changed role in integrated pest management. Pestology 23(6): 30-36.
- Mandal S.K., Sah S.B. and Gupta S.C. (2006) Neem based integrated management approaches for insect-pests of okra (*Abelmoschus esculentus* L. Moench). International Journal of Agricultural Science 2: 499-502.
- Pavela R. (2009) Effectiveness of some botanical insecticides against *Spodoptera littoralis* Boisduval (Lepidoptera: Noctuidae), *Myzus persicae* Sulzer (Hemiptera: Aphididae) and *Tetranychus urticae* Koch (Acari: Tetranychidae). Plant Protection Science 45: 161-167.
- Sinha S.R. and Sharma R.K. (2007) Efficacy of neem and synthetic pesticides against insect pests of okra. Indian Journal of Entomology 69(4): 42-44.
- Tripathi A., Singh N., Misra M., Dwivedi H.D. and Dube, N.K. (2012) An earth-friendly herbal pesticide from *Pongamia pinnata* L. Current Botany 3(2): 1-2.
- Varma Y.C.K. (2018) "Ready To Use Veppenna Veluthulli Soap". Kalpadhenu. Quarterly Malayalam Magazine Jan-March 2018 by Kerala Agricultural University. pp: 45-46.



Effect of carbofuran on quantitative and qualitative alterations in haemolymph of larva of *Oryctes rhinoceros* L. (Coleoptera: Scarabaeidae)

V.S. Salini

Department of Environmental Sciences, University of Kerala, Thiruvananthapuram 69558, India.
Email: salinivs81@gmail.com

ABSTRACT: Investigation to evaluate the toxicity of carbofuran pesticides on haematological parameters of third instar larvae of *Oryctes rhinoceros* L. Indicated alterations in total haemocyte count and differential haemocyte count for toxicity assessment. Various doses of carbofuran (0.05g, 0.010g and 0.015 g) applied on insect through oral route and its impact after 24 hours of its application revealed that various doses of carbofuran exert specific alterations in both total and differential haemocytes of insect haemolymph. © 2019 Association for Advancement of Entomology

KEYWORDS: carbofuran, changes, *Oryctes rhinoceros*, toxicity, haemocytes

Haemocytes and immune responses are considered to be potential indicators of toxicity in insects. Hence the study of changes in either the total or part of insect haemolymph is a proper system for detecting effects of toxic substances. Toxic substances induce an irreversible cytopoiesis of the host's haemocytes (Vladimir *et al.*, 1991). There are very little study on the haemograms of insects exposed to toxic substances and the role of haemocytes and direct detoxification of pesticides. Cytopoiesis has been proven in insects exposed to lethal doses of arsenates, nicotine dichloro-diethyl ether, carbon tetrachloride and DDT (Vladimir *et al.*, 1991).

Carbofuran is a very toxic pesticide widely used by farmers and registered for more than 25 crops in India. As a result of widespread use, air, water and food are polluted with carbofuran and its metabolites (Bushway *et al.*, 1992; Kross *et al.*, 1992; Waite *et al.*, 1992). Carbofuran has high

toxicity to human through the oral and inhalation routes of exposure affecting the nervous system. It is highly toxic to birds, bees, fish and non-target species due to its high acute toxicity. The residues of these chemical have been reported in plant, soil and water there for its use has been restricted or banned in many countries (Goulart *et al.*, 2015). Present investigation is focused to evaluate the toxicity of carbofuran pesticides on haematological parameters of third instar larvae of *Oryctes rhinoceros* L. to understand the impacts on circulatory system of insects.

Third instar larvae of coconut beetle, *O. rhinoceros* one of the important economic pests of coconut palm having long life span, voracious feeding habit, sensitivity to insecticides or any control agent and ease in rearing and handling the larvae of *Oryctes rhinoceros* being excellent experimental animal was used as test animal. Various stages of larvae

* Author for correspondence

were collected from the local manure pits and reared in the laboratory on cow dung which formed the stock. In the present study the third instar larvae, those have long lifespan, peculiar voracious feeding habit and ease of rearing were considered for the isolation from the stock and each larva kept separately in plastic containers with cow dung as feed.

Carbofuran is broad spectrum commercial grade carbamate insecticide used for control of insects, mites and nematodes and being also used against soil and foliar pests of field, fruits, vegetables and forest crops. Carbofuran is highly toxic by inhalation or ingestion and moderately toxic by dermal absorption.

The chemical name of carbofuran is 2, 3- dihydro 2, 2- dimethyl-7- benzofuranyl methyl carbamate. Formulations of carbofuran include flowable or granular form Granular form like Furadan 3G used in the present study is usually prepared by mixing technical grade materials with silica based particles in required proportions. Pure form is a white crystalline solid with slight phenolic odour. It has a melting point of 153-154°C. It is slightly soluble in water. It is highly soluble in N- methyl-2- pyrrolindone, dimethyl formaldehyde, dimethyl sulfoxide, acetone, aectonitrite, methylene chloride, cyclohexanone, benzene and xylene. It is stable under alkaline conditions. Degradation of carbofuran in soil takes place by microbial action. In water, direct photolysis and photo irradiation via hydroxyl radical, 2-hydroxy furadan and furadan phenol are the major pathways of degradation. In the air, degradation occurs by photolysis. Half-life in water is 5.1 weeks at pH 7.0 and 1.2 hours at pH 10 and in the soil several days to over three months (HSDB, 1998)

Three doses of the of the toxicity viz., 0.05, 0.010 and 0.015g doses of carbofuran mixed with 30g cow dung each was kept in containers for a day. Then actively feeding larvae after 30-35 days of moulting with an average weight of 9.6 ± 0.01 g were introduced into each experimental container with four replications along with a control without furadan. Pesticide dose was chosen based on result of preliminary continuous bioassays and probit

analysis, (Finney, 1971). Behavioural changes and toxic signs were recorded daily.

Haemolymph was collected from both treated and control larvae. A puncture was made on the body wall so as to draw the exuded haemolymph using a capillary tube and kept in eppendorf tubes containing a few crystals of phenylthiourea (Wyatt and Pan, 1978) to prevent melanisation. The collected samples were used immediately, for analysis.

Haemolymph smear was prepared according to the method of Arnold and Hinks (1979). The smear of haemolymph was prepared by placing a drop of freshly extracted haemolymph on a clean glass slide and a thin uniform smear was drawn by using a rectangular cover slip at 45 degrees. After air drying for few minutes, the smear fixed in methanol and stained with Giemsa's stain for 5 min., washed in double distilled water and mounted in DPX.

Total haemocyte count (THC) was done by the method of Gosh and Roy (1984). A Newbaur Haemocytometer was used for this purpose (Witting, 1966). The haemolymph was initially collected on micro slides. This haemolymph was taken into a clear WBC pipette filling up to the mark 0.5. Care was taken to avoid air bubbles. The blood sticking to the tip of the pipette was wiped out. Dilution medium (Turk's dilution fluid) was pipette up to the mark 1.1. The haemolymph was allowed to mix thoroughly with the dilution medium. The fluid from the lower end of the pipette was discarded. The counting chamber of the haemocytometer was charged and the preparation was kept aside for the haemocytes to settle. The haemocytes were counted from the four corners squares with the aid of a microscope. Total number of haemocytes was calculated by multiplying the average number of cells in one chamber with the volume of one square of haemocytometer and dilution factor, i.e., average number of cells in one chamber $\times 10 \times 20$. Following formula of Jones (1962) was adapted for calculations:

$$\frac{\text{Haemocytes in 1mm Squares} \times \text{dilution} \times \text{depths at the Chamber}}{\text{number of 1mm square counted}}$$

Haemolymph smears prepared from each experimental larva were examined under a light

microscope, and all cells were counted. The total cells were counted and the percentage of each kind of haemocytes Prohaemocytes (PRC), Plasmotocytes (PLC), Granulocytes (GRC), Adipocytes (ADC), Spherulocytes (SPC) and Oenocytes (OEC) were calculated to arrive the differential haemocytes. All the data were analysed statistically at $p < 0.005$. The significance was calculated by using ANOVA.

Differential Haemocyte Count (DHC) of control and exposed to carbofuran for 24 hours

Differential Haemocyte Count in experiment and control larvae is given in Table 1. Proportion of the PRC in the control was 46.00 ± 3.79 per cent while 18.33 ± 1.45 PLC, 20.0 ± 0.58 GRC, 6.67 ± 0.88 ADC, 5.67 ± 1.45 SPC and 3.33 ± 0.88 OEC indicating the population size of PRC was the highest followed by GRC and PLC. The least population was observed in OEC followed by SPC and ADC. When the larvae exposed to 0.005g carbofuran for 24 h the PRC, PLC and GRC were 17.67 ± 1.45 , 9.00 ± 1.15 and 60.0 ± 2.31 per cent respectively expressing a steep elevation of GRC count over control as against PLC showing a significant reduction in their population. Proportion of the other cell types were 7.00 ± 0.58 , 4.66 ± 0.33 and 1.67 ± 0.33 per cent respectively for ADC, SPC and OEC. A slight decrement was noted in the count of SPC and OEC from control value. Exposing to the higher dose of 0.01g carbofuran, the mean population of PRC was 13.33 ± 0.88 per cent while PLC- 8.00 ± 1.53 , GRC- 68.33 ± 0.88 , ADC - 4.67 ± 0.88 , SPC - 3.33 ± 0.67 and OEC- 2.33 ± 0.88 per cent wherein, GRC showed steep significant elevation as against the decrement of ADC, SPC and OEC though statistically insignificant.

However 0.015 g carbofuran treated larvae haemolymph exhibited that the mean counts of haemocytes were PRC- 11.00 ± 1.15 per cent of PRC, 6.33 ± 0.88 PLC, 72.00 ± 1.73 GRC, - 5.33 ± 0.33 ADC, 4.00 ± 0.58 SPC and 1.33 ± 0.33 per cent OEC respectively indicating significant increase in case of PRC, PLC and GRC, however,

insignificant in the case of ADC, SPC and OEC count. Overall assessment expressed a significant sharp increase of granulocytes due to exposure larvae corresponding with increase in dose of carbofuran as against other haemocytes got decreased over control.

Cytological study of haemolymph of *O. rhinoceros* larvae-control and exposed to carbofuran

Haemocytes of control larvae comprised of PRCs, PLCs, GRCs, ADCs, SPRs and OECs (Fig. 1). PRCs found in numerous groups were small round cells with dense homogenous cytoplasm and large nucleus. PLCs were spindle shaped cells with a centrally placed round nucleus and surrounding of abundant cytoplasm. GRCs were observed as large spherical or oval cells having more granular cytoplasm and centrally located round or elongated nucleus. ADCs were small round or slightly elongated and centrally or eccentrically located nucleus. The cytoplasm contained characteristic small to large refringent fat droplets and other non-lipid granules in addition to vacuoles. SPCs were round with small central or eccentric nucleus. A number of spherules are found in the cytoplasm. These cells are larger than granulocytes. OECs were small to large oval or spherical cells with a granular, thick, homogenous cytoplasm and centrally located small round nucleus.

High total haemocytes counts with moderate increase in granulocytes were found in the larvae exposed to 0.005g carbofuran for 24h (Fig. 2). Degeneration and nuclear pyknosis was observed in granulocytes. Reactive changes were observed in PLCs whose cytoplasm was darkly stained. Smears of the larvae exposed to 0.010g carbofuran for 24 h showed mild decrease in total haemocytes with increase in number of GRCs which were degenerated with distorted shape having irregular nucleus. Some of them showed enlargement. (Fig. 3).

Blood smear of larvae exposed to 0.015g exhibited mild decrease in total haemocytes with increase in GRCs which were more basidophilic with thickened granules. Clustering of cells with abnormal staining

was observed with ruptured cell membrane and distorted cell shape (Fig. 4). Carbofuran exposed larvae showed a significant decrease of total haemocytes and various cytopathological changes, particularly an increase in GRC and increased cellular damage compared to control.

The haemocytes of insects constitute a complex system of cells circulate in the haemolymph which play an essential role in immunity against invading substances through coagulation, phagocytosis, encapsulation and detoxification process. Haemocytes are several types and their primary functions also include storage and distribution of nutritive materials. Six types of haemocytes were identified in the haemolymph of *O. rhinoceros* larvae such as PRC, GRC, PLC, SPC, OEC and ADC (Annie, 1995). In the present study their response to different doses of carbofuran at various time periods were investigated. A drastic change in total haemocytes (THC) with various histopathological changes in haemocyte morphology was observed due to carbofuran intoxication. This is because haemocytes are known to respond to

various intrinsic or extrinsic factors. Under adverse conditions and at the time of experimental stress, numbers of haemocytes were reported to get increased (Shapiro, 1979, Gupta, 1985). However, the present investigation indicated a decrease in the total haemocytes due to carbofuran treatment which could be the result of degeneration of pathological cells caused by toxicity of carbofuran.

Number of haemocytes is a key factor in compaction of the encapsulation of invading foreign bodies (Sendi and Salehi, 2010). Moreover, PLC and GRC have been found to be most sensitive and the main phagocytic haemocytes in most of the insect studied (Crossley 1964, Arnold, 1970; Neuvarth, 1974; Akain and Sato, 1978). In this sense, differential haemocyte count (DHC) is more meaningful, because, present investigation found sharp increase of GRC in the haemolymph of treated larvae and other haemocytes showed numerical decline over control. Such an increase in the population size of GRC might be connected with the growing demand for cellular immunity (Gupta, 1985, 1986, 1991). This is because granular

Table 1. Total and differential haemocytes in the haemolymph of control *Oryctes rhinoceros* larvae exposed to carbofuran for 24 h.

Doses of carbofuran (g/larvae)	Total haemocyte count (THC) (cu/mm)	Differential haemocyte count (DHC) (%)					
		Prohaemocyte (PRC)	Plasma-tocyte (PLC)	Granulocyte (GRC)	Adipocyte (ADC)	Sperulocyte (SPC)	Oenocyte (OEC)
Control	7973.33± 1065.85a	46.00± 3.79a	18.33± 1.45a	20.0± 0.58a	6.67± 0.88a	5.67± 1.45a	3.33± 0.88a
0.005	13766.6± 523.87b**	17.67± 1.45 b**	9.00± 1.15 b**	60.0± 2.31b**	7.00± 0.58a	4.66± 0.33 a	1.67± 0.33a
0.010	6563.33± 545.60a	13.33± 0.88 c **	8.00± 1.53c**	68.33± 0.88c**	4.67± 0.88 a	3.33± 0.67 a	2.33± 0.88 a
0.015	3933.33± 348.01d*	11.00± 1.15 d **	6.33± 0.88d**	72.00± 1.73d**	5.33± 0.33 a	4.00± 0.58 a	1.33± 0.33 a
ANOVA	F=37.78 P=.000	F=56.83 P=.000	F=17.73 P=.001	F=242.37 P=.000	F=2.43 P=0.141	F=1.32 P=0.333	F=1.75 P = 0.234

Values are the mean of five observations ±SE

Common alphabets denote insignificant difference between control and doses

Different alphabets denote significant difference between control and doses

(*) significant at 5% level (**) significant at 1% level




Fig. 1. Blood smear shows heamocytes of control larvae X40x

- | | |
|-----------------|----------------|
| 1. Proheamocyte | 3. Adipocyte |
| 2. Plasmatocyte | 4. Sperulocyte |




Fig. 2. Blood smear shows heamocytes of 0.005g Carbofuran/ 24 hours

1. GRC shows degeneration
2. GRC shows nuclear pyknosis
3. PLC shows darkly stained cytoplasm

haemocytes are primarily involved in body defence activities (Ambrose and George, 1996). A study of *Atemisia annua* extract in *Eurygaster integriceps* revealed an alteration in the number of hemocytes and their phagocytic activity (Zibae and Bandani, 2010).

Pathological study of haemolymph indicated dose dependent cellular degeneration due to carbofuran treatment. Numerous changes in cytoplasm and nucleus observed in haemolymph of larvae treated with the highest dose. Vacuolization of cytoplasm and cellular clumping were the feature of high dose of carbofuran (0.015g) treated larvae as result of




Fig. 3. Blood smear shows heamocytes of 0.010g Carbofuran /24 hours

1. Distortion in cell shape
2. Degenerative changes with irregular nucleus
3. GRC shows cellular enlargement




Fig. 4. Blood smear shows heamocytes of 0.015g Carbofuran/ 24 hours

1. GRC shows clustering with ruptured cell membrane
2. Ruptured cell membrane and distorted cell shape
3. Basidophilic with thickened granules

aggregation of several cells due to loss of their cells boundaries. Similar pathological systems were reported by using some of the insecticides (Yeager and Manson, 1942; Gupta and Sutherland, 1968; Zaidi and Khan, 1977; Azam and Ilyas, 1986; Younes, *et al.*, 1999; Haq, *et al.*, 2005; Sendi and

Salehi, 2010). Phytochemicals like plumbagin and neem induced similar changes (Sharma *et al.*, 2003). *O. rhinoceros* larvae exhibited a high cytological response to carbofuran indicating that carbofuran exerted peculiar changes in the circulatory system of insect.

Several reports were published on the impact of insecticides in altering the number and morphology of insect haemolymph. Electron microscopic studies of *Spodopteralitura* Fabricious larvae treated with neem gold and *Artemisia calamus* oil found cytoplasmic projections and rapid regeneration in granulocytes. Vacuolization in the cytoplasm and degeneration in organelles in PLCs and GRCs leading to degenerative transformation and degranulation were observed within a period of 48 hours of exposure resulting in the disintegration of immunity-building mechanism (Sharma *et al.*, 2003, 2008). In the present study similar observation could be observed in *O. rhinoceros* treated with different doses of carbofuran.

REFERENCES

- Akai H. and Sato S. (1978) Ultra structure of haemocytes of the wild silk worm, *Antheraea yamamai* (Lepidoptera: Saturniidae). Japanese Journal of Applied Zoology 22: 225-233.
- Annie Thomas (1995) Studies on haemocytes during metamorphosis in the grubs of *Oryctes rhinoceros* Linn. (Coleoptera: Scarabaeidae). Proceedings of the 7th Kerala Science Congress, Palakkad. pp 329-331.
- Ambrose D. P. and George P. J. E. (1996) Total and differential haemocytes diversity in three morphs of *Rhynocoris marginatus* (Insecta: Heteroptera: Reduviidae). Fresenius Environmental Bulletin 5: 202-206.
- Arnold J. W. (1970). Haemocytes of the pacific beetle cockroach, *Diplotera punctata*. Canadian Journal of Entomology 102: 530-535.
- Arnold, J. W. and Hinks, C. F. (1979). Insect haemocytes under light microscopy technique. In: Gupta, A. P. (ed.), Insect Haemocytes. Cambridge University Press, Cambridge.
- Azam A. F. and Ilyas M. (1986). The effects of BHC on the haemocytes of *Dysdercus cingulatus* (Pyrrhocoridae: Hemiptera). Biologia 32: 23-28.
- Crossley, A. C. S. (1964). An experimental analysis of the origins and physiology of haemocytes in the blue bottle blowfly, *Calliphora erythrocephala*. Journal of Experimental Zoology 157: 375-397.
- Gosh D. and Roy S. (1984) Foreign body induced changes in the haemocytes of eri silkworm *Philosamia ricini* (Lepidoptera). Proceedings of oriental Entomology Symposium. pp 191-194.
- Gupta A. P. (1985) Cellular elements in the haemolymph. In: Kerkut G. A. and Gilbert L. I. (eds.), Comprehensive Insect Physiology, Biochemistry and Pharmacology 30: 401-455.
- Gupta A. P. (1986) Arthropod immunocytes, identification, structure, function and analogies to the functions of vertebrate B- and T lymphocytes. In: Gupta, A. P. (ed.), Haemocytic and Humoral Immunity in Arthropods. Wiley and sons, New York. pp 3-59.
- Gupta A. P. (1991) Insect immunocytes and other haemocytes roles in cellular and hormonal immunity. In: Gupta, A. P. (ed.), Immunology of Insects and other Arthropods. Boca Raton, CRC Press. pp 19-118.
- Gupta, A. P. and Sutherland J. (1968) Invitro-transformation of the insect plasmatocyte in some insects. Journal of Insect Physiology 12: 1369-1375.
- Haq M. R., Sabri M. A. and Rashid A. (2005) Toxicity of nicotinyl insecticides on the haemocytes of red cotton bug, *Dysdercus koengii* Fb. Pyrrhocoridae: Hemiptera. Journal of Agriculture and Social Science 3: 239-241.
- HSDB (1998) Hazardous Substances Data Book. Toxicology data file on the national library of medicines, USA. <http://toxnet.nlm.nih.gov>.
- Jones J. C. (1962) Current concepts of concerning insect haemocytes. American Zoology 2: 209-246.
- Neuwirth M. (1974) Granular haemocytes, the main phagocytic blood cells in *Calpodex ethlius* (Lepidoptera: Hesperidae). Canadian Journal of Zoology 52: 783-784.
- Piegeolet E. and Corbisier P. (1990) GPX, SOD and Catalase inactivation by A.O. Mech. Age. Dev. 51:283.
- Pimentel D. (1992) Environment and human cost of pesticide use. Bioscience 42: 740-760.
- Sendi J.J and Salehi R. (2010) The effect of methoprene on total haemocyte counts and histopathology of haemocytes in *Papilio demoleus* L.

- (Lepidoptera). Munis Entomology and Zoology 5(1): 240-246.
- Shapiro M. (1979) Changes in haemocytes populations. In: Gupta A.P. (ed.) Insect Haemocytes, Development, Forms, Functions and Techniques. Cambridge University Press, Cambridge. pp 475-523.
- Vladimir Landa, Jan Sula, Frantisek Marec, Vladimir Matha and Thomas Soldan. (1991). Methods for assessing exposure of insects. In: Tardiff R.G. and Goldstein B. (ed.), Methods for Assessing Exposure of Human and Non-human Biota. (C) SCOPE. John Wiley and Sons Ltd. pp 250-265.
- Witting G. (1966) Phagocytosis by blood cells in healthy and diseased caterpillar II, a consideration of the method of making haemocyte counts. Journal of Invertebrate Pathology 8: 461-477.
- Wyatt G. R. and Pan M. L. (1978) Insect plasma proteins. Annual Review of Biochemistry 47: 779-817.
- Yeager J.F. and Manson S.C. (1942) Changes induced in the blood cells of the southern armyworm, *Prodenia eridaia* by the administration of poisons. Journal of Agricultural Research 64: 307-332.
- Younes N.W.F., Abul- Dahab F.F., Assar A.A. and Hanna M.M. (1999) Histopathological studies on the effect of some botanical extracts on the cotton leafworm, *Spodoptera littoralis* Boisd. (Lepidoptera: Noctuidae) II- effects of the integument, the midgut and fatbody. 2nd Science conference on the role of science in the development of Egyptian Society and Environment, Zagazig University, Faculty Science, Benha. pp113-129.
- Zaidi Z. S. and Khan M. A. (1977) Effects of aldrin and dipterex on the haemocytes of red cotton bug *Dysdercus cingulatus* Fabr. (Hemiptera: Pyrrhocoridae). Botyu-Kayaku. 42: 141-148.
- Zibae A. and Bandani A. R. (2010) Effects of *Artemisia annua* L. (Asteracea) on digestive enzymes profiles and cellular immune reactions of sunn pest, *Eurygaster integriceps* (Heteroptera: Scutellaridae), against *Beauveria bassiana*. Bulletin of Entomological Research 100, 185-196).



Bioefficacy of horticultural mineral oil against spider mite, *Tetranychus truncatus* Ehara (Prostigmata: Tetranychidae) on okra

Kavya Yadav*, Haseena Bhaskar* and Madhu Subramanian

Department of Agricultural Entomology, College of Horticulture, Kerala Agricultural University, Vellanikkara, 680656, Kerala, India. Email: bhaskarhaseena@yahoo.co.in; g.a.kavya@gmail.com

ABSTRACT: A field study was conducted to evaluate the efficacy of horticultural mineral oil (HMO), combination of HMO + neem oil and neem oil 2 per cent along with a synthetic acaricide, Spiromesifen 240SC and an untreated control against *Tetranychus truncatus* on okra during March, 2018. The plots treated with HMO at 2.5 (92.60%) and 3.0 per cent (93.90%) as well as combination treatments HMO 2.5 per cent + neem oil 2.0 per cent (94.14%) and HMO 3.0 per cent + neem oil 2.0 per cent (96.79%) recorded significant reduction in mite population and were superior to plots treated with either spiromesifen (91.08%) or neem oil alone at 2.0 per cent (90.42%). The high efficacy of HMO against the spider mite *T. truncatus* brought out in the study suggests that HMO can be an effective tool for mite management in vegetable crops. © 2019 Association for Advancement of Entomology

KEYWORDS: Horticultural mineral oil (HMO), neem oil, spiromesifen, *Tetranychus truncatus*

Okra is cultivated in an area of 5,11,000 hectares in India with a production of 58,49,000 metric tonnes (GOI, 2017). Among several factors responsible for the low productivity of okra, the damage inflicted by insect and mite pests has been considered important (Varadaraju, 2010). More than hundred species of insects have been reported as pests of okra (Santhoshkumar *et al.*, 2013). However, among them, only to a few insects such as leaf hopper, aphid, whitefly and shoot and fruit borer are considered as economically important. Among the mite pests, spider mites belonging to the genus *Tetranychus* have emerged as a major pest of okra causing considerable yield loss (Ghosh *et al.*, 1996; Srinivasa and Sugeetha, 1999; Kumaran *et al.*, 2007). Recent studies at Kerala Agricultural University identified *Tetranychus truncatus* Ehara

as the predominant species of mite infesting vegetable crops in Kerala, including okra (Bennur *et al.*, 2015).

The spider mites colonise undersurface of the leaves and cause significant damage by feeding on sap. This results in yellowing and speckling of leaves, webbing, premature leaf fall, stunted growth, reduction in photosynthetic activity and ultimately death of the whole plant (Damirel and Cabuk, 2008). Apart from its polyphagous nature, high reproductive potential and short life cycle, factors such as change in climatic conditions and over-use of plant protection chemicals also help to compound the mite problem. Though conventional pesticides offer good control, they have high residue levels and cause resurgence and resistance (Khajehali *et*

* Author for correspondence

al., 2011; Sharma and Bhullar, 2018). Moreover they cannot be recommended during the later stages of the crop, when mite damage typically intensifies. Consequently, biocontrol agents, botanicals and mineral oils are increasingly being evaluated against the mites.

Mineral oils have been used for centuries to control insect and mite pests on several crops (Egho and Emosairue, 2010). With recent advances in technology, refinement of petroleum oil to summer spray oils commonly called as horticultural mineral oils (HMOs) or agricultural mineral oils (AMOs) has made it possible to use them all the year round, without any risk of phytotoxicity (Davidson *et al.*, 1991; Agnello, 2002). Oils have several advantages over conventional pesticides, such as low mammalian toxicity, low residual toxicity, minimal risk of resistance development and limited effects on beneficial organism (Beattie *et al.*, 2002). Laboratory bioassay studies conducted at Kerala Agricultural University revealed that HMO at 2.0 and 2.5 per cent possess appreciable efficacy against both egg and active stages of *T. truncatus* and is relatively safer to the predatory mite, *Neoseiulus longispinosus* (Yadav and Bhaskar, 2018).

A field experiment was carried out to test the efficacy of HMO against *T. truncatus* on okra (variety Arka Anamika) at College of Horticulture, KAU, Vellanikkara during March, 2018. Two concentrations of HMO namely 2.5 and 3.0 per cent and its combinations with neem oil *viz.*, HMO 2.5 per cent + neem oil 2 per cent and HMO 3.0 per cent + neem oil 2.0 per cent were evaluated along with neem oil 2.0 per cent alone, an acaricide spiromesifen 240 SC @ 0.02 per cent and a control treatment with water spray. The crop was raised as per the Package of Practices Recommendations (KAU, 2016) at a spacing of 60×30cm in plots of 2×2m size. The experiment was laid out in Randomized Block Design with seven treatments and four replications. Mites were released on 45 days old okra plant at the rate of 25 active mites/ leaf by stapling mite infested mulberry leaf bit of 3cm² size each on top, middle and bottom leaf of

okra plant. Treatments were imposed two weeks after the release of mites using a hand sprayer.

The number of mites from three windows of 1cm² each from top, middle and bottom leaves of randomly selected five plants per replication were recorded. The mite count was recorded *in situ* by using a hand lens of 10X magnification one day before spraying and 1, 3, 7, 10 and 14 days after spraying. Data on mean population of mites were transformed using square root transformation. Population difference on one, three, seven, ten and fourteen days after treatment were tested by one way ANOVA. The mean per cent reduction in population of mites over pre count was also worked on seven and fourteen days after treatment application.

The results of the field experiment to evaluate the efficacy of different treatments against *T. truncatus* are presented in Table 1. The mean population of *T. truncatus* before the application of treatments ranged from 17.73 to 18.59 per cm² leaf area. One day after spraying, all the treatments significantly reduced the population of mite as compared to untreated control. The mean mite population ranged from 4.85 to 18.51 per cm² leaf area. The lowest mean mite count of 4.85/cm² leaf area was recorded by HMO 3.0 per cent + neem oil 2.0 per cent followed by HMO 2.5 per cent + neem oil 2.0 per cent (5.15/cm² leaf area) which were on par with each other. HMO 2.5 and 3.0 per cent recorded 5.46 and 5.33 mites/cm² leaf area respectively and were on par with each other and also with HMO 2.5 + neem oil 2.0 per cent, HMO 3.0 + neem oil 2.0 per cent and neem oil 2 per cent (5.43 mites/ cm² leaf area). The acaricide spiromesifen 240 SC recorded mite count of 5.88 mites/ cm² leaf area which was on par with HMO 2.5 per cent, HMO 3.0 per cent and neem oil 2.0 per cent.

Three days after spraying, the plants treated with combination of HMO + neem oil harboured significantly lower mite population compared to other treatments. HMO 3.0 per cent + neem oil 2.0 per cent and HMO 2.5 per cent + neem oil 2.0 per cent recorded 1.59 and 1.43 mean mite per cm²

leaf area respectively. This was followed by HMO 2.5 per cent (2.49/cm² leaf area) and HMO 3.0 per cent (2.31 mites/cm² leaf area) which were on par with each other and the above treatments. The acaricide, spiromesifen 240 SC recorded 2.87 mites/cm² leaf area and was on par with neem oil 2 per cent (3.10 mites/cm² leaf area) and with HMO 2.5 and 3.0 per cent.

At seven days after treatment, all the treatments significantly reduced the mite population as compared to untreated control (15.53 mites/cm² leaf area). The lowest mite population of 1.04 per cm² leaf area was recorded by HMO 2.5 per cent + neem oil 2.0 per cent followed by HMO 3.0 per cent (1.08/cm² leaf area), HMO 3.0 per cent + neem oil 2.0 per cent (1.11/cm² leaf area) and HMO 2.5 per cent (1.33/cm² leaf area). However, these treatments did not differ significantly. Spiromesifen 240 SC (1.82/cm² leaf area) and neem oil 2.0 per cent (2.32 mites /cm² leaf area) were on par with each other and differed significantly from treatments of HMO and combination of HMO + neem oil.

Per cent reduction in mite count after seven days of treatment application was worked out. By seventh day of treatment, HMO 2.5 per cent + neem oil 2.0 per cent recorded 96.21 per cent reduction in the mite count closely followed by HMO 3.0 per cent + neem oil 2.0 per cent (93.95%), HMO 3.0 per cent (93.90%) and HMO 2.5 per cent (92.60%). This was followed by treatments *viz.*, spiromesifen 240 SC (89.99 %) and neem oil 2.0 per cent (87.26 %).

Similar trend was observed on ten days after spraying where treatments of HMO and combination of HMO + neem oil continued to record lower mean mite counts. The treatments, HMO 2.5 per cent (0.70/cm² leaf area), HMO 3.0 per cent (0.73/cm² leaf area), HMO 2.5 per cent + neem oil 2.0 per cent (0.79/cm² leaf area) and HMO 3.0 per cent + neem oil 2.0 per cent (0.87/cm² leaf area) recorded mean mite count on par with each other which was significantly lower. Spiromesifen 240 SC and neem oil 2.0 per cent recorded mean mite counts of 1.57 and 2.04 per cm² leaf area

respectively which were on par with each other, but significantly differed from treatments of HMO and combination of HMO + neem oil.

At fourteen days of spraying, all the treatments recorded significant reduction in mite population as compared to untreated control (12.86 / cm² leaf area). HMO 2.5 per cent recorded lowest mean mite count of 0.54 per cm² leaf area, followed by HMO 3.0 per cent (0.58/cm² leaf area), HMO 3.0 per cent + neem oil 2.0 per cent (0.59 /cm² leaf area) and HMO 2.5 per cent + neem oil 2.0 per cent (0.67/cm² leaf area) which were all on par with each other and significantly superior over Spiromesifen and neem oil. Mite population count in Spiromesifen 240 SC (1.62/ cm² leaf area) and neem oil 2.0 per cent (1.74/ cm² leaf area) were on par with each other.

Per cent reduction in mite count after fourteen days of treatment application was worked out. By fourteenth day, the highest reduction in mite population over untreated control was observed in HMO 2.5 per cent (96.99%) followed by, HMO 3.0 per cent + neem oil 2.0 per cent (96.79%), HMO 3.0 per cent (96.72%) and HMO 2.5 per cent + neem oil 2.0 per cent (96.21%), Spiromesifen 240 SC (91.08 %) and neem oil 2 per cent (90.42 %).

In the field experiment, HMO alone (2.5 and 3.0%) and in combination with neem oil (2.0%) were significantly superior to both the acaricide Spiromesifen and neem oil. Spiromesifen, an inhibitor of lipid biosynthesis, is highly toxic to eggs and immature stages of spider mites, while it acts more slowly against adult females, causing reduction in fertility and fecundity (Marcic *et al.*, 2011). Krishna and Bhaskar (2013) reported a higher reduction in egg count (15.40%) of *T. urticae* due to Spiromesifen, while it recorded very low adult mortality (3.40%). Similarly, Sato *et al.* (2011) studied the toxicity of Spiromesifen to different developmental stages, and found egg stage of *T. urticae* was most sensitive. But laboratory bioassay had revealed that HMO possess very high efficacy against both egg and adult of *T. truncatus* and recorded 100 per cent mortality of eggs at concentrations of 1.5, 2.0, 2.5 and 3.0 per cent

Table 1. Efficacy of Horticultural Mineral Oil (HMO) against *Tetranychus truncatus* on okra

Treatments	Mean no. of mite/cm ² leaf area				Per cent reduction on 7 DAT	Mean no. of mite/cm ² leaf area		Per cent reduction on 14 DAT
	Pre count	1 DAT	3 DAT	7 DAT		10 DAT	14 DAT	
T ₁ - HMO 2.5%	17.98 (4.24)	5.46 ^{bc} (2.33)	2.49 ^{bc} (1.56)	1.33 ^c (1.15)	92.60	0.70 ^c (0.83)	0.54 ^c (1.01)	96.99
T ₂ - HMO 3.0%	17.73 (4.21)	5.33 ^{bc} (2.31)	2.31 ^{bc} (1.49)	1.08 ^c (1.04)	93.90	0.73 ^c (0.84)	0.58 ^c (1.03)	96.72
T ₃ - HMO 2.5% + neem oil 2.0%	17.76 (4.21)	5.15 ^c (2.27)	1.59 ^c (1.22)	1.04 ^c (1.02)	94.14	0.79 ^c (0.88)	0.67 ^c (1.08)	96.21
T ₄ - HMO 3.0% + neem oil 2.0%	18.36 (4.28)	4.85 ^c (2.20)	1.43 ^c (1.16)	1.11 ^c (1.05)	93.95	0.87 ^c (0.93)	0.59 ^c (1.04)	96.79
T ₅ - Neem oil 2.0%	18.21 (4.26)	5.43 ^{bc} (2.33)	3.10 ^b (1.75)	2.32 ^b (1.51)	87.26	2.04 ^b (1.43)	1.74 ^b (1.49)	90.42
T ₆ - Spiromesifen 240SC - 0.02%	18.19 (4.26)	5.88 ^b (2.42)	2.87 ^b (1.66)	1.82 ^b (1.34)	89.99	1.57 ^b (1.24)	1.62 ^b (1.45)	91.08
T ₇ - Control	18.59 (4.31)	18.51 ^a (4.29)	17.91 ^a (4.23)	15.53 ^a (3.94)	16.46	12.35 ^a (3.51)	12.86 ^a (3.65)	30.83
CD value (p=0.05)	NS	0.15	0.43	0.18	0.34	0.21	0.26	0.65

DAT = Days after treatment. Means followed by same letter in the column do not differ significantly. Figures in the parentheses are square root transformed values.

(Yadav and Bhaskar, 2018). High efficacy of HMO against both egg and active stages of spider mite might have resulted in significant reduction in the mite count on treated okra plants compared to Spiromesifen, which possess relatively lower efficacy against adult mite. However, field evaluation of HMO at 1.0 and 2.0 per cent concentration against *T. urticae* on brinjal had shown HMO to significantly reduce mite infestation on par with Spiromesifen (Kavya *et al.*, 2015). In the present study, HMO was evaluated at higher concentrations of 2.0 and 2.5 per cent. This could be another reason for higher efficacy of HMO over the acaricide, Spiromesifen.

In the study, HMO showed greater persistence in field as indicated by progressive reduction in mite count up to 14 days of treatment application. In addition to its high efficacy against spider mites, HMO was also found to be safe to the predominant

mite predator, *Neoseiulus longispinosus* (Yadav and Bhaskar, 2018). These attributes auger well for HMO to be a safer alternative to synthetic acaricides for mite pest management in vegetable crops.

REFERENCES

- Beattie G. A. C., Watson D. M., Stevens M. L., Rae D. J., and Spooner-Hart R. N. (2002) Spray Oils Beyond 2000. University of Western Sydney, Sydney, 623 pp.
- Bennur S., Abida P. S., Vasala P. A., Mathew D. and Bhaskar H. (2015) DNA barcoding of spider mites (Prostigmata: Tetranychidae) in vegetables using *COI* and *ITS2* markers. *Genome* 58(1): 195.
- Damirel N and Cabuk K. (2008) Population trends of two-spotted spider mite, *Tetranychus urticae* Koch (Acari: Tetranychidae) on cotton nearby soil asphalt road. *Journal of Entomology* 5 (2): 122-127.

- Davidson N. A., Dibble J. E., Flint M. L., Marer P. J. and Guye A. (1991) Managing Insects and Mites with Spray Oils. University of California, Berkeley, 45 pp.
- Egho E. O. and Emosairue S. O. (2010) Field evaluation of mineral oils for insect pests management and yield of cowpea (*Vigna unguiculata*) (L) Walp in Abraka, Southern Nigeria. Archives of Applied Science and Research 2(4): 57-67.
- Ghosh J., Mukherjee A. B. and Sarkar P. K. (1996) Assessment of loss of bhendi against red spider mite. Environmental Ecology 14: 480-481.
- GOI (2017) Government of India. Horticultural Statistics at a Glance 2017 [on-line]. Available: <http://www.agricoop.nic.in/pdf/chapter07.pdf> [15 June 2018].
- KAU (2016) Package of Practices Recommendations: crops (15th Ed.). Kerala Agricultural University, Thrissur, Kerala. 391pp.
- Kavya M.K., Srinivasa N.A., Vidyashree S., and Ravi G.B. (2015) Bioefficacy of newer acaricides against two spotted spider mite, *Tetranychus urticae* and phytoseiid predator, *Neoseiulus longispinosus* on brinjal under field condition. Plant Archives 15(1): 493-497.
- Khajehali J., Nieuwenhouse P.V., Demaghat P., Tirry L. and Leeuwen T.V. (2011) Acaricide resistance and resistance mechanism in rose green houses in Netherlands. Pest Management Science 67: 1424-1433.
- Krishna R. A. and Bhaskar H. (2013) Ovicidal and adulticidal effect of acaropathogenic fungi, neem oil and new acaricides molecules *Tetranychus urticae* Koch. Entomon 38 (3): 177-182.
- Kumaran N., Douressamy S., Ramaraju K. and Kuttalam K. (2007) Estimation of damage and yield loss due to *Tetranychus urticae* Koch (Acari: Tetranychidae) on okra under artificial infestation. Journal of Acarology 17(1&2): 4-6.
- Marcic D., Peric P. and Milenkovic S. (2011) Pesticides - Formulations, Effects and Fate. Tech Publisher, Europe. 62p.
- Santoshkumar C., Kedar, Kumaranag K. M. and Nitin T. (2013) Integrated pest management of 12 important pests of okra. *Krishisewa*. [e-journal]. Available: <http://www.krishisewa.com/articles/disease-management/233-okra-ipm.html>. [06 June 2018].
- Sato M. E., Da Silva M. Z., Raga A., Cangani K. G., Veronez B. and Nicastro R. L. (2011) Spiromesifen toxicity to the spider mite *Tetranychus urticae* and selectivity to the predator *Neoseiulus californicus*. Phytoparasitica 39: 437-445.
- Sharma R. K. and Bhullar M. B. (2018) Status of acaricide resistance in field collected two-spotted spider mite, *Tetranychus urticae* Koch from vegetable growing areas of Punjab, India. Journal of Entomological and Zoological Studies 6(1): 328-332.
- Srinivasa N. and Sugeetha G. (1999) Bioeffectiveness of certain botanicals and synthetic pesticides against okra spider mite *Tetranychus macfarlanei*. Journal of Acarology 15(1&2): 1-5.
- Varadaraju, M. V. 2010. Seasonal incidence and management of okra mites, *Tetranychus* spp. MSc (Ag) thesis, University of Agricultural Sciences, Dharwad, Karnataka. 79p.
- Yadav K. and Bhaskar H. (2018) Effect of horticultural mineral oil on *Tetranychus truncatus* Ehara (Prostigmata: Tetranychidae) and its predator *Neoseiulus longispinosus* (Evans) (Mesostigmata: Phytoseiidae). 1st International Conference on Biological Control Approaches and Applications, September 27-29, 2018. Bengaluru, India, 131p



First report of *Aeolesthes holosericea* (Fabricius, 1787) (Cerambycidae: Lamiinae) from Goa, India

Parshuram S. Naik and S. V. More*

Department of Zoology, ADKS College, Dodamarg, 416512, Sindhudurg, Maharashtra, India;

Email: sadamore6046@gmail.com; parshuramnaik1996@gmail.com

ABSTRACT: *Aeolesthes holosericea* is reported for the first time for Goa with its dorsal, ventral and lateral photographic views and current geographical distribution.

© 2019 Association for Advancement of Entomology

KEY WORDS: *Aeolesthes*, Goa

Aeolesthes holosericea is commonly known as apple stem borer or cherry stem borer (Tara *et al.*, 2008). It was reported as polyphagous pest which damage wide variety of trees and fruit plants (Gupta and Tara, 2013). There are eight host plant of this species reported by (Stebbing, 1914) and it was also reported from thirty seven host plant species by (Beeson, 1941). The genus *Aeolesthes* is composed of 6 species from Indian subcontinent (Tara *et al.*, 2008) of them no previous record of this genus from Goa. There are 1536 current species of longhorn beetles known for India (Kariyanna *et al.*, 2017). On the basis of its external characters, the species *A. holosericea* is confirmed on the original description by (Gahan, 1906) and also it was confirmed by Dr. Hemant Ghate, PG research center, Modern College Pune. The present communication gives additional geographical location of this species in India.

***Aeolesthes holosericea* (Fabricius, 1787) (image 1)**

Ceramryx holosericeus Fabricius, 1787: 135 (m. s.); Fabricius, 1801: 281; Zimsen, 1964: 166 (Syn.).

Specimens examined: One male, 11.iii.2019, Sal-Punarvasan Goa (latitude 15.687381 N and 73.962045 E), Coll. S. V. More, damaged species, collected from light pole, host plant-unknown.

Adult (male): Body length: 31mm; width: about 7 to 8mm. Antennae longer than body (65mm in length), antennomere five to eight with spine at apex, segment first to five partially dark brown and remaining antennomeres brownish, first antennomere dorsally wrinkled and thickened, second antennomere short, segment third smooth, segment first to four gradually thickened at apex, segment four and five about equal length, apical segment much longer than others (16mm in length). Head with a straight, dark brown to reddish brown, covered with brownish fine hairs, front view of head or on the frons region slightly covered with wrinkled, eyes divided into upper and lower lobes, upper eye lobes widely separated. Prothorax dark brownish, rounded at each side, with irregularly wrinkled on dorsal side, central portion smooth, pronotum covered with very fine silky pubescence at lateral side. Scutellum slightly whitish, tongue like, elytra with bands or patches, duller to brighter (19mm in

* Author for correspondence




Image 1. *Aeolesthes holosericea*. A-dorsal view; B- full dorsal view of head and thorax; C- fore tibia with spine; D-full dorsal view of thorax and elytra; E-front view of head; F-full details of abdomen; G-lateral view details

length), each elytra with pointed spine at apex of elytra suture other one blunt spine its opposite side. Legs thinner, covered with greyish pubescence, protibia, mesotibia and metatibia with spine at apex, first tarsal segment of mid and hind legs longer than others, claws brownish, widely separated. Gula dark brown in colour, prosternum brownish, the mesoventrite, metanepisternum, metaventrite and discrien covered with brownish to whittish pubescence, abdomen ventrite one to five covered whitish pubescence, apical abdomen ventrite covered with fine brownish hairs, more on tip, ventrite first occupied large space as compared to others.

Distribution: Pakistan, Indonesia, Vietnam, Laos, Malaysia, Myanmar, China, Srilanka, Thailand and India (Tamil Nadu, Maharashtra, Andhra Pradesh, Arunachal Pradesh, Karnataka, Madhya Pradesh Andaman and Nicobar Island, Assam, Rajasthan, Punjab, Nagaland and Jammu Kashmir).

ACKNOWLEDGEMENTS

We are grateful to Dr. Hemant Ghate, Post graduate Research Centre, Modern College of Arts, Science and Commerce College, Shivajinagar, Pune, for identification. We thank the authorities of respective Colleges for the facilities and encouragement.

REFERENCES

- Beeson C.F.C. (1941) The ecology and control of the forest insects of India and the neighboring countries (1961 reprinted edition). New Delhi, Govt. of India.
- Gahan C.J. (1906) Fauna of British India including Ceylon and Burma. Coleoptera Vol. I. Taylor and Francis, London, (Cerambycidae), Taylor and Francis, London, UK.
- Gupta R and Tara J.S. (2013) First record on the biology of *Aeolesthes holosericea* Fabricius, 1787 (Coleoptera: Cerambycidae), an important pest on apple plantations (*Malus domestica* Borkh.) in India. Munis Entomology and Zoology 8 (1): 243-251.
- Kariyanna B., Mohan M., Gupta R and Vitali F. (2017) The checklist of longhorn beetles (Coleoptera: Cerambycidae) from India. Zootaxa 4345 (1): 1–317.
- Stebbing E.P. (1914) Indian Forest Insects of Economic Importance: Coleoptera. Eyre and Spottiswoode Ltd., London, UK.
- Tara J.S., Gupta R and Chhetry M. (2008) A study on *Aeolesthes holosericea* Fabricius, an important pest of apple plantations (*Malus domestica* Borkh.) in Jammu region. The Asian Journal of Animal Science 3 (2): 222-224.



First report of incidence of eriophyid mite *Aceria* sp. on *Amaranthus*

K. M. Sreekumar*, **N. Srinivasa¹** and **R. Sivamoorthy**

Kerala Agricultural University, College of Agriculture, Padnekkad, Kasaragod, Kerala, India;

¹AINP (Agricultural Acarology) at UAS, Bengaluru, Karnataka, India.

Email: sreekumar.km@kau.in

ABSTRACT: Eriophyid mite *Aceria* sp. damaging *Amaranthus* (*Amaranthus tricolor*) is reported from India for the first time. The mite cause severe malformation of the shoot, making it fibrous and reducing the yield. Foliar application of spiromesifen or fenpyroximate reduced the damage symptoms. DNA data for the mitochondrial COI gene and nuclear gene (ITS 2 region) are being generated for accurate species delineation. © 2019 Association for Advancement of Entomology

KEY WORDS: *Aceria* sp, damage symptoms, *Amaranthus*

Amaranth (*Amaranthus tricolor*) is a common leafy vegetable cultivated all over the country and its major growing season in Kasaragod district of Kerala is summer after the cessation of North East monsoon. Extensive cultivation of leaf amaranth is a common practice by farmers in the coastal area of Kanhangad in Kasaragod district. The crop sown during October is continued up to second week of June when the fields are usually submerged due to continuous rains. Shoots of amaranth are harvested every 10 days during this nine-month crop period. The marketability of the produce is good since crop is red in colour and farmers used to get a remunerative price. But from the last three years, growers of Padannakad area close to the Agricultural college campus are experiencing the problem of eriophyid mite infestation in the crop. February onwards mite affected plants show crinkling, deformity and malformation of tender leaves, severe reduction in leaf size and stunting (Plate 1). As the affected shoots become more



Plate 1. Crinkling & malformation of *Amaranthus* shoot

* Author for correspondence




Plate. 2. stereomicroscopic view of *Aceria* sp

fibrous, causes difficulty in harvesting. Such damage symptoms get extended rapidly and by April month most of the plants in the field show the symptoms and the crop appears sickly because of stunted growth. Upon stereozoom microscopic examination of the affected shoot, eriophyid mites were noticed in good numbers. During May 2019, on an average as many as twenty mites were recorded in 5 cm length of tender shoot with the mite number ranging from 8 - 28. Because of severe stunting, the number of periodical tender shoot harvests from April to June was found reduced to almost 50 per cent. Since there was severe crinkling, malformation and fibrous nature of the shoots, marketability was severely affected, fetching the growers a very low price. Altogether

there was more than fifty per cent reduction in the revenue as surveyed from 10 to 15 farmers in the affected area. An observational trial to contain the pest with foliar application of spiromesifen (@100g ai/ha) or fenpyroximate (@30g ai/ha) immediately after an harvest, reduced the mite damage symptoms almost completely for a period of at least 15 days when the new shoots would be ready for the next harvest (POP of KAU, 2016).

Eriophyid mites collected from the infested shoots were identified by the AINP (Agricultural Acarology) at UAS, Bengaluru as *Aceria* sp (plate 2). Of course, it is the first report of eriophyid mite on amaranth *Amaranthus tricolor* in India. *Aceria amaranthi* recorded on *Amaranthus* sp. from Tanzania in 1992 has been reported in great numbers (70 to 200 per gall) causing numerous galls on both the surfaces of young and matured leaves with all the developmental stages within the same gall. But the presently recorded *Aceria* sp. do not cause galls on leaves or shoots. Also taxonomically important the pattern of median, admedian and submedian lines on the dorsal shield are distinct for these two species under the common genus *Aceria*. Supportingly, DNA data of *Aceria* sp. for both mitochondrial COI gene and nuclear gene (ITS2 region) are being generated for more accurate species delineation.

It is worth undertaking detail studies on symptom or damage, ecological and economic aspects of this eriophyid mite infestation on the important vegetable crop *Amaranthus*.

REFERENCE

- POP of KAU (2016) Package of Practices Recommends crops Kerala Agricultural University, Vellanikkara, Thrissur, Kerala, India



First report of *Rinamba opacicollis* Cameron (Hymenoptera: Braconidae, Doryctinae) in India as parasitoid of coffee stem borer, *Xylotrechus quadripes* (Chevrolat) (Coleoptera: Cerambycidae)

A. Roobakkumar^{*1}, H.G. Seetharama¹, P. Krishna Reddy¹, M.S. Uma¹ and A. P. Ranjith²

¹Entomology Division, Central Coffee Research Institute, CRS Post-577 117, Chikkamagaluru Dist, Karnataka, India; ²Insect Ecology and Ethology laboratory, University of Calicut, Kerala, India.

Email: roobakkumar@gmail.com

ABSTRACT: *Rinamba opacicollis* Cameron (Hymenoptera: Braconidae) was collected from Chikkamagaluru, Karnataka, India for the first time from the larvae of white stem borer, *Xylotrechus quadripes* Chevrolat infesting arabica coffee. Its role in the biological or integrated control of *X. quadripes* remains to be evaluated. White stem borer could be the first host record of this parasitoid all over the world. © 2019 Association for Advancement of Entomology

KEY WORDS: Ectolarval parasitoid, *Rinamba opacicollis*, *Xylotrechus quadripes*

The coffee white stem borer (CWSB), *Xylotrechus quadripes* (Coleoptera: Cerambycidae) is a major and economically important pest of arabica coffee in India. This pest was first noticed in India during 1838 (Stokes 1838) and its distribution is confined to only Asian countries ((i.e. Burma, China, India, Java, Nepal, Sri Lanka, Thailand and Vietnam) and has not been reported in other coffee growing countries (Le Pelly, 1968). The adult beetles are active in bright sunshine hours and female lays eggs in the cracks and crevices under the loose scaly bark of the main stem and thick primaries. The infestation starts with the feeding of early instar larvae on the outer surface and then gradually entering inside the main stem. Extensive feeding leads to the formation of tunnels inside the stem

interrupting the nutrient supply and thereby leading to substantial reduction in the yield (Seetharama *et al.*, 2005). The annual loss due to the CWSB in India is about \$17.5-26 million (Venkatesha *et al.*, 2012). Severe infestation leads to yellowing of leaves, defoliation and subsequent death of the plant. The Coffee White Stem Borer has two peak flight periods, summer flight during April - May and winter flight during October to December. The winter flight is very crucial, as all the adult beetles tend to emerge during this period (Seetharama *et al.*, 2005). The concealed feeding habit of this pest necessitates timely implementation of IPM practices to manage the pest under the economic threshold level. Cultural practices like maintenance of optimum shade, tracing and uprooting of the infested plants before


* Author for correspondence

the flight period (March and September) and the judicious use of chemical pesticide, Chlorpyrifos @ 3ml/l (First fortnight of April and October) are the recommended IPM practices for the CWSB.

Nevertheless, use of bio-control strategies for management of CWSB has not been very successful. Though, some parasitoids were earlier identified on CWSB, they could not be included in the IPM because of their low potential against CWSB and failure in the establishment in field (Prakasan *et al.*, 1986; Shylesha *et al.*, 1992; Veeresh, 1993; Venkatesha *et al.*, 1997; Seetharama *et al.*, 2008). Hence, efforts have been continued, to identify potential natural enemies against CWSB. In order to achieve potential biological control programs, severely CWSB infested coffee plants were collected before the emergence period (March 2017) from Central Coffee Research Institute (CCRI) farm, Chikkamagaluru Dist, Karnataka, India and stored in isolated closed room and regularly monitored for the emergence of natural enemies, if any. During the routine observations on the stored stems, we found the emergence of parasitoids in large numbers. These insects were collected using aspirator and observed under laboratory for confirmation. Further, the infested plants were split opened and found that some of the CWSB larvae were found parasitized. The parasitized larvae were taken to laboratory and reared till emergence of adults. Both the insects which emerged from cut stems in the storeroom and the parasitized CWSB larvae were found to be similar. The adults of these parasitoids were sent to Insect Ecology and Ethology laboratory, University of Calicut, for taxonomic identification and identified as *Rinamba opacicollis* Cameron (Hymenoptera: Braconidae, Doryctinae) by Ranjith. The same specimens were submitted to the Insect depository of National Bureau of Agriculturally Important Insects (NBAIR), Bengaluru, India to maintain as type specimen (NBAIR/HYM-BRAC/23819). Based on the literature, this is the first report of this parasitoid in India and even from Oriental region. More interestingly, this could be the first host record for the genus. Braconidae is one of the largest families within the Hymenoptera, which act as

parasitoids on some immature stages of holo and hemimetabolous insects. Braconids include some important parasitoids that develop endoparasitically in the host body though majority of the species in Braconidae are ectoparasitoids on late instars of host larvae. *Rinamba*- one small genus with less than ten species described. The synonyms for *Rinamba* are *Pseudorhoptrocentrus* Granger, 1949 (synonymized by Belokobylskij in 2004) and *Rhoptrocentroides* Marsh 1993 (synonymized by Belokobylskij in 1995 with *Pseudorhoptrocentrus*). This is distributed in Afrotropical, Neotropical and Oceanic regions. The genus *Rinamba* belongs to the tribe Doryctini including approximately 35 Palearctic genera (Belokobylskij *et al.*, 2004). This is a moderately large subfamily of the family Braconidae with more than 1000 described species worldwide. Most of the known doryctine species are idiobiont gregarious ectoparasitoids of the larvae of xylophagous or bark-boring Coleoptera, while some species live on Lepidoptera or Hymenoptera-Symphyta (sawfly) larvae (Loni *et al.*, 2005).

The adult parasitoids collected from the CWSB infested stored stems were maintained on 10% honey solution in the laboratory. Various methods were tried to standardize the mass rearing techniques for this parasitoid using the CWSB larvae. The adult parasitoids along with the CWSB infested stems were placed inside cages for two days. Adults were found active and hovering around the feeding WSB larvae inside the cut stems exhibiting good searching ability by means of cues. *Rinamba opacicollis* found to be a gregarious ectoparasitoid as female individual deposit eggs on CWSB larvae through its long ovipositor. The spot of oviposition was marked, and the egg laying was confirmed by splitting of the stem. In another method which was originally used for rearing the Braconid, *Parallorhogas pallidiceps* by Balakrishnan and Anishkumar (2008), a microscopic slide was glued on cardboard (5 mm thickness) and the other side of the cardboard was covered with muslin cloth. Arabica stem powder was sparsely sprinkled over the muslin cloth to elicit adults towards the slide-cardboard. A small slit (2.5 cm × 0.5 cm) was made on the cardboard and a late instar larva of CWSB was placed inside the



Adult female




Eggs laid on WSB larva



Parasitoid - Larvae



Parasitoid - Pupa



Parasitized larva of WSB

slit and covered with cotton plug. Oviposition was observed in the larva present inside the muslin cloth. Long and slender eggs were laid in groups and hatched larvae were found to feed externally on the WSB larva. The female parasitoid was larger in size (1 to 1.3 cm) compared to male (0.3 to 0.4 cm). The life cycle of the parasitoid was studied on WSB larvae using the slide technique. The development period of egg, larvae and pupa were recorded as 6.14 ± 0.89 (5-7), 11.14 ± 1.86 (9-14) and 27.14 ± 3.6 (24-31) days, respectively. The study revealed that the time taken for completion of the life cycle ranged from 38 to 44 days.

Description of *Rinamba opacicollis* Cameron

Body length 6.84 mm, fore wing 4.96 mm, ovipositor 8.84 mm. Antenna short with 32 segments. Face convex in lateral view, rugose-reticulate, setose. Eyes glabrous with crenulated margin. Torular region raised. Clypeus strongly sculptured with distinct ventral carina. Tentorial pit deep. Lateral temple transversely striate. Frons longitudinally striate with a deep pit medio-basally. Ocellar area sculptured. Vertex smooth, sparsely setose.

Occipital carina crenulate. Maxillary palp with five segments. Labial palp with three segments. Propleuron transversely striated. Mesosoma moderately dorso-ventrally flattened. Median lobe of mesoscutum with strong medial longitudinal groove. Mesoscutum smooth, sparsely setose with lateral carina. Notauli crenulate anteriorly, meeting posteriorly. Scutellar sulcus divided by six carinae. Scutellum smooth, sparsely setose. Median area of metanotum with pits anteriorly, smooth medio-posteriorly. Propodeum rugose-reticulate with median longitudinal and lateral carinae anterior half, posteriorly with two anteriorly diverging carinae and with a pair of deep smooth pits sub medially. Mesopleuron smooth medially and anteriorly rest transversely striate. Sternaulus deeply impressed, crenulate, running along almost entire length of mesopleuron. Metapleuron smooth mid anteriorly, sparsely setose, rest transversely rugose striate. Fore wing 3.9× longer than maximum width. Pterostigma 3.9× longer than maximum width. Fore wing vein r arising before mid level of pterostigma. Second submarginal cell narrowing apically. Vein cu-a postfurcal. Fore femur robust. Mid and hind

femora transversely striate dorsally. Metasoma 1.0× longer than mesosoma and head combined. First metasomal tergite rugose reticulate, smooth medio-basally with moderately angulate corners basally and with apically converging pair of strong longitudinal carinae and small smooth medio-posterior area. Ovipositor with dorsal nodus and ventral serrations.

Considering the spontaneous occurrence of *R. opacicollis* in coffee white stem borer infested areas and its efficiency in parasitizing the CWSB larvae inside the stem, systematic studies to assess and exploit the potential of this parasitoid against *X. quadripes* are being pursued.

ACKNOWLEDGEMENTS

The authors are grateful to Dr. Y. Raghuramulu, Director of Research (Retd) and Dr. N. Surya Prakash Rao Joint Director, Central Coffee Research Institute for his constant encouragement, support and revision of the manuscript. The authors are thankful to the Insect Ecology and Ethology laboratory, University of Calicut, for taxonomic identification of the specimen.

REFERENCES

- Balakrishnan M.M. and Anishkumar P.K. (2008) Integrated stem borer management in smallholder coffee farms in India, Malawi and Zimbabwe. CFC ICO Final technical report. Pp 309.
- Belokobylskij S.A. (2004) New genus and new subgenus of subfamily Doryctinae (Hymenoptera: Braconidae) from the old world fauna. *Annales de la Société Entomologique de France* 40: 199–204.
- Belokobylskij S.A., Iqbal M. and Austin A.D. (2004) Systematics, distribution and diversity of the Australian doryctine wasps (Hymenoptera, Braconidae, Doryctinae). *Records of the South Australian Museum Monograph Series* 8: 1–150.
- Belokobylski, S.A. (1995) Main evolutionary transformations of morphological structures in the subfamilies Doryctinae and Exothecinae (Hymenoptera, Braconidae). *Entomologicheskoe Obozrenie* 74(1): 153–176.
- Le Pelley R.H. (1968) *Pests of Coffee*. Longmans, Green and Co. Ltd, London. 590pp.
- Loni A., Jucker C., Belokobylskij S. and Lupi D. (2015) First record of *Rhoptrocentrus piceus* Marshall (Hymenoptera, Braconidae, Doryctinae) as parasitoid of *Psacotha hilaris hilaris* (Pascoe) (Coleoptera, Cerambycidae). *ZooKeys* 482: 1–8.
- Prakasan C.B., Sreedharan K. and Bhat P.K. (1986). New record of a parasite of coffee white stem-borer *Xylotrechus quadripes* Chev. from India. *Journal of Coffee Research* 16: 38–40.
- Seetharama H.G., Kumar P. K.V., Sreedharan K. and Vasudev V. (2008) Field release of *Apenesia sahyadrica* against coffee white stem borer. *Journal of Coffee Research* 36: 57–59.
- Seetharama H.G., Vasudev V., Vinod Kumar P. K. and Sreedharan K. (2005) Biology of coffee white stem borer *Xylotrechus quadripes* Chev. (Coleoptera: Cerambycidae). *Journal of Coffee Research*, 33: 98–107.
- Shylesha A.N., Veeresh G.K. and Siddegowda D.K. (1992) New record of egg parasite and survey of natural enemies complex of white stem borer of coffee *Xylotrechus quadripes* Chev. (Cerambycidae: Coleoptera). *Journal of Plantation Crops* 20: 138–139.
- Stokes H. (1838) Report of the Commissioner, Mysore
- Veeresh G.K., Shylesha A. N. and Siddegowda D.K. (1995) Ecobiology studies on *Allorhogas pallidiceps* (Perkins) (Braconidae: Hymenoptera). A larval parasite of CWSB, *Xylotrechus quadripes* Chev. *Journal of Plantation Crops*. 20: 123–126.
- Venkatesha M.G., Seetharama H.G and Sreedharan K. (1997) *Iphiaulax* sp. A new Braconid parasitoid of coffee white stem borer, *Xylotrechus quadripes* (Chevr.) (Coleoptera: Cerambycidae). *Pest Management in Horticultural Ecosystems* 3: 112–113.
- Venkatesha M.G. and Dinesha, A.S. (2012) The coffee stem borer, *Xylotrechus quadripes* (Coleoptera: Cerambycidae): bio ecology, status and management. *International Journal of Tropical Insect Science* 32: 177–188.



Scorpion Hemocyte- Plasmocyte

U. H. Shah*

Department of Zoology, Balwant College, Vita 415 31, Maharashtra. Affiliated to Shivaji University, Kolhapur, Maharashtra. Email: uhs7460@gmail.com

ABSTRACT: The plasmocytes in five different scorpions- *Mesobuthus tumulus tumulus*, *M. tumulus concanesis*, *Orthochirus bicolor*, *Heterometrus xanthopus*, *H. phipsoni* were studied in the present investigation. The hemocytes are polymorphic and their population is about 70 – 80%. The length varied from 6- 12 μ m and the width is 6- 12 μ m in *M. tumulus tumulus*, *M. tumulus concanesis* and *O. bicolor*. In *H. xanthopus* and *H. phipsoni* the length ranged between 10- 35 μ m and width between 3- 11 μ m. The cytological characteristics were studied in all five species of scorpions. The nucleus is basophilic and placed at the centre. The cytological detail of plasmocyte in *H. xanthopus* of was studied by TEM. It is polymorphic with rod shaped mitochondria and centrally placed nucleus.

© 2019 Association for Advancement of Entomology


KEY WORDS: *Mesobuthus tumulus tumulus*, *M. tumulus concanesis*, *Orthochirus bicolor*, *Heterometrus xanthopus*, *H. phipsoni* cytological characteristics, TEM

Arthropoda is the largest phylum on the earth, inhabiting in air, water and on land. The study of hemocytes is the most fascinating area of research. Kollmann (1908) first reported the morphology and types of hemocytes- the blood cells, in arthropoda. Just like vertebrate blood cells, the hemocytes play important role in immune system, coagulation of hemolymph after rupture of cuticle, in wound healing etc (Millar and Ratcliff, 1989). The hemocytes are embryologically derived from intermediate mesoderm (Anderson, 1972). The morphology and nomenclature of hemocytes in different arthropods is confusing and varied. Jones (1962) and Price and Ratcliffe (1974), presented a new nomenclature system applicable for all arthropods. Though there is disagreement about the types of hemocytes, ultra structurally seven types of hemocytes are identified as- Prohemocytes (PRs), Plasmocytes (PLs), Granulocyte (GRs), Spherulocytes (SPs),

Adipohemocytes (ADs), Oenocytes (OEs) and Coagulocytes (COs) in almost all arthropods. A perusal of literature indicates that some groups of arthropoda have received detailed attention about study of hemocytes, are- insects, crustaceans and myriopods. Though some work was done on arachnids, scorpions – the living fossil, the oldest group in arthropods remain neglected. Ravindernath (1974) did a pioneer work about hemocytes of *Palamnaeus swammerdami*. In the present investigation the morphology of plasmocytes were studied in five different species of scorpion- *Mesobuthus tumulus tumulus*, *Mesobuthus tumulus concanesis*, *Orthochirus bicolor*, *Heterometrus xanthopus* and *Heterometrus phipsoni*.

During this investigation five different species of scorpions were collected from different localities

* Author for correspondence



from Maharashtra (India). *H. xanthopus*, *H. phipsoni* were collected from their natural burrows while *M. tumulus tamulus*, *M. tumulus concanensis*, *O. bicolor* were collected underneath the stones. The males and females were placed in separate perforated jars with hibiscus leaves and soil from its natural habitat. These were fed with cockroaches (Shah and Patil, 2011).

For collection of hemolymph the method employed as described by Padmanabha (1967) with some modifications. It is collected by aspiration through hypodermic needle inserted through arthroidal membrane of pedipalps. For morphological study Pappenheim'spanochrome, Giemsa stain and Leishman's stains were employed. Janus Green B was used to observe mitochondria while Sudan

Table 1. Plasmocyte Characteristics in Different Species of Scorpions

Sr. No.	Species of scorpion	Shape variation		Size variation (µm)		Nucleus-cytoplasmic ratio	Position of nucleus	Nature of staining reaction	
		cell	nucleus	cell	nucleus			cytoplasmic inclusion	nucleus
1	<i>Mesobuthus tumulus tamulus</i> ,	P	R	7- 21♂ 4-11♀	3-5	35-45	C	AG	B
2	<i>Mesobuthus tumulus concanesis</i>	P	R	6- 18♂ 4-18♀	3-4	25-30	C	AG	B
3	<i>Orthochirusbicolor</i>	P	R	9- 20♂ 3-12♀	3-5	35-60	C	SG	B
4	<i>Heterometrusxanthopus</i>	P	O	10- 30♂ 3-10♀	4-10	40-50	C	SG	B
5	<i>Heterometrusphipsoni</i> .	P	E	11- 32♂ 4-11♀	4-10	45-50	C	SG	B

B- Basophilic C- Centric E- Elliptical O- Oval P- Polymorphic R- Round
AG- Agranular SG- Slightly Granular

Black B and PAS were used for cytochemistry. These techniques include light microscopy, phase contrast microscopy and transmission electronic microscopy (TEM). The quantitative methods include Total Hemocyte Count (THC) and Differential Hemocyte Count (DHC).

The morphological study was done in different five species of scorpion in both male and female. All morphological features of scorpion are similar to that of insect with slight differences. In this investigation Jones system of classification was followed.

In all five species of scorpion clearly differentiated seven types of hemocytes were observed- Prohemocytes (PRs), Plasmocytes (PLs), granulocytes (GRs), Spherulocytes (SPs), Adipohemocytes (ADs), Oenocytoids (ODs), and Coagulocytes (COs).

Plasmocyte is the unique type of hemocyte in scorpion due to its polymorphic nature. It is fusiform in *M. tamulus tamulus*, elongated in *M. tumulus concanesis*, irregular in *O. bicolor* and spindle shaped in *H. xanthopus* and in *H. phipsoni*. However these shapes are not characteristics of the species. During preparation of hemolymph smear PLs adhere the glass slide to produce broad cytoplasmic extensions. Due to this it was very difficult to measure the dimensions of the cell. This was overcome by using 2% versene fixative. In *M. tumulus tamulus*, *M. tumulus concanesis* and *O. bicolor* the length and width is 6- 12 µm. In *H. xanthopus* and in *H. phipsoni* the length ranged from 10- 35 µm while the width was 3- 11 µm (Table 1). The cytoplasm was agranular in *M. tamulus concanesis* and granular in *H. xanthopus*, *O. bicolor* and *H. phipsoni*. The granules are Sudan Black B positive indicating lipid material in it. The nucleus is centrally placed and measured about 3-

10 µm in diameter. It is round in *M. tumulus tamulus*, *M. tamulus concanesis*, and *O. bicolor*. It is oval in *H. xanthopus* and elliptical in *H. phipsoni* (Plate I).

The values PLs was 72% in *M. tumulus tamulus*, 65% in *M. tamulus concanesis*, 75% in *O. bicolor*, 82% in *H. xanthopus* and 79% in *H. phipsoni* as compare to that of other types of hemocytes.

Examination of scorpion hemocytes with TME was particularly useful in distinguishing the PLs from other hemocytes. In *H. xanthopus*, the plasma membrane of PLs clearly showed cytoplasmic projections. TEM photography also showed pinocytic vesicles indicating phagocytic nature of it.

The selection of proper technique becomes important since several methods are available for the study of arthropod hemocytes. During the course of this investigation, it was noticed that any one technique was not suitable for all hemocytes; therefore certain modifications were made with combination of some methods. In all five species the PLs represents bulk of hemocyte population. A common feature of PLs is presence of vacuoles which was not reported in all five species of scorpions. In fixed preparation PLs showed stiff spike like projections (plate I).

As described by Gupta (1985a), PLs are having large nucleo-cytoplasmic ratio, which is considered as the stem cell nature of the hemocytes (Srivastava and Richards, 1965) which gives rise to other types of hemocytes. In the present investigation the PLs of all species having common features to that of GRs. The granules in PLs are small and refractile as compare to PLs as described by Kollaman (1908).

The large number of population and presence of stiff projections might be because of its phagocytic

activity. The functional importance of the different hemocytes is still not clearly defined; hence there is ample scope to study scorpion hemocytes.

REFERENCES

- Anderson D. T. (1972) The development of Hemimetabolous Insects. In: Developmental system: Insects, Counce, S. J. and Waddington, C. H. (Ed.), Academic Press, London, New York. pp. 95-163.
- Gupta A. P. (1985) Cellular elements in hemolymph. In: A. P. Gupta (Ed.) Comprehensive Insect Physiology, biochemistry and Pharmacology. Pergamon Press, Oxford. Vol. 3. pp 402- 444.
- Jones J. C. (1962). Current concepts concerning insect hemocytes- Review. American Zoologist 2: 209-246.
- Kollmann M. (1908) Recherch essur les leucocytes et le tissue lymphoide des invertebres. Annales des sciences naturelles, Zoologie 9:1- 238.
- Millar D. A. and Ratcliff N. A. (1989) The evolution of blood cells: Facts and enigmas. Endeavor 13: 72-77.
- Padmanabha N. B. (1967) Perfusion fluid for the scorpion, *Heteromatus fulvipes*. Nature 213(74): 410.
- Price C. D. and Ratcliffe N. A. (1974) A reappraisal of insect haemocyte classification by the examination of blood from fifteen insect orders. Cell and tissue research 147(4): 537-549.
- Ravindranath M. H. (1974) The hemocytes of scorpion *Palamnaeus swammerdami*. Journal of Morphology 144: 1- 10. <https://doi.org/10.1002/jmor.1051440102>
- Shah U. H. and Patil A. E. (2011) The hemocytes types, differential and total counts in *Mesobuthus tumulus concanesis*. Geobios 38(2-3): 141-144.
- Srivastava S. C. and Richards A. G. (1965) An autobiographic study of relationship between hemocytes and connective tissue in the wax moth *Galleria mellonella*. Biological Bulletin (Wood Hole) 128: 337- 345.

Contents of Volume 44

No. 1

- Distribution and habitat characteristics of the Troidine butterfly community in the Western Ghats, a biodiversity hotspot in India
Mary Anto, George Mathew and Roby T. Jose 01
- Monitoring global public health threat - surveillance of *Aedes (Stegomyia)* mosquitoes in new Mangalore sea port, India
R. Rajendran, K. Regu and J.M. Kurian 15
- Current distribution of Nilgiri grass yellow *Eurema nilgiriensis* Yata (Lepidoptera: Pieridae), with an updated taxonomic key to *Eurema* of Western Ghats, India
Sujitha P. C., Prasad G., Nitin R., Dipendra Nath Basu, Krushnamegh Kunte and Kalesh Sadasivan 23
- A new subgenus and three new species of stingless bees (Hymenoptera: Apidae: Apinae: Meliponini) from India
S. Shanas and P. Faseeh 33
- Franklinothrips vespiformis* Crawford (Thysanoptera: Aeolothripidae), a potential predator of the tea thrips, *Scirtothrips bispinosus* Bagnall in south Indian tea plantations
P. Mahendran and B. Radhakrishnan 49
- Performance of sorghum genotypes under zero tillage conditions in rice fallows with reference to stem borer, *Chilo partellus* (Swinhoe)
P. Yogeswari, C. Sandhya Rani and G. Ramachandra Rao 57
- Study on varietal preferences and seasonal incidence of parasitoids of rice pests
J. Alfred Daniel, K. Ramaraju, S. Mohan Kumar, P. Jeyaprakash and N. Chitra 65

Study on adult emergence, female calling and mating behaviour in <i>Maruca vitrata</i> F. (Lepidoptera: Crambidae) in Kerala, India S. Eureka, K.M. Sreekumar, K. Subaharan, B. Ramesha and T. Santhoshkumar	73
---	----

SHORT COMMUNICATION

<i>Dialeurodes pongamiae</i> - A new species of whitefly (Hemiptera: Aleyrodidae) from India R. Sundararaj and D. Vimala	79
First report of <i>Macrochenus guerinii</i> (White 1858) (Cerambycidae: Lamiinae) from Maharashtra, India S. V. More and M. S. Prashant	81

No. 2

Studies on polymorphism of enzyme systems in populations of <i>Apis florea</i> F. (Hymenoptera: Apidae) from Chandigarh and foothills of Himachal Pradesh, North West India Rajeev Kumar, Jaspreet Kaur and Neelima R Kumar	83
Screening of rice accessions and newer molecules against lepidopterous pests in Manipur, India Mukta Das, I. Yimjenjang Longkumer and K.I Singh	95
Life table and economic threshold concept for ecologically sustainable management of <i>Diacrisia casignetum</i> Kollar (Lepidoptera: Arctiidae) on jute Nayan Roy	103
Description of a new species of <i>Callocleonymus Masi</i> (Hymenoptera: Chalcidoidea: Pteromalidae) from India Ankita Gupta, Namitha George and P. M. Sureshan	111
Phytochemical screening for identification of bioactive compounds of <i>Lantana camara</i> Linn. (Verbenaceae) responsible for larvicidal action against <i>Aedes triseriatus</i> Say, 1823 (Diptera : Culicidae) Rhitayu Chakraborti and Probir Kumar Bandyopadhyay	117

- Negative cross resistance of *Spodoptera litura* Fabricius population of tomato to newer molecule spinetoram
M. Visnupriya and N. Muthukrishnan 127

SHORT COMMUNICATION

- Description of a new species of Lathromeris Foerster
(Hymenoptera: Trichogrammatidae) from India
Mohd. Yousuf, Mohsin Ikram and Neha Rajwar 133

- Eco-friendly management of leaf eating caterpillar
Noorda blitealis Walker in moringa
D. Kamaraj and S. Manisegaran 137

- Effect of coriander *Coriandrum sativum* L. on parasitization
behaviour of *Trichogramma chilonis* Ishii (Trichogrammatidae:
Hymenoptera) in brinjal ecosystem
P. Dominic Manoj and G. Ravi 143

- Invasion and establishment of Bondar's nesting whitefly, *Paraleyrodes
bondari* Peracchi (Hemiptera: Aleyrodidae) in Indian mainland and
Andaman and Nicobar Islands
*C.V. Vidya, R. Sundararaj, A.K. Dubey, Haseena Bhaskar,
Mani Chellappan and M.K. Henna* 149

- First record of body colour polymorphism in giant African snail
Achatina fulica (Bowdich, 1822) - a comparative study using
mitochondrial cytochrome oxidase subunit I (COI) gene
Keerthy Vijayan, R. Sugantha Sakthivel and T.V. Sajeev 155

No. 3

- Bioecology of the tea thrips, *Scirtothrips bispinosus* Bagnall
(Thysanoptera: Thripidae) infesting tea in south India
P. Mahendran and B. Radhakrishnan 161

- Comparative studies of mymarid diversity from three different zones
of paddy ecosystem in Tamil Nadu, India
J. Alfred Daniel, K. Ramaraju and A. Rameshkumar 173

<p>Volatile metabolites of <i>Lecanicillium saksenae</i> (Kushwaha) Kurihara and Sukarno and their toxicity to brinjal mealybug <i>Coccidohystrix insolita</i> (G) <i>P. Sreeja and O. P. Reji Rani</i></p>	183
<p>A new genus and a new species of Tropidopolinae (Orthoptera: Acrididae) from India <i>Mohd. Imran Khan and Mohd. Kamil Usmani</i></p>	191
<p>Biochemical changes in <i>Holotrichia repetita</i> Sharp (Coleoptera: Melolonthidae) and <i>Galleria mellonella</i> L. (Lepidoptera: Pyralidae) due to the biopesticide <i>Steinernema</i> sp. <i>N. Santhana bharathi, A. Deepa, P. Chithra,</i> <i>A. Aasha and K. Sujatha</i></p>	197
<p>Efficacy and biosafety of new generation insecticides for the management of <i>Leucinodes orbonalis</i> Guenee (Lepidoptera: Pyralidae) in brinjal and <i>Earias vitella</i> Fabricius (Lepidoptera: Noctuidae) in okra <i>V. Vijayasree and Hebsy Bai</i></p>	203
<p>Detection of dengue virus in <i>Aedes</i> mosquitoes in Delhi, India <i>Suresh Chand Kaushik, Sukhvir Singh,</i> <i>Purnima Srivastava and R. Rajendran</i></p>	213
<p>Evaluation of entomopathogenic fungi against <i>Raoiella indica</i> Hirst (Acari: Prostigmata: Tenuipalpidae) <i>Indhusri Chavan, S. Pradeep, S. Sridhara</i> <i>and K.N. Ashrith</i></p>	219
<p>SHORT COMMUNICATION</p>	
<p>Report of <i>Celosterna scabrator</i> (Fabricius, 1781) (Coleoptera: Cerambycidae: Lamiinae) from Goa, India <i>S. V. More and M. S. Prashanth</i></p>	225
<p>Biology of eri silkworm, <i>Samia ricini</i> (Donovan) on castor, <i>Ricinus communis</i> L. <i>Vaishali V. Birari, M. R. Siddhapara and Divya H. Patel</i></p>	229

Gender associated morphological differences in <i>Corcyra cephalonica</i> (Stainton) (Lepidoptera: Pyralidae)	
<i>K. C. Sowjanya, K. Murali Mohan and M. Thippaiah</i>	235

Identification of a species of deer fly attacking human and live stocks in Assam, India	
<i>Dipankar Biswas, Dibya Ranjan Bhattacharyya Kaushal Yadav, Pranjali jyoti Baruah and Biswa jyoti Borkakoty</i>	237

No. 4

Taxonomic studies on the genus <i>Glyphodes</i> Guenee (Lepidoptera: Crambidae: Spilomelinae) from Karnataka, India	
<i>P. Maheswara Reddy and M. Shankara Murthy</i>	241

Influence of spinosad on the reproductive potential of <i>Tribolium castaneum</i> (Herbst), (Coleoptera: Tenebrionidae) infesting wheat	
<i>Umme Habiba, Wahedul Islam and Selina Parween</i>	249

Relative abundance and foraging activity of hymenopteran pollinators in cucurbitaceous vegetables	
<i>Erra Harisha and S. Shanas</i>	259

On a new species of <i>Neoceratobaeus</i> Rajmohana (Hymenoptera: Scelionidae) from India	
<i>P. Sunita and K. Rajmohana</i>	269

Occurrence of multiple nest entrance in the stingless bee <i>Tetragonula travancorica</i> (Hymenoptera: Meliponini)	
<i>P. Faseeh and S. Shanas</i>	275

SHORT COMMUNICATION

Influence of wind direction on parasitization behaviour of <i>Trichogramma chilonis</i> Ishii (Hymenoptera: Trichogrammatidae) in brinjal ecosystem	
<i>P. Dominic Manoj, G. Ravi and M.I. Manivannan</i>	283

Evaluation of pongamia oil soap against leaf hopper, <i>Amrasca biguttula biguttula</i> (Ishida) infesting okra <i>Anu Thomas and K. M. Sreekumar</i>	287
Effect of carbofuran on quantitative and qualitative alterations in haemolymph of larva of <i>Oryctes rhinoceros</i> L. (Coleoptera: Scarabaeidae) <i>V.S. Salini</i>	293
Bioefficacy of horticultural mineral oil against spider mite, <i>Tetranychus truncatus</i> Ehara (Prostigmata: Tetranychidae) on okra <i>Kavya Yadav, Haseena Bhaskar and Madhu Subramanian</i>	301
First report of <i>Aeolesthes holosericea</i> (Fabricius, 1787) (Cerambycidae: Lamiinae) from Goa, India <i>Parshuram S. Naik and S. V. More</i>	307
First report of incidence of eriophyid mite <i>Aceria</i> sp. on <i>Amaranthus</i> <i>K. M. Sreekumar, N. Srinivasa and R. Sivamoorthy</i>	309
First report of <i>Rinamba opacicollis</i> Cameron (Hymenoptera: Braconidae, Doryctinae) in India as parasitoid of coffee stem borer, <i>Xylotrechus quadripes</i> (Chevrolat) (Coleoptera: Cerambycidae) <i>A. Roobakkumar, H.G. Seetharama, P. Krishna Reddy, M.S. Uma and A. P. Ranjith</i>	311
Scorpion Hemocyte- Plasmocyte <i>U. H. Shah</i>	315

AUTHOR INDEX

- Aasha A., 197
Alfred Daniel J., 65, 173
Ankita Gupta, 111
Anu Thomas, 287
Ashrith K.N., 219
Biswa jyoti Borkakoty, 237
Chithra P., 197
Chitra N., 65
Deepa A., 197
Dibya Ranjan Bhattacharyya, 237
Dipankar Biswas, 237
Dipendra Nath Basu, 23
Divya H. Patel, 229
Dominic Manoj P., 143, 283
Dubey A.K., 149
Erra Harisha, 259
Eurekha S., 73
Faseeh P., 33, 275
George Mathew, 01
Haseena Bhaskar, 149, 301
Hebsy Bai, 203
Henna M.K., 149
Indhusri Chavan, 219
Jaspreet Kaur, 83
Jeyaprakash P., 65
Kalesh Sadasivan, 23
Kamaraj D., 137
Kaushal Yadav, 237
Kavya Yadav, 301
Keerthy Vijayan, 155
Krishna Reddy P., 311
Krushnamegh Kunte, 23
Kurian J.M., 15
Madhu Subramanian, 301
Mahendran P., 49, 161
Maheswara Reddy P., 241
Mani Chellappan, 149
Manisegaran S., 137
Manivannan M.I., 283
Mary Anto, 01
Mohan Kumar S., 65
Mohd. Imran Khan, 191
Mohd. Kamil Usmani, 191
Mohd. Yousuf, 133
Mohsin Ikram, 133
More S. V., 81, 225, 307
Mukta Das, 95
Murali Mohan K., 235
Muthukrishnan N., 127
Namitha George, 111
Nayan Roy, 103
Neelima R Kumar, 83
Neha Rajwar, 133
Nitin R., 23
Parshuram S. Naik, 307
Pradeep S., 219
Pranjal jyoti Baruah, 237
Prasad G., 23
Prashant M. S., 81
Prashanth M. S., 225
Probir Kumar Bandyopadhyay, 117
Purnima Srivastava, 213
Radhakrishnan B., 49, 161
Rajeev Kumar, 83
Rajendran R., 15, 213
Rajmohana K., 269

Ramachandra Rao G., 57
Ramaraju K., 65, 173
Ramesha B., 73
Rameshkumar A., 173
Ranjith A. P., 311
Ravi G., 143, 283
Regu K., 15
Reji Rani O. P., 183
Rhitayu Chakraborti, 117
Roby T. Jose, 01
Roobakkumar A., 311
Sajeev T.V., 155
Salini V.S., 293
Sandhya Rani C., 57
Santhana bharathi N.
Santhoshkumar T., 73
Seetharama H.G., 311
Selina Parween, 249
Shah U. H., 315
Shanas S., 33, 259, 275
Shankara Murthy M. 241
Siddhapara, 229
Singh K.I, 95
Sivamoorthy R., 309
Sowjanya K. C., 235

Sreeja P., 183
Sreekumar K. M., 73, 287, 309
Sridhara S., 219
Srinivasa N., 309
Subaharan K., 73
Sugantha Sakthivel R., 155
Sujatha K., 197
Sujitha P. C., 23
Sukhvir Singh, 213
Sundararaj R., 79, 149
Sunita P., 269
Suresh Chand Kaushik, 213
Sureshan P. M., 111
Thippaiah M., 235
Uma M.S., 311
Umme Habiba, 249
Vaishali V. Birari, 229
Vidya C.V., 149
Vijayasree V., 203
Vimala D., 79
Visnupriya M., 127
Wahedul Islam, 249
Yimjenjang Longkumer I., 95
Yogeswari P., 57

ACKNOWLEDGEMENTS

The EDITORIAL BOARD of ENTOMON profoundly express profound and sincere thanks to the following experts/ researchers/ scientists in peer reviewing the manuscripts and for their constructive comments and suggestions on the articles published in the ENTOMON volume 44, issues 1 to 4.

Anil Kumar Dubey, Zoological Survey of India, Andaman and Nicobar Region Centre,
Port Blair, Andaman & Nicobar Islands, India

Anil Kumar Sethy, Institute of Wood Science & Technology, institutes of Indian Council of
Forestry Research & Education (ICFRE), Bangaluru, Karnataka, India

Avtar Kaur Sidhu, High Altitude Regional Centre, Zoological Survey of India, Saproon,
Solan, Himachal Pradesh, India

Balakrishnan, N., National Centre for Disease Control - Plague Surveillance Unit, Bengaluru,
Bengaluru, India

Daniel, B.A., Zoo Outreach Organisation /IUCN SSC South Asian Invertebrate Specialist
Group, ZEN, Coimbatore, Tamil Nadu, India

Devasahayam, S., ICAR - Indian Institute of Spices Research, Calicut, Kerala, India

Evans, D. A., University college, University of Kerala, Thiruvananthapuram, Kerala, India

Gayathri Elayidam, U., VTM NSS Zoology, Dhanuvachapuram, Kerala, India

Haseena Bhaskar, AINP on Agricultural Acarology, Department of Agricultural Entomology,
College of Horticulture, Kerala Agricultural University, Vellanikkara, Thrissur,
Kerala, India

Hebsi Bhai, Kerala Agricultural University, Thiruvananthapuram, Kerala, India

Hemant V. Ghate, Department of Zoology, Modern College, Shivajinagar, Pune, India

Ian J. Kitching, Natural History Museum, Cromwell Road, London, U.K

Jorge Ari Noriega, Department of Biogeography and Global change, Madrid, Spain

Josephraj Kumar, A., ICAR-Central Plantation Crops Research Institute, Regional Station,
Kayamkulam, Kerala, India

Kolla Sreedevi, ICAR-Indian Agricultural Research Institute, New Delhi, India

Luc Willemsse, Afdelingshoofd Collectie Entomologie & Geologie, Entomological & Geological
Collections, Naturalis Biodiversity Center, Leiden, Nederland

Mallik, B., University of Agricultural Sciences, Bengaluru, Karnataka, India

Mani Chellappan, Department of Agricultural Entomology, College of Horticulture, Kerala
Agricultural University, Vellanikkara, Thrissur, Kerala, India

Mohd Yousuf, Tropical Forest Research Institute, Jabalpur, Madhya Pradesh, India

Nasser, M., Department of Zoology, University of Calicut, Kerala, India

Natarajan, N., Department of Agricultural Entomology, Tamil Nadu Agricultural University, Tamil Nadu, India

Pandey, J.P., Silkworm Physiology Laboratory, Central Tasar Research & Training Institute (Central Silk Board), Ranchi, Jharkhand, India

Panicker, K.N., Amrita Institute of Medical Sciences, Kochi, Kerala, India

Rajmohana, K., ENVIS Centre on Faunal Diversity, Zoological Survey of India, Kolkata, West Bengal, India

Raman Velayudhan, Vector Ecology and Management Unit, Department of Control of Neglected Tropical Diseases (CDS/NTD), World Health Organization, Geneva, Switzerland

Raman, A., Charles Sturt University & Graham Centre for Agricultural Innovation, Orange, NSW, Australia

Ramaraju, K., Tamil Nadu Agricultural University, Coimbatore, Tamil Nadu, India

Ramesha, B., College of Agriculture, Kerala Agricultural University, Padannakkad, Kasaragod, Kerala, India

Ravi Kumar, G., Seri-Biotech Research Laboratory, Central Silk Board, Kodathi, Carmelram, Bangaluru, Karnataka, India

Sabu K Thomas, St. Joseph's College, Devagiri, Kozhikode, Kerala, India

Samiran Chakrabarti, Former Emeritus Fellow (UGC), University of Kalyani, Kolkata, West Bengal, India

Selvanarayanan, V., Department of Entomology, Faculty of Agriculture, Annamalai University, Chithambaram, Tamil Nadu, India

Sigfrid Ingrisch, Zoologisches Forschungsmuseum Alexander Koenig, - Leibniz-Institut für Biodiversität der Tiere - Adenauerallee, Bonn, Germany

Sreekumar, K.M., College of Agriculture, Kerala Agricultural University, Padnekkad, Nileswaram, Kasaragod, Kerala, India

Subramanian, K.A., Southern Regional Centre, Zoological Survey of India, Chennai

Sudhir Singh, Systematic Laboratory, Forest Entomology Division, Forest Research Institute, Dehradun, Uttarakhand, India

Sureshan, P.M., Western Ghat Field Research Centre Zoological Survey of India, Eranhipalam, Kozhikode, Kerala, India

Vasantharaj David, B., International Institute of Biotechnology & Toxicology, Padappai, Kancheepuram district, Tamil Nadu

Viraktamath, C.A., University of Agricultural Sciences, Bengaluru, Karnataka, India

INFORMATION TO CONTRIBUTORS

ENTOMON (Print ISSN: 0377-9335) is the official publication of the Association for Advancement of Entomology (AAE), a non-governmental organization of Entomologists in India and abroad, since 1975. It publishes original research articles in Entomology and related branches of science. Outstanding articles, invited papers projecting novel ideas/ technology beneficial to the members of the AAE also may be considered for publication.

Announcements of seminars/ symposia, book reviews and other items of entomological interest will also be considered for publication.

Research papers - 'Full papers' are to be covered in 4-10 printed pages and 'Short Communications' 1 - 3 pages.

The articles should be organized in the format seen in the latest issue of ENTOMON. Full papers consist of Title, Authors' name/s and address, Abstract, Key words, Introduction, Material and methods, Results, Discussion, Acknowledgements, and References. Short Communication should be presented in the same format as in full papers, but without subheadings.

Publication policy: Submission of a manuscript to ENTOMON implies that the content has neither been published earlier nor will be sent to any other publisher without intimation to ENTOMON.

Entomon is committed to maintaining publication ethical standards. On allegations of misconduct, the Editorial Boards is empowered to take appropriate action, including retraction of published articles, according to the Committee on Publication Ethics (COPE) guidelines.

At least one of the authors should be a member of AAE.

A fee will be charged for each black and white printed page (invoice will be sent along with the proof) for publication of the articles in ENTOMON. If illustrations are desired in colour in the print, the actual cost of colour plate has to be borne by the author.

A free PDF offprint of each article will be supplied to the author identified for correspondence.

Manuscript submission: All manuscripts should be submitted by e-mail and all correspondence will be through e-mail *editor.entomon@kau.in*.

All manuscripts, after a preliminary scrutiny by the editorial team, will be subjected to peer-review by at least two referees who are experts in the area of the submitted paper. ENTOMON aims to process the articles within five months of receipt. Publication will be based on priority with effect from the date of acceptance. Papers adjudged demanding immediate attention of beneficiaries will be *fast-tracked* for publication.

Soft copy of each manuscript should be e mailed to *editor.entomon@kau.in* and if hard copies to be delivered please send to "the Chief Editor, ENTOMON, Department of Entomology, College of Agriculture, Kerala Agricultural University, Vellayani, Trivandrum 695522, Kerala, India.

Manuscript preparation: Manuscripts prepared on the basis of following guide lines will facilitate early publication in ENTOMON.

Manuscripts should be typed double space having 3.5 cm margin on the left and 2.5 cm margin on the right. The first page should contain the title, author/s' name/s, affiliation and email address. When the number of authors are more than one, indicate the name and e mail of the author for correspondence with an asterisk mark and specify "author for correspondence" in a foot note. The second page should contain the abstract, followed by key words and a running title. From page 3 onwards type the text continuously from Introduction to References. Place the Tables and Illustrations on separate sheets at the end of the manuscript. The pages are to be numbered serially.

Title should be brief, informative and in sentence case.

Address of each author should be given in italics. E mail address and mobile number of the author identified for correspondence should be provided.

Abstract should be concise, accurate and informative. It should be complete in itself but limited to 250 words.

Key words should be 4 – 6, indicators of the work, helpful in indexing the article.

Introduction should include specific aim of the research work undertaken, a review of literature leading to the identification of gaps in knowledge. It should justify the work carried out avoiding elementary details and repetition of well known facts.

Materials and method should be concise but provide enough detail to permit proper interpretation of the results as well as to allow repetition by others. Technical description of method is needed only when the method is new. If the method followed has been already described elsewhere, just give the reference. If any alteration is made, describe the alteration along with reason.

Results should be presented in clear and concise form. Data must be analysed adopting suitable statistical methods. Tables should be numbered consecutively in arabic numeral and should be self explanatory. Repetition of the data should be avoided in the text but for highlighting specific findings. Do not include graphs duplicating the data presented in the tables. Material appropriate for discussion should not be included in results.

Illustrations should be of good quality. Photographs and diagrams should be organized into plates and numbered serially. The illustrations in each plate should be numbered consecutively as Fig. 1, Fig. 2 etc., without distinction between drawings, graphs and photographs, with proper labeling. Legend for the figures should be provided in separate sheet.

All illustrations must be referred to at the appropriate places in the text. Illustrations should be submitted in TIFF format at the following resolutions: line art, 1200 dpi; grey scale, 800 dpi; and colour halftone, 600 dpi. Figures should be sized to fit 24 cm x 18cm.

Discussion and interpretation of the data should be with reference to the objectives of the experiment. Relate the results to previous studies and discuss their implications. Compare and contrast your findings with known details and highlight if any. Project the new contributions in the paper and stress the importance and relevance of the study. Suggest plausible ways of exploring answers for the new questions arising from results. Discussion should also point out limitations of the study, if any.

Acknowledgement of financial grants, technical assistance, identification of specimens and supply of essential literature may be included.

Citations in the text should be formatted as follows: Nair (1990) or (Nair, 1990), Bhasin and Roonwal, 1954 or (Bhasin and Roonwal, 1954) or Bhasin and Roonwal (1954) and Nair *et al.*, 2004 or Nair *et al.* (2004). Groups of references, with in parentheses, should be cited in chronological order.

References should be formatted according to the style of ENTOMON, as given below.

Reference cited should be listed in alphabetical order.

Examples of citations under references:

Articles in journals:

Author A. (year) Title of the article. Name of the journal in full (not in italics), Volume number (issue number): page numbers.

Author A., Author B. and Author C. (year) Title of the paper. Name of the journal in full, Volume number (issue number): x – y.

Author A., Author B., Author C and Author D. (year) Title of the paper. Name of the journal in full, Volume number (issue number): x – y.

Book chapters:

Author A. (year) Title of the chapter. In: *Name of the book* Vol. number (Eds. Editor A. Editor B. and Editor C.), Name of the publisher, City, pp x – y.

Books:

Author A. (year) Title of the book. Name of the publisher, City, xyz pp.

Conference proceedings:

Author (year) Title of the article. In: Proceedings of xxxxx. Place of the conference, dates month, year, publisher, pp x – y.

Internet resources:

Author (2013) Title. Name of the publisher, City. Available from: <http://xxxxxx/> (Accessed on 24 March, 2014).

Please note that page ranges are connected by n-dash (the length of an ‘n’) and not by hyphen (-). Use of a tool such as *Latex* for reference management and formatting is recommended.

Papers must strictly conform to the requirements of the latest version of the **International Code of Zoological Nomenclature**.

Deposition of **voucher specimens**, in public depositories, in case of new reports, to facilitate verification by others is strongly suggested.

Proof of the article will be sent to the author for correspondence by e-mail as PDF file for proof correction, and will be asked to return corrected proof with in three days by e mail.

Disclaimer: The information and opinions presented in the articles of ENTOMON reflect the views of the author/s and not of the Journal or its Editorial Board or the publisher. Publication articles/ short communications do not give any endorsement by the JOURNAL.

Statement of ownership and other particulars of ENTOMON

(Form IV, Rule 8 of Registration of Newspapers (Central) Rules 1956)

1. Place of publication : Trivandrum
2. Periodicity of publication : Quarterly
3. Printer's name, nationality and address : Dr K D Prathapan, Indian, Secretary,
Association for Advancement of Entomology,
Department of Entomology, College of Agriculture,
Kerala Agricultural University, Vellayani PO,
Thiruvananthapuram 695522, Kerala, India
4. Publisher's name, nationality and address : - do-
5. Editor's name, nationality and address : Dr M S Palaniswami, Indian,
Chief Editor, ENTOMON,
Association for Advancement of Entomology,
Department of Entomology, College of Agriculture,
Kerala Agricultural University, Vellayani PO,
Thiruvananthapuram 695522, Kerala, India
6. Name and address of the
Individual who owns the paper : Association for Advancement of Entomology,
Department of Entomology, College of Agriculture,
Kerala Agricultural University, Vellayani PO,
Thiruvananthapuram 695522, Kerala, India

I, Dr K. D. Prathapan, Secretary, Association for Advancement of Entomology, here by declare that the particulars given above are true to the best of my knowledge and belief.

Sd/-

Vellayani PO, Thiruvananthapuram 695522

Dr K. D. Prathapan

31 December 2019

Publisher, ENTOMON



Association for Advancement of Entomology

(Reg. No. 146/ 1975)

*Department of Entomology, Kerala Agricultural University,
Vellayani PO, Thiruvananthapuram 695522, Kerala, India. E mail: aae@kau.in
web:www.entomon.in*

EXECUTIVE COMMITTEE (2017 – 2019)

President: Prof. N. Mohandas, Former HOD (Entomology) & Research Coordinator,
Kerala Agricultural University, Thiruvananthapuram

Vice Presidents:

1. Prof. A. Visalakshi, Former HOD, Dept. of Entomology, Kerala Agricultural University, Thiruvananthapuram
2. Professor & HOD, Dept. of Entomology, Kerala Agricultural University, Vellayani, Thiruvananthapuram
3. Dr. R. Rajendran, Deputy Director, NCDC, Cherthala

Secretary: Dr. K. D. Prathapan, Dept. of Entomology, Kerala Agricultural University,
Vellayani, Thiruvananthapuram

Joint Secretaries:

1. Dr. Hebsi Bai, Former Profesor, Dept. of Entomology, Kerala Agricultural University, Vellayani, Thiruvananthapuram
2. Dr. D. A. Evans, Reader, University College, University of Kerala, Thiruvananthapuram
3. Dr. C. A. Jayaprakas, HOD, Crop Protection, ICAR-CTCRI, Thiruvananthapuram

Treasurer: Dr. O. P. Reji Rani, Dept. of Entomology, Kerala Agricultural University,
Vellayani, Thiruvananthapuram

Members:

1. Prof. G. Madhavan Nair, Former HOD, Dept. of Entomology, Kerala Agricultural University, Thiruvananthapuram
2. Prof. S. Devanesan, Former Dean, Kerala Agricultural University, Vellayani, Thiruvananthapuram
3. Dr. S. Naseema Beevi, Former Professor, Dept. of Entomology, Kerala Agricultural University, Thiruvananthapuram
4. Prof. Thomas Biju Mathew, Dept. of Entomology, Kerala Agricultural University, Vellayani, Thiruvananthapuram
5. Dr Joseph Rajkumar, Principal Scientist, Division of Crop Protection, ICAR-CPCRI, Kayamkulam
6. Prof. P. A. Rajan Asari, Former Professor, Dept. of Entomology, Kerala Agricultural University, Thiruvananthapuram
7. Dr. E. Pushpalatha, Reader, Calicut University, Kozhikode
8. Prof. K. Sudharma, HOD, Dept. of Entomology, Kerala Agricultural University, Vellayani, Thiruvananthapuram
9. Dr Ambili Paul, Dept. of Entomology, Kerala Agricultural University, Vellayani, Thiruvananthapuram
10. Dr E. R. Harish, Division of Crop Protection, ICAR-CTCRI, Thiruvananthapuram
11. The Chief Editor, ENTOMON, Ex officio - member
12. Dr Mary Teresa Miranda, Fatima Mata National College, Kollam
13. Dr S. Shanas, Dept. of Entomology, Kerala Agricultural University, Vellayani, Thiruvananthapuram



Published by :

Association for Advancement of Entomology
Department of Entomology, Kerala Agricultural University
Vellayani P.O, Thiruvananthapuram 695522, Kerala, India
Email : aae@kau.in; web: www.entomon.in